



Googong Township Pink-tailed Worm-lizard Protection and Management Plan

Prepared for Googong Township Pty Ltd

Version 5 – July 2014

Biosis offices

AUSTRALIAN CAPITAL TERRITORY

Canberra

Floor 1, Unit 3, 38 Essington Street
Mitchell ACT 2911

Phone: (02) 6241 2333
Fax: (02) 6280 8752
Email: canberra@biosis.com.au

NEW SOUTH WALES

Sydney

Unit 14, 17-27 Power Avenue
Alexandria NSW 2015

Phone: (02) 9690 2777
Fax: (02) 9690 2577
Email: sydney@biosis.com.au

Wollongong

8 Tate Street
Wollongong NSW 2500

Phone: (02) 4229 5222
Fax: (02) 4229 5500
Email: wollongong@biosis.com.au

QUEENSLAND

Brisbane

Suite 4 First Floor, 72 Wickham Street
Fortitude Valley QLD 4006

Phone: (07) 3831 7400
Fax: (07) 3831 7411
Email: brisbane@biosis.com.au

VICTORIA

Ballarat

506 Macarthur Street
Ballarat VIC 3350

Phone: (03) 5331 7000
Fax: (03) 5331 7033
Email: ballarat@biosis.com.au

Melbourne (Head Office)

38 Bertie Street
Port Melbourne VIC 3207

Phone: (03) 9646 9499
Fax: (03) 9646 9242
Email: melbourne@biosis.com.au

Wangaratta

16 Templeton Street
Wangaratta VIC 3677

Phone: (03) 5721 9453
Fax: (03) 5721 9454
Email: wangaratta@biosis.com.au

Document information

Report to: Googong Township Pty Ltd

Prepared by: Robert Speirs

Biosis project no.: 13402 → 16561 → 18082

File name: 18082.GoogongTownship.PTWL-P&MP.FinalV5.RES06072014

Citation: Biosis (2014). Googong Township Pink-tailed Worm-lizard Protection and Management Plan – Version 5. Prepared for Googong Township Pty Ltd. Author: R. Speirs, Biosis Pty Ltd, Canberra. Project 18082.

Acknowledgements

Biosis acknowledges the contribution of the following people and organisations in undertaking this study:

- Michael Nolan, Malcolm Leslie and Mark Attiwill (Googong Township Pty Ltd)
- Paul Keighley and Paula Nott (Manidis Roberts)
- Rod Pietsch (NSW OEH)

The following Biosis staff have been involved in this project:

- Jodie Cooper and Samantha Vertucci for assistance in the field
- James Shepherd and Ashleigh Pritchard for GIS analysis and mapping

© Biosis Pty Ltd

This document is and shall remain the property of Biosis Pty Ltd. The document may only be used for the purposes for which it was commissioned and in accordance with the Terms of the Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

Disclaimer:

Biosis Pty Ltd has completed this assessment in accordance with the relevant federal, state and local legislation and current industry best practice. The company accepts no liability for any damages or loss incurred as a result of reliance placed upon the report content or for any purpose other than that for which it was intended.

Document control

| Version | Internal review | External review | Date issued |
|--|-----------------|--|-------------|
| Draft version 01 | Daniel Gilmore | Paul Keighley Michael Nolan | 02/09/2011 |
| Draft version 02 | - | Googong Foreshores-Township Interface Working Group | 22/09/2011 |
| Draft version 03 for public comment | - | Paul Keighley Mark Attiwill DSEWPaC | 29/09/2011 |
| Draft version 04 (for DSEWPaC final review) | - | Paula Nott Michael Nolan | 01/11/2011 |
| Final version 01 (for Ministerial endorsement) | - | Paula Nott Michael Nolan | 18/11/2011 |
| Final version 02 (for Ministerial endorsement) | - | Michael Nolan DSEWPaC | 04/07/2012 |
| Final version 03 (revision to address NSW EP&A Act approval) | - | Chontelle Perucich Rod Pietsch (NSW OEH) | 25/06/2013 |
| Final version 04 (revision to address IWC infrastructure staging requirements) | - | Michael Nolan | 29/04/2014 |
| Final version 05 (revision to address NH1B planning and design requirements) | - | Michael Nolan | 06/07/2014 |

Contents

| | |
|---|-----------|
| Abbreviations and Common Terms | v |
| 1. Introduction | 1 |
| 1.1 Purpose..... | 1 |
| 1.2 Background..... | 2 |
| 1.3 Structure of this PTWL-P&MP | 4 |
| 2. Establishment, Protection and Management of the PTWL Conservation Area..... | 5 |
| 2.1 The PTWL Conservation Area concept | 5 |
| 2.1.1 Conservation principles..... | 5 |
| 2.1.2 Design and location of the PTWL Conservation Area..... | 5 |
| 2.1.3 Management zones | 6 |
| 2.1.4 Key threats and management priorities | 7 |
| 2.2 PTWL Establishment Works and Management by GTPL..... | 7 |
| 2.2.1 Establishment of the PTWL Conservation Area boundary and fencing..... | 7 |
| 2.2.2 Weed removal | 10 |
| 2.2.3 Physical removal of Radiata Pine and thinning of Burgan | 11 |
| 2.2.4 Translocation of habitat resources and PTWL individuals | 11 |
| 2.2.5 Re-establishment and encouragement of native grasses..... | 12 |
| 2.2.6 Additional management measures during construction | 13 |
| 2.3 Monitoring and Management by GTPL | 13 |
| 2.3.1 Weed monitoring and management..... | 13 |
| 2.3.2 Monitoring of native grass re-establishment success..... | 13 |
| 2.3.3 Monitoring of PTWL abundance and distribution..... | 14 |
| 2.3.4 Management of herbivores and feral predators..... | 14 |
| 2.3.5 Prevention of domestic animal impacts upon PTWL | 15 |
| 2.3.6 Public education and community engagement..... | 15 |
| 2.4 Perpetual Monitoring and Management by Council | 16 |
| 2.4.1 Ongoing weed monitoring and management | 16 |
| 2.4.2 Monitoring of native grass re-establishment success..... | 16 |
| 2.4.3 Monitoring of PTWL abundance and distribution..... | 16 |
| 2.4.4 Ongoing deterrence of unrestrained domestic animal access to the PTWL Conservation Area | 16 |
| 2.4.5 Legal mechanisms to protect the PTWL Conservation Area in perpetuity..... | 17 |
| 3. Consultation and Review of this PTWL-P&MP..... | 18 |
| 3.1 Consultation undertaken during the development of this PTWL-P&MP | 18 |
| 3.1.1 Googong Township Foreshores Interface Working Group | 18 |
| 3.1.2 Further consultation undertaken during 2011 | 18 |
| 3.2 Public and agency comment on the draft PTWL-P&MP | 18 |

| | | |
|-----------|---|-----------|
| 3.3 | Ongoing review of this PTWL-P&MP | 19 |
| 4. | Summary of Management Actions and Responsibilities | 20 |
| | Figures..... | 23 |
| | References..... | 30 |
| | Appendix A: Background to the PTWL at Googong | 32 |
| | Appendix B: Submissions received during Public Exhibition of the PTWL-P&MP..... | 36 |
| | Appendix C: Submissions received during consultation under Part 3A Project Approval..... | 42 |
| | Appendix D: Section 88B Instrument..... | 43 |

List of Tables

| | | |
|----------|--|----|
| Table 1: | Relevant Conditions of Approval for the protection and management of the PTWL | 1 |
| Table 2: | PTWL Conservation Area management zones | 6 |
| Table 3: | PTWL Conservation Area management summary..... | 20 |
| Table 4: | Issues raised in submissions received during the exhibition of the final draft PTWL-P&MP | 36 |
| Table 5: | Issues raised in comments received from NSW Office of Environment and Heritage | 42 |

Abbreviations and Common Terms

| | |
|------------------------|---|
| ACT TAMS | ACT Government Territory and Municipal Services Directorate |
| AHD | Australian Height Datum |
| APZ | Asset Protection Zone |
| CEMP | Construction Environmental Management Plan |
| Council | Queanbeyan City Council |
| DECCEW ACT | Department of Environment, Climate Change, Energy and Water |
| DSEWPaC | Commonwealth Department of Sustainability, Environment, Water, Population and Communities (Department of the Environment from September 2013 onwards) |
| EEC | Endangered Ecological Community |
| EP&A Act | <i>Environmental Planning and Assessment Act 1979</i> |
| EPBC Act | <i>Environment Protection and Biodiversity Conservation Act 1999</i> |
| EPI | Environmental Planning Instrument |
| Googong IWC Project | Googong township Integrated Water Cycle Project |
| Googong township | The area encompassed by Googong township |
| GTPL | Googong Township Pty Ltd |
| LEP | <i>Queanbeyan Local Environmental Plan 2012</i> |
| LGA | Local Government Area |
| NPWS | NSW National Parks and Wildlife Service (part of the OEH) |
| OEH | NSW Office of Environment and Heritage |
| PTWL | Pink-tailed Worm-lizard |
| PTWL Conservation Area | The area of the Study Area proposed to be dedicated and managed as a conservation area for Pink-tailed Worm-lizard |
| Study Area | The area of Googong township assessed as supporting PTWL habitat during the 2010 surveys |
| TSC Act | <i>Threatened Species Conservation Act 1995</i> |
| sp. | species (singular) |
| spp. | species (plural) |
| ssp. | subspecies |
| var. | variety |
| VPA | Voluntary Planning Agreement |

1. Introduction

1.1 Purpose

The Commonwealth Department of Sustainability, Environment, Water, Population and Communities (DSEWPaC) approved the development of Googong township (on 19 May 2011) subject to a number of Conditions of Approval (CoA). CoA 1 related to the protection and management of the Pink-tailed Worm-lizard (*Aprasia parapulchella*) (PTWL) within Googong township. CoA 1 has been addressed in this document in the manner detailed in Table 1 below.

The Googong township Integrated Water Cycle Project (Googong IWC Project), which includes construction and operation of a water recycling plant as well as potable water and wastewater services for the township, was approved by the NSW Department of Planning and Infrastructure on 24 November 2011. Table 1 also includes the relevant NSW Project Approval CoA related to the protection of the PTWL.

Table 1: Relevant Conditions of Approval for the protection and management of the PTWL

| Condition of Approval 1 | Section/s |
|--|-------------------------|
| CoA 1 as per the EPBC Approval | |
| <i>The person taking the action must prepare and submit a Pink-tailed Worm-lizard Protection and Management Plan for the Minister's approval for the protection of Pink-tailed Worm-lizard (Aprasia parapulchella). The plan must include:</i> | Entire document |
| <i>i. Details of the establishment of the Pink-tailed Worm-lizard Conservation Area;</i> | 2.1 2.2.1 |
| <i>ii. Management measures to mitigate construction impacts;</i> | 2.2.1 2.2.4 2.2.6 |
| <i>iii. Measures for the management of the Pink-tailed Worm-lizard Conservation Area for before and after the conservation area's dedication to Queanbeyan City Council or other appropriate authority;</i> | 2.2 2.3 2.4 |
| <i>iv. Maps showing fences and other infrastructure;</i> | Figure 4 |
| <i>v. Details of legal mechanisms to protect the conservation area in perpetuity; and</i> | 2.4.5 |
| <i>vi. Provision for public comment on the draft plan.</i> | 3.2 |
| <i>The plan must be submitted to the Minister for written approval within 6 months of the date of this approval.</i> | 4.0 |
| <i>The person taking the action must not commence construction within 50 metres of Pink-tailed Worm-lizard habitat until the Minister has approved the plan.</i> | 2.2.1 Figure 2 |
| <i>The approved Pink-tailed Worm-lizard Protection and Management Plan must be implemented.</i> | 3.2 4.0 |
| CoA B14 as per the Project Approval under Section 75J of the NSW Environmental Planning & Assessment Act 1979. | |
| <i>The Proponent shall establish and maintain in perpetuity a dedicated area of land on the project site for the conservation of the Pink-tailed Legless Lizard (Aprasia parapulchella) as outlined in the plan prepared in</i> | Entire document |

| Condition of Approval 1 | Section/s |
|--|---|
| <i>accordance with condition D9 and shown in Appendix 2.</i> | |
| CoA D9 as per the Project Approval under Section 75J of the NSW Environmental Planning & Assessment Act 1979. | |
| <i>The Proponent shall prepare and implement an Aprasia Conservation Management Plan for the project to provide and maintain habitat for the Pink-tailed Legless Lizard in accordance with condition B14. This plan must be prepared in consultation with OEH and DSEWPaC, and be submitted to the Director-General for approval by the end of June 2012. The plan must:</i> | Entire document |
| <i>(a) be prepared or peer reviewed by a suitably qualified ecologist;</i> | Prepared by Robert Speirs (Biosis) Peer reviewed by Dr Will Osborne (University of Canberra) |
| <i>(b) be based on the recommendations in the EA and the objectives of the National Recovery Plan for the species;</i> | Appendix A |
| <i>(c) outline the roles and responsibilities of parties that would implement the plan</i> | Table 3 |
| <i>(d) set out the appropriate objectives, actions and milestones for the Proponent, prior to handing over ownership of this land to Queanbeyan City Council;</i> | 2.1.1 |
| <i>(e) include:</i> | 2.1 |
| <i>(i) procedures to survey and mark the boundary of the conservation area and a 20 meter buffer zone;</i> | |
| <i>(ii) procedures for the establishment and maintenance of boundary fencing, including measures to promote kangaroo grazing;</i> | 2.1 |
| <i>(iii) procedures and success criteria for habitat restoration and weed management;</i> | 2.3.2 2.3.3 |
| <i>(v) a community education program;</i> | 2.3.6 |
| <i>(vi) procedures to achieve long-term security for the conservation area;</i> | 2.4 |
| <i>(vii) a program to monitor the Pink-tailed Legless Lizard population within the conservation area; and</i> | 2.3 |
| <i>(viii) a program which sets out milestone dates for achieving the actions and measures in the plan.</i> | Table 3 |

1.2 Background

Googong township is a new master-planned town for a population of some 16,000 people, which will be constructed over the next twenty years. The vision is for a new, vibrant and sustainable community with an economic town centre and strong sense of place.

Approval for Googong township has been achieved through three different approval pathways, outlined as follows:

-
- Approval to develop Googong township subdivision, urban development works and the Googong IWC Project was granted under sections 130(1) and 133 of the Commonwealth *Environment Protection and Biodiversity Conservation Act 1999* (EPBC Act) on 19 May 2011.
 - For the approval of all infrastructure relating to the potable water, recycled water and sewage system for the township, an environmental assessment was prepared under (the now repealed) Part 3A of the NSW *Environmental Planning and Assessment Act 1979* (EP&A Act) to assess the impacts of construction and operation of infrastructure. On 24 November 2011, a Concept Approval for the ultimate development (Stage 1 and Stage 2) and a Project Approval for Stage 1 of the Googong IWC Project was granted by the NSW Planning Assessment Commission, under delegation from the Minister for Planning and Infrastructure. Stage 1 of the Project comprises the following infrastructure:
 - a water recycling plant (WRP);
 - temporary reservoirs for recycled and potable water;
 - pumping stations for sewage, recycled water and potable water;
 - mains pipework (including rising and distribution mains) for sewage, recycled water and potable water to connect to Neighbourhood 1A (NH1A); and
 - connection to the stormwater management system.
 - For the development of NH1A, approval was gained from Queanbeyan City Council (QCC) under Part 4 of the EP&A Act. NH1A includes construction of the subdivision and associated infrastructure including stormwater, roads, civil works and utilities.

To satisfy the relevant conditions of approval from the above described approvals, Biosis Pty Ltd (previously 'Biosis Research Pty Ltd') was engaged by the Googong Development Corporation (now 'Googong Township Pty Ltd' (GTPL)) in 2010 to prepare an assessment of the impacts of Googong township upon an area of known PTWL habitat occurring within the eastern extent of the township (refer to Figure 1). In order to inform this assessment, habitat quality mapping was completed and intensive targeted rock-turning surveys were conducted throughout the areas determined to constitute potential habitat for the species. PTWL habitat throughout the Study Area was mapped according to ranking criteria that incorporated the abundance and density of surface rocks as well as vegetation composition. Using these ranking criteria, the Study Area was segmented into areas of 'Very High', 'High', 'Medium' and 'Low' quality habitat for the PTWL.

The results of the field surveys and habitat mapping were used to inform the preparation of an assessment against the EPBC Act Significant Impact Criteria (Commonwealth of Australia 2008) and to make recommendations for the design and ongoing management of a proposed PTWL Conservation Area. In accordance with the recommendations provided, GTPL proposed to establish, rehabilitate and dedicate to public ownership, a 52 ha PTWL Conservation Area within Googong township. The proposed PTWL Conservation Area included the entire area mapped as 'Very High' quality habitat, the majority of the 'High' quality habitat and 'Medium' quality habitat as well as proposing to restore and protect areas of 'non-habitat', strategically located to increase habitat connectivity and reduce 'edge-effects' (refer to Figures 2 and 3). The EPBC Act Significant Impact Criteria assessment concluded that the proposed development of Googong township would be unlikely to result in a significant impact upon the PTWL, provided the proposed PTWL Conservation Area is established and appropriately managed in perpetuity.

As such, this approach to the management of the PTWL within Googong township was proposed by GTPL in the submission of an EPBC Act Referral of the proposed action to DSEWP&C for assessment of Googong township against the provisions of Part 9 of the EPBC Act.

1.3 Structure of this PTWL-P&MP

This PTWL-P&MP is structured in the following manner:

Section 2 – Details regarding the establishment, protection and management of the PTWL Conservation Area.
Within Section 2:

- Subsection 2.1 details the PTWL Conservation Area concept including the conservation principles, design and location, and the proposed management zones;
- Subsection 2.2 details the initial works and management actions to be undertaken by GTPL;
- Subsection 2.3 details the monitoring and management of the PTWL Conservation Area to be undertaken by GTPL; and
- Subsection 2.4 details the monitoring and management of the PTWL Conservation Area to be undertaken in perpetuity by Queanbeyan City Council (Council).

Section 3 – Details regarding the consultation and review undertaken during the preparation and to be undertaken during implementation of this PTWL-P&MP:

- Subsection 3.1 details the consultation undertaken during the development of this PTWL-P&MP;
- Subsection 3.2 details the provision that has been made for public and agency comment on this PTWL-P&MP; and
- Subsection 3.3 details the ongoing review procedure for this PTWL-P&MP.

Section 4 – A summary of the management actions to be undertaken and the parties responsible.

2. Establishment, Protection and Management of the PTWL Conservation Area

2.1 The PTWL Conservation Area concept

2.1.1 Conservation principles

The following four principles recommended by Biosis and independently endorsed by PTWL expert Dr Will Osborne have been applied by GTPL in determining the location design, establishment and management of the PTWL Conservation Area within Googong township:

- including, and thereby preventing the disturbance of, all areas of 'Very High' quality habitat and the majority of the areas of 'High' and 'Medium' quality habitat within the PTWL Conservation Area;
- providing a balanced outcome of urban development and a consolidated, contiguous PTWL Conservation Area that reduces habitat fragmentation and improves habitat quality for the species in the long term;
- optimising the habitat connectivity of the PTWL Conservation Area to the adjoining Googong Foreshores; and
- implementing an ongoing management regime that will effectively manage the PTWL Conservation Area for the conservation of the PTWL, whilst remaining fiscally responsible and practicable to implement and manage.

These principles have been considered by GTPL as 'objectives' to be met during the design and management of Googong township in order to facilitate development, whilst ensuring the development does not have a 'significant impact' (as defined pursuant to the EPBC Act) upon the population of PTWL.

2.1.2 Design and location of the PTWL Conservation Area

The PTWL Conservation Area that will be established by GTPL (as illustrated in Figures 2 and 3) has been designed in a manner that will result in a qualitative and quantitative long-term net-benefit to PTWL habitat within the locality. With regard to the location and extent of the PTWL Conservation Area, it should be noted that of the PTWL habitat assessed as occurring within Googong township, the PTWL Conservation Area will encompass the following.

1. The entire 24.2 ha area of 'Very High' quality habitat.
2. The majority (6.25 ha or 65.2%) of the 'High' quality habitat. The loss of the balance 3.33 ha or 34.8% of 'High' quality habitat will be effectively compensated for by restoring and protecting 'Medium' quality habitat and areas of 'non-habitat', strategically located to increase habitat connectivity and reduce 'edge-effects'.
3. The majority (15.71 ha or 66.1%) of the area of 'Medium' quality habitat. The retained areas will be restored and, over time, become higher quality habitat.

As such, the PTWL Conservation Area proposed by GTPL will, in time, encompass a total of approximately 54 ha containing a minimum of approximately 46.16 ha of 'Very High' or 'High' quality habitat. This will result in a substantial long-term net increase given that the total area of 'Very High' or 'High' quality habitat prior to the establishment of the PTWL Conservation Area is 33.78 ha. In addition, the habitat restoration and management measures detailed in this PTWL-P&MP will:

- substantially improve habitat quality within the PTWL Conservation Area;
- maintain and improve habitat connectivity within the PTWL Conservation Area; and
- improve habitat connectivity between the PTWL Conservation Area and the adjoining Googong Foreshores.

2.1.3 Management zones

The PTWL Conservation Area will be divided into three (3) broad management zones:

- PTWL habitat zone – this is the majority of the PTWL Conservation Area;
- Habitat buffer zone – this is a 20 m zone at the urban interface; and
- Montgomery Creek zone – this is the area immediately adjacent to, and including, the creek line.

Table 2 provides details of the management zones including the objective habitat quality and the management actions to be implemented with the aim of achieving this objective.

Figure 3 shows the areas of key management actions, such as shrub thinning and rock placement (detailed further in Section 2.2). Figure 3 also identifies the existing E2 zoning based on the Queanbeyan Local Environmental Plan 2012 (LEP). The E2 zoning contains certain additional management provisions.

Table 2: PTWL Conservation Area management zones

| Zone | Area (ha) | Objective habitat quality (long-term) | Primary aims | Management actions |
|--------------------------|-----------|---------------------------------------|--|--|
| PTWL habitat zone | 42.79 | High to very high | <ul style="list-style-type: none"> • Enhance PTWL habitat characteristics: <ul style="list-style-type: none"> – Moderate to high rock scatter density. – Native grass dominated groundstorey. – Low fuel loads. | <ul style="list-style-type: none"> • Weed removal and control. • Targeted woody weed and Radiata Pine removal. • Maintain fuel loads and grassland vegetation, primarily by kangaroo grazing. • Placement of suitable habitat rocks translocated from elsewhere within Googong township. |
| PTWL habitat buffer zone | 4.51 | Medium | <ul style="list-style-type: none"> • Manage edge effects. • Promote PTWL habitat characteristics. • Bushfire asset protection. | <ul style="list-style-type: none"> • Weed control. • Maintain fuel loads and grassland vegetation. High height slashing may be required. • Rubbish removal. |
| Montgomery Creek zone | 2.14 | Low | <ul style="list-style-type: none"> • Maintain water quality and flows. • Enhance native vegetation. | <ul style="list-style-type: none"> • Weed removal and control. • Native vegetation planting (riparian species). |

2.1.4 Key threats and management priorities

A risk management approach has been undertaken with regard to the design and management of the PTWL Conservation Area, particularly with respect to the design, location and staging of the conservation area fencing. The risks, based on the likelihood and consequences of potential impacts, were discussed and agreed to by the Googong Foreshores-Township Interface Working Group on 9 September 2011. This risk assessment was informed by the scientific advice from expert ecologists and utilised the experience of local land managers. The management approach discussed in the remainder of this section is based on the following threats to the conservation of the PTWL, in order of priority:

1. Trail bikes – the use of trail bikes within the PTWL Conservation Area is likely to disturb key habitat features, such as small surface rocks.
2. Four-wheel-drive vehicles – similar to trail bikes, four-wheel-drive vehicles may disturb habitat features. However, due to the steep topography throughout much of the PTWL Conservation Area movement within the PTWL Conservation Area by such vehicles is limited.
3. Unleashed/feral dogs and cats – these animals may excavate under and around habitat rocks and directly predate on PTWL individuals, however, the likelihood of this occurring is considered to be low.
4. Pedestrians – while the likelihood of people walking through areas of PTWL habitat is high, the level of impact upon the species, which may result from human foot traffic and other pedestrian access impacts is considered to be low.
5. Bush rock removal – while bush rock removal is recognised as a key threatening process to the PTWL, the fencing type and schedule detailed in Section 2.2.1 will prevent unauthorised vehicular access to the PTWL Conservation Area. Impacts associated with the removal of bush rocks without the aid of a vehicle (i.e. carrying by hand from the PTWL Conservation Area to residential properties via Googong Foreshores) are considered to be unlikely and of low significance.

With regard to all the above priority risks, it has been identified by the Googong Foreshores-Township Interface Working Group that public education and community engagement is of key importance to the protection of the PTWL Conservation Area and the minimisation of the risks/impacts detailed above. Section 2.3.6 details the public education and community engagement actions that will be undertaken.

2.2 PTWL Establishment Works and Management by GTPL

2.2.1 Establishment of the PTWL Conservation Area boundary and fencing

Boundary form and function

The boundary fence between the PTWL Conservation Area and the surrounding urban areas of Googong township will be 1.8 m in height. To respond to the highest priority risks discussed in Section 2.1.4, the fence will be constructed using chain mesh with galvanised posts and rails at the top and approximately 0.9 m. This fence type is considered to be the most appropriate as it will:

- not create a visually unappealing barrier between the PTWL Conservation Area and the adjacent residential areas;
- be effective in preventing illegal access into the PTWL Conservation Area (entry without a key would require climbing over or cutting holes in the 1.8m boundary fence); and
- provide some deterrent to domestic cats and dogs which may escape or roam from the surrounding future residential areas.

Legal pedestrian access to the PTWL Conservation Area (i.e. for passive recreation purposes such as bushwalking, bird watching, etc) will only be made available via Googong Foreshores when open to the public (generally 8am to 5pm). No formed access tracks or other facilities will be established within the PTWL Conservation Area.

As shown in Figure 4, where the PTWL Conservation Area boundary meets the Googong Foreshores boundary, the PTWL Conservation Area fence will join the fence that will be constructed between the urban (residential) areas of the township and Googong Foreshores. This fence will be of the same type and form, similarly designed in a manner that will minimise the risk of pest fauna species, illegal vehicular and pedestrian access into Googong Foreshores.

Existing fencing between the PTWL Conservation Area and the adjoining Googong Foreshores will be removed to allow for the free movement of kangaroos, wallabies and wombats between the conservation area and Googong Foreshores. An appropriate level of grazing by native herbivores will greatly assist in maintaining the grassland habitat desirable to PTWL and reduce fuel loads.

Maintaining and monitoring the fence around the PTWL Conservation Area to prevent illegal access into the PTWL Conservation Area will also prevent such access into Googong Foreshores. Upon construction of the adjacent residential properties, community surveillance of the PTWL Conservation Area will provide a considerable deterrent to people wishing to enter the PTWL Conservation illegally.

Gates with a six metre wide opening will be installed in the fence at a number of locations along the boundary, strategically chosen in order to provide emergency and other authorised access into the PTWL Conservation Area. The type and form of these gates will be consistent with that of the adjoining fence and they will be constructed in a manner that does not result in them becoming a weak point in the fence.

A 20 m wide 'buffer zone' will be established running around the inside of the boundary of the PTWL Conservation Area (refer to Figure 3). This buffer zone will be monitored during the twice-annual (spring and autumn) weed monitoring and management program (refer Section 2.3.1) and any disturbance or additional weed establishment/encroachment will be promptly and sensitively controlled. Alike the balance of the PTWL Conservation Area, the buffer zone will be managed for PTWL conservation and, as such, will not be used as a transport corridor, or other incompatible use. However, the buffer zone may form part of the asset protection zone (APZ) for adjacent residential properties and, as such, may be managed as an Outer Asset Protection Area in accordance with Planning for Bushfire Protection - A Guide for Councils, Planners, Fire Authorities and Developers (NSW Rural Fire Service 2006), which entails maintaining fuel loads at less than eight (8) tonnes per hectare (ha). It should be noted that it is expected that in this environment, no additional measures are expected to be required to maintain such fuel loads. Notwithstanding this, asset protection for residences located opposite the PTWL Conservation Area will be primarily achieved by the road reserve and measures to be implemented within the residential properties. As previously stated, grazing by native herbivores at the desirable intensity to optimise PTWL habitat quality will also greatly reduce fuel loads within the PTWL Conservation Area.

In the event that native herbivore grazing is insufficient to maintain the required fuel loads within the buffer zone, slashing may be undertaken within the buffer zone to maintain fuel loads to Outer Protection Area standards. Slashing equipment will be thoroughly cleaned of all potentially weed seed laden material prior to entry and cutter blades will be set high enough to avoid rocks.

The boundary between the PTWL Conservation Area and the adjacent surrounding future residential development areas will be the area where 'edge effects' are most relevant and will require the highest degree of ongoing management. As such, all reasonable efforts have been made during the design of the PTWL Conservation Area to minimise the length of the boundary between the PTWL Conservation Area and the adjacent surrounding future residential development areas. This was achieved through the design of the

PTWL Conservation Area in accordance with the principles discussed in Section 2.2.1 and on the advice of relevant experts. In particular, this related to consolidation of habitat areas to reduce fragmentation by restoring areas within the PTWL Conservation Area, thereby providing increased habitat connectivity and quality within the PTWL Conservation Area and improving habitat connectivity to the adjoining Googong Foreshores. This process is illustrated in Figures 2 and 3, particularly on the southern side of Montgomery Creek.

Sealed edge roads will be constructed around the majority of the boundary of the PTWL Conservation Area with residential lots located on the opposite side of the road. The location of roads in this manner is effective in discouraging the dumping of rubbish and the often well intentioned (however highly environmentally degrading) practice of spreading lawn clippings throughout the grassland over the back fence. In order to avoid the establishment of additional exotic plants and to prevent increases in the proportion of those already present, disturbance to the topsoil between the road and the PTWL Conservation Area boundary fence will be minimised. Should the placement of additional soil be required in this area, this soil will be sourced from adjacent areas and will be seeded with local native grasses. The use of soil sourced in this manner will assist in preventing the introduction of additional exotic plant species into the locality.

With regard to the above, given the topography of the area, the delivery of a full edge road is not practicable along a section of the boundary of the northern part of the PTWL Conservation Area. As such, a six (6) metre wide formed gravel fire trail will be established along this section between the PTWL Conservation Area and the adjoining residential lots (refer Figure 5). Whilst not comprising part of the PTWL Conservation Area (and thus not being subject to the measures of this PTWL-P&MP), the fire trail will be fenced into the PTWL Conservation Area with the 1.8m boundary fence located between the fire trail and the adjoining lots. As such, for the relevant section of the PTWL Conservation Area boundary, the boundary fence will be moved six metres outwards to encompass the fire trail, however the PTWL Conservation Area boundary will remain unchanged (as illustrated in Figures 2, 3 and 5). The fire trail will be locked at either end and will provide access to authorised parties only, primarily for bushfire management, land maintenance and to monitor the interface.

Boundary establishment schedule

The trigger for establishment is the commencement of residential subdivision works for Googong township within 50 m of the identified PTWL habitat. This trigger is considered to mark 'Year 0' of the PTWL Conservation Area and all works to establish the PTWL Conservation Area will proceed in stages from this point. Figure 2 provides the indicative 'Year 0' trigger line.

In accordance with the above, the relevant section of the PTWL Conservation Area boundary will be defined and fenced prior to any residential subdivision construction works commencing within 50 m of the relevant section of the identified PTWL Habitat. Fence construction will then proceed in stages, generally as per the diagrammatic representation provided in Figure 4.

The current land use and management regime (i.e. for agricultural purposes, notably sheep grazing) has been in place throughout the PTWL Conservation Area and surrounds for an extended period. This land use and management regime will continue until 'Year 0' will occur as it will best allow for the maintenance of the PTWL habitat quality and the PTWL population within. The existing stock fencing within the PTWL Conservation Area and immediate vicinity will also remain without substantial alteration until 'Year 0' (Note: this does not preclude routine maintenance or replacement of the existing fences, if required). The continuation of the current land use and the retention of the existing stock fencing will also preclude public access to the PTWL Conservation Area prior to its formal establishment.

In relation to Stage 1 of the Googong IWC Project, Sewage Pumping Station 2 (SPS2) will be the closest infrastructure construction works to the PTWL Conservation Area (refer to Figure 6). As illustrated in Figure 6,

SPS2 and its associated construction footprint will be located within the Year 0 trigger line and construction works (scheduled to commence in July 2014) will result in the disturbance of PTWL habitat. As also illustrated in Figure 6, the sewer rising main and the two gravity sewer mains which will connect to SPS2 will also be partly located within the Year 0 trigger line. Whilst located within the Year 0 trigger line, the commencement of the establishment of the PTWL Conservation Area will not be triggered by the construction of SPS2 and associated sewer mains given the following.

1. SPS2 is a component of the Googong IWC Project, infrastructure works which must be completed prior to the development of the remainder of Neighbourhood 1A or any of Neighbourhood 1B. Similarly, the gravity sewer mains are required to service Neighbourhood 1A. The Googong IWC Project works and the gravity sewer mains for Neighbourhood 1A are quite discrete from the residential subdivision construction works that will occur within the Year 0 trigger line for Neighbourhood 1B. In this regard, residential construction works for Neighbourhood 1B are not scheduled to commence until May 2015.
2. The area of PTWL habitat disturbance that will occur for the construction of the sewer infrastructure (SPS2 and associated sewer mains) is well defined and will be limited to the minimum required to allow for the practicable construction of the infrastructure. In this regard, disturbance for the construction of the sewer infrastructure will be confined to the construction works footprint as illustrated in Figure 6. If all PTWL habitat within this defined 'maximum' construction footprint is disturbed it would result in the disturbance of 0.42 ha of 'Medium' quality habitat and 0.03 ha of 'Low' quality habitat.
3. The sewer infrastructure construction works will not result in the provision of public access to the PTWL Conservation Area or immediate surrounds. Only those parties specifically engaged to work on the construction project will be permitted to access the works area. All such staff and contractors will be inducted as described in Section 2.2.6 and educated regarding the PTWL Conservation Area and the relevant protection measures required of the particular construction personnel.
4. The construction of sewer infrastructure will not introduce or proliferate any of the 'key threats and management priorities' listed in Section 2.1.4.
5. The 'Translocation of habitat resources and PTWL individuals' (including the 'importation of habitat rocks' and 'PTWL salvage and translocation program') as detailed in Section 2.2.4 will be implemented for the area of PTWL habitat disturbed for the sewer infrastructure construction.
6. A construction exclusion fence will be established between the sewer infrastructure construction footprint and the PTWL Conservation Area boundary. As illustrated in Figure 6, the fence will run parallel to and at least five metres from the PTWL Conservation Area boundary. The construction exclusion fence will be constructed of sturdy materials, fit for purpose and maintained for the duration of construction works.



2.2.2 Weed removal

Post establishment of the PTWL Conservation Area boundary, all woody weeds (i.e. Sweet Briar (*Rosa rubiginosa*) and African Boxthorn (*Lycium ferocissimum*)) will be removed (via poisoning and physical removal) from the PTWL Conservation Area.

A targeted weed removal program (spot spraying) has been implemented to control the Serrated Tussock (*Nassella trichotoma*) (approximately 50 plants were identified in 2010) located along the Montgomery Creek riparian zone within the PTWL Conservation Area. In January 2013 the 50 plants were located and sprayed with Glyphosate (with blue marker dye). These plants will be checked during spring 2013 to ensure a

thorough kill was achieved. Any plants remaining alive and any others located within the PTWL Conservation Area were sprayed at this time. Eradication of this weed species is essential to prevent its spread and proliferation throughout the PTWL Conservation Area. As such, GTPL will continue to undertake the control works required to eradicate Serrated Tussock within the PTWL Conservation Area.

All weed removal works will be undertaken by trained and competent personnel using weed management techniques that are targeted to the species with minimal impact upon non-target species.

Specific efforts to eradicate or substantially reduce the other exotic grass and herbaceous species (primarily pasture species and common rural species), which are widespread throughout the PTWL Conservation Area are unwarranted. These species are generally considered 'naturalised' throughout the rural areas of the Southern Tablelands and, as such, efforts to eradicate them would be largely futile given their abundance throughout the wider locality. The removal of stock and associated nitrification of the soils, combined with the re-establishment and appropriate grazing of native grasses is likely to reduce the prominence of many of the exotic grasses and herbs within the PTWL Conservation Area.



2.2.3 Physical removal of Radiata Pine and thinning of Burgan

The Radiata Pine (*Pinus radiata*) planted along the gully in the eastern part of the PTWL Conservation Area (refer to Figure 3) will be physically removed. The trees will be sawn at the base, felled and removed from the PTWL Conservation Area. The tree stumps will remain in place to minimise soil disturbance and erosion. If trees are chipped onsite the resulting mulch will be removed and not dumped or distributed within the PTWL Conservation Area.

The areas within the PTWL Conservation Area which support dense stands of Burgan (*Kunzea eriocoides*) will be thinned (refer to Figure 3). Burgan bushes will be sawn at the base and removed from the PTWL Conservation Area. Care will be taken to minimise disturbance to the soil surface and avoid disturbance to areas supporting substantial rock scatter density.

The thinning of dense stands of Burgan will also reduce shading of PTWL habitat, encouraging the growth of Kangaroo Grass and other native groundstorey species, which increase habitat quality for the PTWL. Reduced shading also increases the thermoregulatory benefit offered by habitat rocks to PTWL, and thus, increases their utilisation of these important habitat features. It should be noted, however, that the thinning of Burgan will not become a widespread operation, nor will it aim to remove or substantially reduce the presence of the species within the PTWL Conservation Area or the very extensive adjoining Googong Foreshores.



2.2.4 Translocation of habitat resources and PTWL individuals

Importation of habitat rocks

Suitable habitat rocks removed by GTPL during the construction of the edge road and other excavations within the immediate vicinity of the PTWL Conservation Area will be imported into the PTWL Conservation Area. These rocks will then be scattered throughout the existing areas devoid of suitable habitat rocks or where such rocks are at low scatter density (refer to Figure 3). The rocks used for importation will be selected due to their small and/or flat characteristics. Large or spherical rocks will not be imported. Rocks will be scattered in a manner that results in a moderate to high scatter density whilst ensuring that rocks are not piled and do not result in excess of 30% ground cover. Care will be taken to avoid existing rocky areas and to minimise soil disturbance during delivery and scattering of these rocks.

To prevent the importation of additional weed species into the PTWL Conservation Area, only rocks removed from adjacent sections of Googong township will be imported.

PTWL salvage and translocation program

Prior to the importation of rocks discussed above, any PTWL individuals uncovered outside of the PTWL Conservation Area within the existing habitat area (refer to Figure 2) will be translocated into the PTWL Conservation Area. It is important to note as the majority of high quality habitat and recorded locations of PTWL will be located within the PTWL Conservation Area, the numbers of PTWL individuals identified for translocation are expected to be low (and may be nil). This proposed salvage and translocation process is not essential to the overall protection of the PTWL or to the success of the PTWL Conservation Area, however, it will be undertaken as an additional conservation measure.

A licence to conduct the PTWL salvage and translocation program will be obtained from the NSW Office of Environment and Heritage (OEH) by a suitably qualified ecologist engaged by GTPL. Any specific conditions of this licence will be adhered during the conduct of the program. The OEH (Queanbeyan Office) will be notified of the proposed timing of the PTWL salvage and translocation program.

The PTWL salvage and translocation program will involve the turning (by a suitably qualified and experienced ecologist or similar) of all suitable habitat rocks and the capture of all PTWL found. Captured PTWL individuals will immediately be taken into the adjoining PTWL Conservation Area and released at the base of a suitable habitat rock located at least 20 m inward from the boundary. Care will be taken to ensure that the PTWL is able to make its way under the selected rock.

To prevent increases in competition in areas of existing habitat within the PTWL Conservation Area, all individuals translocated into the PTWL Conservation Area will be released in the areas of newly created/improved habitat (i.e. areas where imported rocks have been placed).

In order to maximise the number of individuals salvaged, if possible the PTWL salvage and translocation program should be completed when the conditions are suitable to survey for the species (i.e. <28 degree Celsius sunny days in spring or autumn).

In addition to the PTWL salvage and translocation program, protocols to be adhered to if PTWL are discovered during construction works are to be included in the site induction for all construction personnel working directly adjacent to the PTWL Conservation Area. The protocol that will be followed is to pause the activity and contact the relevant person on site nominated to capture and remove the PTWL encountered. The nominated person must be reasonably familiar with PTWL (i.e. be able to distinguish between a PTWL and a juvenile snake, etc). Upon notification, the nominated person will capture by hand (wearing gloves), and release the PTWL within the PTWL Conservation Area, as described above.

2.2.5 Re-establishment and encouragement of native grasses

A native grass re-establishment and encouragement program will be implemented throughout the PTWL Conservation Area. This will be aimed at facilitating and encouraging the dominance of native grasses (notably Kangaroo Grass and Red Grass) within the areas of the PTWL Conservation Area where they are not currently the dominant species due to Burgan cover or disturbance.

The program will involve the re-establishment of Kangaroo Grass and Red Grass using stock grown from seed of local provenance (i.e. ACT and surrounds). These grasses will be re-established or boosted via the spreading of fertile Kangaroo Grass and Red Grass seed across the sections of the PTWL Conservation Area where disturbance to the soil surface has occurred during the removal of exotic and native woody species and the importation of habitat rocks. The native grass re-establishment and encouragement program will occur as soon as practicable following the completion of these works.

2.2.6 Additional management measures during construction

In addition to the specific management measures detailed herein, the following standard construction best practice management measures will be adhered during all works within or adjacent to the PTWL Conservation Area, as follows:

1. Construction sites will be fenced for site security and safety reasons. No construction vehicles or personnel will be permitted outside of the construction site fencing.
2. A Construction Environmental Management Plan (CEMP) will be prepared for the management of environmental issues during construction. Relevant sections of the CEMP will be prepared to detail the protection of ecological features of Googong township, including the location of the PTWL Conservation Area. The CEMP will also detail general environmental protection measures, such as sediment and erosion control measures to be undertaken during construction activities.
3. Construction personnel will be inducted. Inductions (and less formal, task-specific actions, such as 'toolbox talks') will include, where relevant, the location of the PTWL Conservation Area and the relevant protection measures required of the particular construction personnel. Generally, this will entail construction personnel being informed to remain within the designated construction sites/areas at all times.
4. In order to prevent the importation of additional weed species into the locality, all vehicles will be cleaned of all potentially seed laden material prior to entry.
5. Construction personnel will not bring any domestic pets into the site.
6. All rubbish will be removed from site and disposed at an appropriately licenced facility. No rubbish will be burned, buried or otherwise disposed of on site.

2.3 Monitoring and Management by GTPL

2.3.1 Weed monitoring and management

A twice-annual (spring and autumn) weed monitoring and management program will be implemented to identify any regrowth of woody weeds and to locate any Serrated Tussock (or other 'Weed of National Significance') that may have re-established within the PTWL Conservation Area. Any such regrowth or re-establishment will be immediately eradicated using appropriate removal techniques.

All weed monitoring and removal works will be undertaken by trained and competent personnel using weed management techniques targeted to the species with minimal impact upon any non-target species.

2.3.2 Monitoring of native grass re-establishment success

The success of the native grass re-establishment and encouragement program will be determined through the conduct of monitoring events by appropriately qualified and experienced personnel (botanist, ecologist, bush regenerator, etc), undertaken biannually (spring and autumn) following the spreading of the grass seed. The biannual monitoring events will continue until Kangaroo Grass and Red Grass combined comprise a minimum of 25% of the groundstorey cover within the re-establishment areas. At each monitoring event, one (1) 4 m² (i.e. 2 m x 2 m) sampling plot per 1000 m² will be randomly located within each re-establishment area. The groundstorey biomass percentage of Kangaroo Grass and Red Grass within each sampling plot will be estimated and used to produce an average biomass percentage for the species within the polygon. If the biomass percentage is insufficient, further seed spreading or infill planting with these species will be undertaken to achieve the desired coverage.

It is envisaged that in the absence of stock grazing it is likely that Kangaroo Grass and Red Grass will readily establish and quickly become the dominant grass species within the re-establishment areas.

2.3.3 Monitoring of PTWL abundance and distribution

A PTWL monitoring program will be implemented to monitor the abundance and distribution of the PTWL throughout the PTWL Conservation Area.

The PTWL monitoring program will involve the turning of rocks across the entire PTWL Conservation Area and the recording of all PTWL individuals identified (i.e. numbers, locations recorded via GPS, etc). The survey effort to be completed will amount to approximately 15 hours of survey effort (i.e. two (2) ecologists for one (1) day), and, as such, the pace at which the survey staff move around the PTWL Conservation Area will need to be established accordingly.

Monitoring survey effort will be expended in a manner that provides a sample of habitat qualities ranging from 'Medium' to 'Very High', and specifically encompassing areas where habitat creation/improvement (i.e. rock placement areas and native grass re-establishment areas) has occurred.

The PTWL monitoring program has been designed in a manner that will involve a measured amount of survey effort (i.e. 15 hours per survey event) spread at low intensity across the entire PTWL Conservation Area. Given the inherent disturbance to habitat involved in rock turning surveys, this approach will distribute the disturbance across a large area, and thereby, prevent the same specific areas being repetitively disturbed (as would be the case if defined survey plots were established).

The results of each monitoring event will be provided for inclusion in the NSW Wildlife Atlas as per the standard conditions of the scientific licence held by the ecologist/zoologist engaged to conduct the monitoring.

The PTWL monitoring program will commence in the spring following the first year of residential subdivision construction works within 50 m of the PTWL Conservation Area. The program will then occur every second year using the same survey techniques at each survey event until handover of the PTWL Conservation Area to Council. The commencement of the PTWL monitoring program, as stated, will provide for a number of monitoring events to occur and allow for baseline results to be obtained prior to the substantial occupation of the adjacent future residential areas.

Notwithstanding the above, an additional 'preliminary' monitoring event was conducted during spring 2013 prior to the PTWL monitoring program commencing. The purpose of this monitoring event was to collect further baseline PTWL population data prior to any potential impacts from the early stages of Googong township being felt within the PTWL Conservation Area. The results of the spring 2013 monitoring event have been added to Figure 2.

The PTWL monitoring program will provide invaluable data regarding the continued viability of the PTWL population and hopefully demonstrate that the conservation and protection of the PTWL Conservation Area (and associated works) has increased the size and secured the viability of the PTWL population in the long-term.

Whilst the PTWL monitoring program will be conducted in accordance with the above, a degree of flexibility will be maintained to allow for the incorporation of new or better survey techniques should these become known/developed in the future. Any such changes will be documented at the time of the review of this PTWL-P&MP, which is to occur at least every five (5) years.

2.3.4 Management of herbivores and feral predators

The feral herbivore European Rabbit (*Oryctolagus cuniculus*) was detected within the PTWL Conservation Area during the 2010 surveys. This species has been identified as an invasive species which suppresses the

regeneration of natural grasses and forbs (NSW Scientific Committee 2002). High intensity grazing by rabbits is likely to adversely impact upon PTWL habitat by reducing the abundance of native grasses. In addition, the excavation of burrows and establishment of latrine sites by rabbits is likely to result in disturbance of PTWL habitat and increased weed infestation.

Whilst important for the maintenance of biomass and fuel loads, overgrazing by over-abundant kangaroo populations within the PTWL Conservation Area and the adjoining Googong Foreshores also has the potential to impact negatively upon the quality of the PTWL habitat.

Feral Cats (*Felis catus*) and the Red Fox (*Vulpes vulpes*) are known to predate upon small reptiles, including those of the family Pygopodidae. The impacts of these predators must be appropriately managed to protect the PTWL and other native fauna within the PTWL Conservation Area.

Given that herbivores and feral predators will move freely between Googong Foreshores and the PTWL Conservation Area, populations of herbivores and feral predators in the locality will be managed effectively by the existing and ongoing operations undertaken by the ACT Government Territory and Municipal Services (ACT TAMS) (Googong Foreshores Draft Plan of Management 2007).

2.3.5 Prevention of domestic animal impacts upon PTWL

The following measures will be implemented to prevent domestic animals from roaming within the PTWL Conservation Area, as follows:

1. A public education and community engagement program will be developed and implemented (refer to Section 2.3.6).
2. A sealed edge road will be located between the PTWL Conservation Area and adjacent residential properties along the majority of the interface
3. The PTWL Conservation Area boundary fence will be installed to provide a deterrent to domestic animals through the installation of chain mesh fencing (refer to Section 2.2.1). This fence will be appropriately maintained.

2.3.6 Public education and community engagement

A public education and community engagement program will be implemented by GTPL to educate the residents of, and the visitors to, Googong township. This program will provide the following:

1. Signage at strategic locations along the PTWL Conservation Area boundary providing details relating to the:
 - a. biodiversity values of the PTWL Conservation Area and importance of protecting such values;
 - b. management activities that have occurred and will continue to occur within the PTWL Conservation Area;
 - c. roles that the public can play in protecting the PTWL Conservation Area;
 - d. actions that will damage the PTWL Conservation Area and/or diminish the habitat values of the area to PTWL (i.e. recreational rock turning, bush rock collection, weed introduction, etc); and
 - e. party responsible for the management of the area and who members of the public should contact should they observe illegal or degrading activities being conducted within or immediately adjacent to the PTWL Conservation Area.

2. A section to be included within a welcome brochure (or similar) supplied to new residents and displayed in other relevant locations (Googong Foreshores visitor centre, community billboards, etc) detailing the above.

2.4 Perpetual Monitoring and Management by Council

The PTWL Conservation Area will be maintained by GTPL at its cost until the completion of the development (issue of a subdivision certificate for creation of the 5,550 lots in Googong township). Prior to or at the time of the completion of the development (which is estimated to take 25 years), the PTWL Conservation Area will be dedicated to Council. This constitutes the binding arrangement incorporated into the Voluntary Planning Agreement (VPA) being made by GTPL and Council. GTPL will work collaboratively with Council to manage the handover of the native grass re-establishment program and the other management measures established by GTPL. The handover will also ensure compliance with Project Approval CoA D9(vi), which requires procedures to achieve long term security for the PTWL Conservation Area. The specific management measures that will continue in perpetuity under the management of Council are detailed below.

2.4.1 Ongoing weed monitoring and management

The twice-annual (spring and autumn) weed monitoring and management program will continue in perpetuity. This program will identify any regrowth of woody weeds and locate any Serrated Tussock (or other 'Weed of National Significance') that may have re-established within the PTWL Conservation Area. Any such regrowth or re-establishment will be immediately eradicated using appropriate techniques.

As previously stated, all weed monitoring and removal works will be undertaken by trained and competent personnel using weed management techniques targeted to the species with minimal impact upon non-target species.

The 20 m wide buffer will continue to be regularly monitored and any disturbance or additional weed establishment/encroachment will be promptly and sensitively controlled. The use and management measures established by GTPL throughout the PTWL Conservation Area will not substantially alter upon handover to Council. That is, the entire PTWL Conservation Area will continue to be managed for the conservation of the PTWL.

2.4.2 Monitoring of native grass re-establishment success

It is anticipated that the objectives of the native grass revegetation program will be met prior to handover to Council. In this case, Council will not be required to conduct specific monitoring of the re-establishment area, however, it will conduct annual reviews of the vegetation cover and condition throughout the PTWL Conservation Area. Should handover occur prior to the minimum of 25% of the groundstorey biomass objective being met throughout the re-establishment areas, Council will ensure that any required additional seed spreading or infill plantings will be undertaken following handover.

2.4.3 Monitoring of PTWL abundance and distribution

The PTWL monitoring program will continue following handover to Council. The methodology and survey for the monitoring program will remain unchanged and continue to occur once every five (5) years in perpetuity.

2.4.4 Ongoing deterrence of unrestrained domestic animal access to the PTWL Conservation Area

The measures implemented by GTPL to deter domestic animals from roaming within the PTWL Conservation Area will remain in place under the management of Council, specifically:

- the public education and community engagement program, including signage, will continue; and
- the PTWL Conservation Area boundary fence will be maintained in order to deter domestic animals.

2.4.5 Legal mechanisms to protect the PTWL Conservation Area in perpetuity

Prior to commencement of construction within 50 metres of the PTWL Conservation Area, an 88b Instrument is to be registered over the land, requiring the owners of the Conservation Area to maintain it pursuant to the terms of the Protection and Management Plan. The 88b Instrument shall be generally in accordance with that included in Appendix D but may be registered in two stages for the portions of the Conservation Area on either side of Montgomery Creek. The Minister is to be notified upon registration of the 88b Instrument prior to the commencement of construction within 50 metres of the Conservation Area. If the 88b Instrument is registered in stages, the Minister is to be notified upon registration of each stage.

The dedication of the land for the PTWL Conservation Area is detailed within the Voluntary Planning Agreement (VPA) for Googong township. Following handover of the PTWL Conservation Area to Council, the PTWL Conservation Area will irrevocably become publicly owned land. It will then be the responsibility of Council to classify the land as community land and prepare a plan of management in accordance with the requirements of section 36 of Part 2 of the *Local Government Act 1993*. This will further enable the PTWL Conservation Area to be protected in perpetuity and provide Council with the authority to manage the land as an asset. This irrevocable dedication of the PTWL Conservation Area to public ownership will ensure that the land can not be used for another purpose in the future.

Additionally, future development can not occur within the PTWL Conservation Area, without the permission of Council or other relevant authority (as this would not be in accordance with the VPA). If such a proposal were to be put forward, it would be subject to the provisions of the EPBC Act with respect to protection of PTWL and its habitat, and a likely referral under the EPBC Act (as it would not be in accordance with Googong township EPBC referral, as approved) would be required.

Upon approval by the (Commonwealth) Minister in July 2012, the management measures and actions described herein became requirements of the approval under the EPBC Act. The Department of the Environment may conduct compliance audits and may implement enforcement measures, if these requirements are not satisfactorily adhered.

Furthermore, the poaching of PTWL or the unapproved disturbance of the habitat of threatened species in NSW is a criminal offence and offenders may be prosecuted in accordance with the provisions of the *Threatened Species Conservation Act 1995* (TSC Act).

3. Consultation and Review of this PTWL-P&MP

3.1 Consultation undertaken during the development of this PTWL-P&MP

3.1.1 Googong Township Foreshores Interface Working Group

As part of the EPBC Act referral for the township, a Googong Foreshores Township Interface Working Group (the 'Working Group') was formed in mid-2010 to undertake alignment between the commitments that were being proposed in the various planning approval documents and the existing Googong Foreshores Draft Plan of Management (ACT Government Territory and Municipal Services 2007). Parties represented in the Working Group include:

- CIC Australia/GTPL.
- Commonwealth Department of Finance.
- Commonwealth Department of the Environment.
- ACT Government Territory and Municipal Services Directorate.
- ACTEW Corporation/ActewAGL.
- Queanbeyan City Council.

The Working Group has developed broad objectives and specific actions, such as the location of fencing, which have been incorporated into this PTWL-P&MP. Relevant members of the Working Group have also been consulted further on specific aspects related to the protection and management of the PTWL. A meeting of the Working Group was held on 9 September 2011 specifically to review the first draft of this PTWL-P&MP. Subsequent proposed revisions of this PTWL-P&MP have been presented to the Working Group members for their review and comment at biannual (May and November) meetings.

3.1.2 Further consultation undertaken during 2011

In order to finalise the EPBC Act referral and ensure the ongoing protection of the PTWL, several meetings were held with DSEWPaC in early 2011. During this time, additional consultation and peer review was also undertaken with Dr Will Osborne, an expert on the PTWL in the ACT and surrounding region of NSW. Further consultation has been conducted more recently with Dr Osborne in relation to the specific measures contained within this PTWL-P&MP.

3.2 Public and agency comment on the draft PTWL-P&MP

In accordance with CoA 1, provision was made for public comment on the final draft PTWL-P&MP.

A copy of the final draft PTWL-P&MP was placed on public exhibition for a two (2) week period from 1 October to 14 October 2011. Public notices were placed in the Queanbeyan Age and Canberra Times newspapers advertising the commencement of the public exhibition period and providing details for the submission of response(s) following review of the PTWL-P&MP. An electronic copy of the PTWL-P&MP was also provided to DSEWPaC, Council, NSW Office of Environment and Heritage (Queanbeyan Office), Friends of Grasslands (FoG) and Dr Osborne for their review and comment.

Three (3) submissions were received on the review of the final draft PTWL-P&MP. Appendix B provides a list of the issues raised in the submissions received and their consideration. A number of minor amendments to this PTWL-P&MP have been undertaken following consideration of these submissions.

3.3 Ongoing review of this PTWL-P&MP

This PTWL-P&MP is subject to review at least every five (5) years. Reviews will be undertaken to provide for adaptive management and to ensure that the objectives of the PTWL Conservation Area are being suitably achieved. The review will be conducted by GTPL prior to handover to Council and by Council post handover. GTPL and Council may conduct the review in-house if suitable expertise is available or engage another suitably qualified specialist/organisation.

4. Summary of Management Actions and Responsibilities

A summary of the management actions and responsible parties for each management action is provided in Table 3. Timings noted start with the 'Year 0' (being the year that residential subdivision construction works first occur within 50 m of the identified PTWL habitat (refer to Figure 2 for the 'Year 0' trigger line). For example, if residential subdivision construction works commence beyond the 'Year 0' trigger line in 2015, then 'Year 1' becomes 2016 and thereon. As detailed in Section 2.2.1 and illustrated in Figure 5, whilst located within the 'Year 0' trigger line, the commencement of the establishment of the PTWL Conservation Area will not be triggered by the limited infrastructure construction works to occur for SPS2 and associated sewer mains.


Table 3: PTWL Conservation Area management summary

| Management action | Timing and details | Responsible party |
|---|--|----------------------------|
| Preparation of the PTWL-P&MP | Submission to the DSEWPac for Ministerial approval by 19 November 2011 (as per the requirements of Condition of Approval 1). | GTPL |
| Preparation of the PTWL-P&MP (referred to as an Aprasia Conservation Management Plan) | Prepared in consultation with OEH and DSEWPac and submitted to the Director-General for approval by the end of June 2012 (as per the requirements of CoA D9). | GTPL |
| Continuation of farming activities and retention of existing stock fencing | The current management and use of the PTWL Conservation Area for agricultural purposes (notably sheep grazing) will continue without substantial alteration until 'Year 0'. The existing stock fencing within the PTWL Conservation Area and immediate vicinity will remain without substantial alteration until 'Year 0'. Note: this does not preclude routine maintenance or replacement of the existing fences if required. | Private land owner/manager |
| Establishment and boundary fencing (Stage 1) | Precise boundary delineation to be determined during detailed design of the relevant section of Googong township. Fencing of the relevant section (Stage 1) of the PTWL Conservation Area to be constructed prior to residential subdivision construction works occurring within 50 m of the PTWL Habitat (refer to Figure 2 for the 'Year 0' trigger line). Relevant existing internal fencing will be removed. Existing fencing will be retained where required for access and land management purposes, particularly south of Montgomery Creek. A construction exclusion fence will be established between the sewer infrastructure construction footprint and the PTWL Conservation Area boundary. As illustrated in Figure 5, the fence will run parallel to and at least five metres from the PTWL Conservation Area boundary. The construction exclusion fence will be constructed of sturdy materials, fit for purpose and maintained for the duration of construction works. | GTPL |
| Weed removal, monitoring and management | Removal of woody weeds to be undertaken following the construction of the first section of PTWL Conservation Area fencing. | GTPL |



| Management action | Timing and details | Responsible party |
|---|--|---------------------------|
| | Small Serrated Tussock infestation to be eradicated within six (6) months following the approval of this PTWL-P&MP. | |
| | Monitoring and management of weeds to be conducted on an ongoing twice-annual basis by GTPL prior to handover and Council and by Council post handover. Commences in 'Year 1'. | GTPL & Council |
| Importation of habitat rocks | Suitable habitat rocks will be removed from the areas of habitat (refer to Figure 2) outside of the PTWL Conservation Area and scattered within the PTWL Conservation Area. This will occur primarily during the works undertaken for the construction of the edge road. Completed in 'Year 1'. | GTPL |
| Translocation of PTWL | In combination with the above importation of rocks, PTWL will be translocated from identified habitat areas (refer to Figure 2), prior to the commencement of construction in those areas. The PTWL removed will be immediately translocated into the PTWL Conservation Area and, to the extent possible, will occur during the suitable survey season for the species (i.e. during suitable weather in spring or autumn). Completed in 'Year 1'. | GTPL Engaged ecologist |
| Monitoring of PTWL abundance and distribution | The PTWL monitoring program will commence the spring following the first year of works within 50 m of the PTWL Conservation Area. The program will then occur every second year until handover of the PTWL Conservation Area to Council. Following handover to Council, the PTWL monitoring program will occur once every five (5) years in perpetuity. Commences in 'Year 1'. | GTPL & Council |
| Re-establishment and encouragement of native grasses. | Re-establishment and encouragement of native grasses throughout the areas disturbed during woody vegetation removal and rock placement will occur immediately following the completion of these works, or following the completion of the section of these works. Commences in 'Year 2'. | GTPL |
| Monitoring of native grass re-establishment | Monitoring of native grass re-establishment to be conducted on biannual basis by GTPL prior to handover. Council will conduct annual overview monitoring of the vegetation composition and condition throughout the PTWL Conservation Area post handover. Commences in 'Year 3'. | GTPL & Council |
| Boundary fencing (Stage 2) | Installation of Stage 2 of the PTWL Conservation Area fence (refer to Figure 4) will be undertaken prior to the commencement of construction works within 50 m of the PTWL Habitat (refer to Figure 2 for the 'Year 0' trigger line) south of Montgomery Creek. | GTPL |
| Physical removal of Radiata Pine and thinning of Burgan | Removal of Radiata Pine and thinning of Burgan will occur following construction of Stage 2 of the PTWL Conservation Area fence (noted above). | GTPL |

| Management action | Timing and details | Responsible party |
|-------------------------|---|---|
| Review of the PTWL-P&MP | The PTWL-P&MP will be reviewed at least every five (5) years. | GTPL will be responsible for this review prior to handover and Council will be responsible post handover. |

Figures






Legend

-  PTWL Conservation Area
-  Googong Township

Acknowledgement: Topo (c) NSW Land and Planning Information (2011);
 Overview (c) State of NSW (c.2003)

Figure 1: Locality plan


0 400 800 1,200 1,600

 Metres
 Scale 1:40,000 @ A4, GDA 1994 MGA Zone 55



Legend

- + 2013 PTWL Survey Record
- 2010 PTWL Survey Record
- Year 0 Triggerline
- Extent of PTWL Habitat
- PTWL Conservation Area
- PTWL Habitat Quality
- Low
- Medium
- High
- Very High
- Neighbourhood 1B Planning Structure
- Googong Township

Figure 2: PTWL Habitat Assessment





Scale: 1:6,000 @ A3
 Coordinate System: GDA 1994 MGA Zone 55



Ballarat, Brisbane, Canberra, Melbourne,
 Sydney, Wangaratta & Wollongong

Matter: 18082
 Date: 08 July 2014
 Checked by: RES, Drawn by: JMS, Last edited by: jshepherd
 Location: P:\18000s\18082\Mapping\18082_F2_PTWL_wPowerline_20140704



Legend



- Year 0 Triggerline
- Burgan Thinning
- Radiata Pine Removal
- Rock Placement
- PTWL Conservation Area
- E2 Zoning (LEP 2012)
- PTWL Conservation Area 20m intensive management buffer
- PTWL Habitat
- Neighbourhood 1B Planning Structure
- Googong Township

Figure 3: PTWL Conservation Area Protection and Management

0 60 120 180 240 300
 Metres
 Scale: 1:6,000 @ A3
 Coordinate System: GDA 1994 MGA Zone 55



Matter: 18082
 Date: 07 July 2014
 Checked by: RES, Drawn by: JMS, Last edited by: jshepherd
 Location: P:\18000s\18082\Mapping\18082_E3_PTWL_Management



Legend

- Year 0 Triggerline
- - - PTWL Conservation Area Fence - Stage 1
- - - PTWL Conservation Area Fence - Stage 2
- - - Googong Foreshore Fence - Stage 1
- - - Googong Foreshore Fence - Stage 3
- - - Existing Fences
- PTWL Conservation Area
- Neighbourhood 1B Planning Structure
- Googong Township

Figure 4: PTWL Conservation Area Fencing Plan

Disclaimer: Final boundaries are subject to final survey and design

0 60 120 180 240 300

Metres
Scale: 1:6,000 @ A3
Coordinate System: GDA 1994 MGA Zone 55

biosis
Biosis Pty Ltd
Ballarat, Brisbane, Canberra, Melbourne,
Sydney, Wangaratta & Wollongong

Matter: 18082
Date: 07 July 2014
Checked by: RES, Drawn by: JMS, Last edited by: jshepherd
Location: P:\18000s\18082\Mapping\18082_F4_PTWL_Fencing





Figure 5: Boundary Portion Detail - PTWL Conservation Area / Fire Trail



Ballarat, Brisbane, Canberra, Melbourne, Sydney, Wangaratta & Wollongong



Acknowledgements: Imagery (c) Nearmap 2012
Topo (c) NSW Land and Planning Information (2012)

Matter: 18082
Date: 07 July 2014,
Checked by: RES, Drawn by: JMS, Last edited by: jshepherd
Location: P:\18000s\18082\Mapping\18082_F6_PTWL_BoundDetail




Metres
Scale 1:1,500 @ A3
Coordinate System: GDA 1994 MGA Zone 55





- Legend**
- + 2013 PTWL Survey Record
 - 2010 PTWL Survey Record
 - Year 0 Triggerline
 - Extent of PTWL Habitat
 - PTWL Conservation Area
 - PTWL Habitat Quality
 - Low
 - Medium
 - High
 - Very High
 - Sewer Infrastructure
 - SPS2
 - Gravity sewer main
 - Sewer rising main
 - IWC Stage B network construction footprint
 - Gravity sewer main construction footprint
 - Construction exclusion fence

Figure 6: Sewer Infrastructure (SPS2 and Sewer Mains)



Scale: 1:1,500 @ A3
 Coordinate System: GDA 1994 MGA Zone 55



Ballarat, Brisbane, Canberra, Melbourne, Sydney, Wangaratta & Wollongong

Matter: 17162
 Date: 30 May 2014
 Checked by: RS, Drawn by: JMS, Last edited by: jshepherd
 Location: P:\18000s\18082\Mapping\18082_F5_Phase1ConsWorks

References

- ACT Government (2005) *'A Vision Splendid of the Grassy Plains Extended: ACT Lowland Native Grassland Conservation Strategy'*. Action Plan 28'.
- ACT Government (2007) *'Ribbons of Life: ACT Aquatic Species and Riparian Zones Conservation Strategy Action Plan 29'*. Arts Heritage and Environment, Canberra.
- ACT Government Territory and Municipal Services (2007) *Googong Foreshores Draft Plan of Management 2007*.
- Biosis Research & Ecwise Environmental (2009) *'Googong Water Cycle Project – Ecological Assessments – Terrestrial Flora and Fauna'*. A report to Canberra Investment Corporation.
- Brown GW (2010) *'National Recovery Plan for the Pink-tailed Worm-lizard Aprasia parapulchella'* (Draft for comment May 2010).
- Commonwealth of Australia (2008) *EPBC Act Policy Statement 1.1 Significant Impact Criteria*. Department of Environment, Water, Heritage and the Arts.
- DEC (2004) *Threatened Biodiversity Survey and Assessment: Guidelines for Developments and Activities - Working Draft*, <http://www.threatenedspecies.environment.nsw.gov.au/tsprofile/profile.aspx?id=10544>.
- DEC (2005) Pink-tailed Worm-lizard - Threatened Species Profile, <http://www.threatenedspecies.environment.nsw.gov.au/tsprofile/profile.aspx?id=10061>.
- DECC (2009) Pink-tailed Worm-lizard *Aprasia parapulchella* species profile, <http://threatenedspecies.environment.nsw.gov.au/tsprofile/profile.aspx?id=10061>.
- DEWHA (2008a) *Aprasia parapulchella* in Species Profile and Threats Database, http://www.environment.gov.au/cgi-bin/sprat/public/publicspecies.pl?taxon_id=1665.
- Jenkins BR (2000) *'Soil landscapes of the Canberra 1:100 000 Sheet.'* Department of Land and Water Conservation, Queanbeyan.
- Johnstone Centre (2004) *'Environmental Assessment – Googong Urban Investigation Area'*. A report to Willana Associates Pty Ltd.
- Jones SR (1992) *Habitat relationships, diet and abundance of the endangered Pygopodid (Aprasia parapulchella)*. B.App.Sc (Hons) thesis. Applied Ecology Research Group, University of Canberra.
- Jones SR (1999) *Conservation biology of the pink-tailed worm lizard (Aprasia parapulchella)*. PhD thesis, Applied Ecology Research Group, University of Canberra
- Navin Officer (2003) *'Googong Local Environmental Study – Cultural Heritage Component'*. A report to Willana Associates Pty Ltd.
- NSW Rural Fire Service (2006) *Planning For Bushfire Protection. A guide For Councils, Planners, Fire Authorities and Developers*.
- NSW Scientific Committee (2002) *Competition and Grazing by the Feral European Rabbit - Key Threatening Process Listing*, Department of Environment and Climate Change
- Osborne WS, et al. (1991) *'Distribution and conservation status of the endangered pink-tailed legless lizard (Aprasia parapulchella)'*. Research Report to ACT Parks and Conservation Service.

Osborne WS and Coghlan R (2004) '*Distribution of the Pink-tailed Worm Lizard in the Lower Molonglo Valley, ACT, with respect to strategic land planning*'. Applied Ecology Research Group, University of Canberra.

Osborne WS and Jones SR (1995) '*Recovery plan for the Pink-tailed Worm Lizard Aprasia parapulchella. Technical Report No.10.*' ACT Parks and Conservation Service.

Queanbeyan Local Environmental Plan 2012.

Rauhala M (1993) '*The reptile, amphibian and mammal fauna of the Stony Creek Nature Reserve, Australian Capital Territory. Technical Report No. 6.*' ACT Government.

Appendix A: Background to the PTWL at Googong

Description of the PTWL Conservation Area and Surrounds

The PTWL Conservation Area will encompass a section of Montgomery Creek and associated hillslopes and will incorporate approximately 52 ha of land located within the Queanbeyan River catchment, approximately 10 km south of Queanbeyan, New South Wales. The land to the west, northwest and south of the PTWL Conservation Area is, in its current form, predominantly cleared of native woody vegetation and has been subjected to grazing and pasture improvement.

Landform, topography and soils

The topography of the PTWL Conservation Area is dominated by a moderately to deeply incised section of the Montgomery Creek valley. The surrounding elevated lands to the west, north and south generally comprise gently undulating hills, which will be developed for Googong township. The elevation within the PTWL Conservation Area ranges from 720 m Australian Height Datum (AHD) along the western boundary to 640 m AHD at the point at which Montgomery Creek enters Googong Foreshores.

The geology of the local area consists of Silurian volcanics including the Colinton volcanics and the Capanana Formation (Jenkins 2000). There are various tuffs with minor siltstone, shale, sandstone and limestone (Jenkins 2000). Soils within the Study Area are shallow, infertile, strongly acidic and moderately drained, with outcropping granitic rock, predominantly granodiorite (Jenkins 2000).

Management history and current vegetation condition

The majority of Googong township was cleared of native tree cover by felling and firing carried out post European settlement of the area during the early to mid nineteenth century (Navin Officer 2003). The steepest sections of the Montgomery Creek hillslopes were not cleared, likely due to the skeletal nature of the soils and difficult topography. As is evidenced by the existence of granite tors, scattered surface rocks and the general unevenness of the landscape, it can be determined that the cleared land within and directly adjoining the PTWL Conservation Area has not been subject to cultivation or levelling. Excavation and soil movement within the vicinity of the PTWL Conservation Area appears to have been limited to that associated with the construction of dams across the branches of Montgomery Creek, upstream of the PTWL Conservation Area.

Notwithstanding the above, the PTWL Conservation Area and adjoining sections of Googong township have been subject to grazing (notably by sheep) at various intensities for an extended period, likely extending back to the onset of pastoralism post European settlement. The grassland/pasture throughout the more open and flat land located to the west, northwest and south of the PTWL Conservation Area has undergone substantial pasture improvement and modification. The resulting grassland/pasture in the pasture improved areas, whilst supporting a native grass component (i.e. primarily *Austrostipa* spp. and *Austrodanthonia* spp.), is dominated by exotic pasture grasses and weeds.

The groundstorey vegetation throughout the PTWL Conservation Area supports a much higher proportion and diversity of native grasses and forbs. Whilst much of the PTWL Conservation Area supports a component of exotic pasture grasses and weeds, native grasses and forbs represent a much larger component of the groundstorey biomass. Kangaroo Grass (*Themeda triandra*) and other native species more sensitive to intense grazing and elevated soil fertility, constitute a substantial component of the groundstorey biomass throughout much of the PTWL Conservation Area. No evidence is present to suggest that the land within the PTWL Conservation Area has been subject to a lower intensity grazing regime (i.e. sheep grazing appears to have occurred throughout the entire eastern section of Googong township). It can therefore be envisaged that the persistence of native grasses (notably Kangaroo Grass)

and forbs has occurred primarily through the exclusion of pasture improvement management practices carried out to elevate soil fertility ((i.e. spreading of fertiliser (especially superphosphate), incorporation of clover and other exotic pasture species, etc)).

A number of dense stands of Burgan (*Kunzea ericoides*) occur within the PTWL Conservation Area. Burgan is a large dense spreading Tea-tree like native shrub growing to approximately four metres in height. Generally considered a pioneer species, it vigorously occupies areas devoid of groundstorey vegetation and often inhibits the growth of native grasses and forbs.

With regard to the above, it can be determined that whilst the vegetation and landform within the PTWL Conservation Area have been impacted upon by a long history of grazing, the land and associated vegetation type and condition within the PTWL Conservation Area has not been degraded to the extent of that located throughout the surrounding areas of Googong township. The management of the PTWL Conservation Area for pastoral purposes has resulted in the introduction of exotic grasses, herbaceous and woody weeds and has reduced the dominance of native groundstorey vegetation. In this regard, it would reasonably be expected that the condition of the groundstorey vegetation and associated PTWL habitat value throughout the PTWL Conservation Area would continue to degrade if the past and current management regime was to be maintained into the future.

Ecology and Habitat of Pink-tailed Worm-lizard

The PTWL is a small fossorial reptile from the family Pygopodidae (legless lizards), which has a maximum snout vent length of 14 cm and a total length of about 24 cm. PTWL is oviparous (egg laying) with a clutch size of two. Females may need to reach an age of about three (3) or four (4) years before they can reproduce. There is little data on the breeding behaviour of this species (Osborne and Coghlan 2004). The PTWL is moderately common within the ACT region and is often the most abundant reptile at locations within its defined habitat type (Osborne et al. 1991).

The species lives beneath surface rocks and occupies ant galleries where it feeds on ants, particularly their eggs and larvae (Osborne and Jones 1995). Key habitat features for the presence of PTWL are a cover of native grasses (particularly Kangaroo Grass), sparse or no tree cover, little or no leaf litter, and scattered small rocks shallowly embedded in the soil surface (Osborne and Jones 1995).

In the Canberra region, the species is found in areas containing acid volcanic rock types - Late Silurian acid volcanics - that are derived from decomposing rhyodacite, rhyolite or dacite or other Silurian volcanic rocks (Osborne and Coghlan 2004). The distribution of the species is centred on the ACT and this appears to be related to less soil (and rock) disturbance evidenced by the presence of a native grass cover, particularly Kangaroo Grass, Red-leg Grass (*Bothriochloa macra*) and Wattle Mat-rush (*Lomandra filiformis*) (Osborne and Jones 1995). The likelihood of occurrence of PTWL increases with increasing cover of Kangaroo Grass, which is a key botanical indicator of suitable habitat in the ACT region, along with Red-leg Grass and Wattle Mat-rush (Jones 1992, 1999; Osborne & Coghlan 2004). Alternatively, dominance of speargrasses (*Austrostipa falcata*, *A. bigeniculata*) and Tussock Grass (*Poa labillardieri*) decreases the likelihood of finding the species (Osborne and Coghlan 2004; ACT Government 2007; ACT Government 2005).

PTWL habitat sites in the Queanbeyan region support native grassland, derived grassland and open and dry woodland habitats, usually with many loose and partially embedded rocks. Ground cover is typically dominated by Kangaroo Grass and wallaby grasses (*Astrodanthonia* spp.) (R. Rehwinkel pers. comm.). Open woodland habitats are dominated by Yellow Box (*Eucalyptus melliodora*) and Blakely's Red Gum (*E. blakelyi*), while dry forest areas are dominated by Broad-leaved Peppermint (*E. dives*) and Candlebark (*E. rubida*) (Brown 2010).

Notwithstanding, moderate numbers of disturbed sites dominated by exotic ground cover species, such as Wild oats (*Avena* spp.), Fescues (*Vulpia* spp.), Flat weeds (*Hypochaeris* spp.) and Bromes (*Bromus* spp.)

have been found to support at least some individuals, although it was not known if these sites support viable populations (Osborne and Coghlan 2004).

Distribution of Pink-tailed Worm-lizard

Regional

The PTWL occurs in south-eastern Australia, where it is widely but patchily distributed from Gunnedah in northern NSW through southern NSW and the ACT to Bendigo in central Victoria (Brown 2010). Other locations within this geographic area include near Cooma, Yass, Albury, Cootamundra, Tarcutta and Queanbeyan (DEWHA 2008a; DECC 2009). Records cover a wide altitudinal range, from about 200 m altitude near Bendigo to over 800 m altitude in the ACT (Brown 2010).

Locality

The PTWL is regarded as moderately common within the ACT and region where it has a wide and scattered distribution along the rocky hills and slopes of the Murrumbidgee, Molonglo and Queanbeyan River corridors (Brown 2010). The PTWL has been widely recorded throughout Googong Foreshores and surrounding areas (Johnstone Centre 2004). Surveys completed by the Johnstone Centre (2004) throughout the wider locality (encompassing Googong township) recorded seventeen individuals at two (2) locations: thirteen (13) within the “Talpa” property located within the Queanbeyan River catchment approximately two kilometres to the north of the Study Area; and, four within the “McLean” property located within the Jerrabomberra Creek catchment approximately three (3) kilometres to the west of the PTWL Conservation Area.

Habitat assessments carried out during broader ecological surveys completed by Biosis Research (2009) throughout Googong township identified the PTWL potential habitat associated with the lower reaches of Montgomery Creek. This potential habitat (in addition to the previously recognised potential habitat on Reservoir Hill) was surveyed by Biosis Research with two live PTWL and one slough (shed skin) being recorded within the area to become the PTWL Conservation Area (Biosis Research & Ecowise Environmental 2009). In order to more accurately determine the significance of the PTWL population occurring along Montgomery Creek, in spring 2010 GTPL commissioned Biosis to conduct intensive targeted surveys and prepare habitat quality mapping throughout the areas of previously identified potential habitat. Approximately 6,200 suitably sized shelter rocks were turned and 13 live *A. parapulchella* individuals and three sloughs (shed skins) were recorded.

Owing to the results and observations of the 2010 study and previous studies conducted by Biosis Research (2009) and the Johnstone Centre (2004), the PTWL habitat associated with the lower reaches of Montgomery Creek is considered to constitute the only considerable area of PTWL habitat within Googong township.

Threats to Pink-tailed Worm-lizard

The main threats to PTWL as described in the ‘National Recovery Plan for the Pink-tailed Worm-lizard *A. parapulchella* (Draft)’ (Brown 2010) are:

- Habitat loss and fragmentation;
- Removal of rocks;
- Heavy grazing and trampling;
- Invasion of habitat by weeds;
- Modification of habitat i.e. tree planting, invasion of woody shrubs in native grasslands;

-
- Changed fire regimes, which lead to a change in vegetation structure;
 - Recreational activities; and
 - Predation by introduced predators.

Appendix B: Submissions received during Public Exhibition of the PTWL-P&MP

A copy of the final draft Pink-tailed Worm-lizard Protection and Management Plan (PTWL-P&MP) was placed on public exhibition for a two (2) week period from 1 October to 14 October 2011. Public notices were placed in the Queanbeyan Age and Canberra Times advertising the commencement of the public exhibition period and providing details for the submission of response(s) to the PTWL-P&MP. An electronic copy of the PTWL-P&MP was also provided to DSEWPaC, Queanbeyan City Council, NSW Office of Environment and Heritage (Queanbeyan Office), Friends of Grasslands (FoG) and Dr Will Osborne for their review and comment. Table 4 below provides a list of the issues raised in the three (3) submissions received and appropriate consideration of these issues. Minor amendments to the PTWL-P&MP have been undertaken following the consideration of these submissions.

Table 4: Issues raised in submissions received during the exhibition of the final draft PTWL-P&MP

| Issue raised / opinion provided | Consideration and response |
|---|---|
| Friends of Grasslands (FoG) | |
| <p>FoG provided the following points regarding the PTWL-P&MP:</p> <ol style="list-style-type: none"> 1. No concerns raised and statement the plan covers all of the elements that FoG considers important in conserving the PTWL and maintaining its habitat. 2. Support the inclusion of the 20 m buffer zone outside the area defined as 'high quality PTWL habitat'. 3. Express an interest in viewing the results of the proposed PTWL monitoring program. | <p>The approved PTWL-P&MP and any associated monitoring results will be provided on Googong website.</p> |
| Submission from member of the public | |
| <p>Mountain bikes (MTB) track construction and formal access (pedestrian) tracks are not included as an identified threat in the plan. The issue of erosion caused by the creation of any informal tracks (caused by walkers or MTBs) within the PTWL Conservation Area is not defined.</p> | <p>The purpose of the PTWL Conservation Area is to conserve, protect and manage a substantial and viable area of PTWL habitat specifically for the conservation of this species. Whilst people will not be specifically excluded from the PTWL Conservation Area (access will be provided from Googong Foreshores), the area is not proposed to become a reserve with 'park-like' facilities, aimed at catering for pedestrian or other recreational access or usage.</p> <p>A maintained 20 m buffer zone along the perimeter of the PTWL Conservation Area will be provided primarily to reduce 'edge effects'. It also will enable access to the area for walking and serve as an asset protection zone (APZ). No formed access tracks are proposed within the PTWL Conservation Area for pedestrian / MTB (or other) usage.</p> |

| Issue raised / opinion provided | Consideration and response |
|--|---|
| | <p>MTB and pedestrian access is unlikely to result in significant disturbance to the PTWL Conservation Area or the PTWL protected within. Furthermore, the construction of any formal (formed) access tracks within the PTWL Conservation Area would result in significantly more disturbance and disconnection of PTWL habitat than that caused by informal tracks that may be created by pedestrians or occasional MTB passage.</p> <p>As detailed in this PTWL-P&MP, the monitoring of the vegetation cover and composition and the PTWL population within the PTWL Conservation Area will be undertaken to ensure that the objectives set out in the PTWL-P&MP are achieved.</p> <p>Section 2.2.1 of this PTWL-P&MP has been amended to reflect the above (i.e. that no additional formed access tracks will be established within the PTWL Conservation Area).</p> |
| <p>Use of imported topsoil for restoration between the proposed road and the PTWL habitat fence (of the PTWL Conservation Area) would result in weeds.</p> | <p>The PTWL-P&MP does not specify the use of 'imported' topsoil for restoration in this area. The PTWL-P&MP specifies the requirement for the topsoil to not be contaminated with weed seed.</p> <p>However, the concern regarding the potential for nutrient enrichment and associated proliferation of weeds is valid. As such, Section 2.2.1 has been amended to state 'In order to avoid the establishment of additional exotic plants and to prevent increases in the proportion of those already present, disturbance to the topsoil between the edge road and the PTWL Conservation Area boundary fence will be minimised. Should the placement of additional soil be required in this area, this soil will be sourced from adjacent areas and the area reseeded using endemic grass seed. The use of soil sourced in this manner will assist in preventing the introduction of ensure that no additional exotic plant species are introduced into the locality.'</p> |
| <p>The loss of any medium or high value habitat should not occur due to the proposal. The location of the proposed fencing should be situated 20 m from the (blue) 'Year 0' trigger line (Figures 2 and 3) and be extended to meet the existing (Googong Foreshores) fence line in the south of the proposed PTWL Conservation Area.</p> | <p>The establishment, improvement and management of the PTWL Conservation Area will occur as an 'offset' for the impacts upon PTWL that will result from the development of Googong township. The PTWL Conservation Area and its delineation has been determined and agreed in consultation with DSEWPaC (and other stakeholders) throughout the EPBC Act referral process. The delineation and proposed establishment of the PTWL Conservation Area was also independently reviewed and endorsed by a recognised authority on the conservation of the species (Dr W. Osborne). Whilst the establishment of the PTWL Conservation Area will result in the removal of some areas of 'High' or 'Medium' quality habitat, all areas of 'Very High' quality habitat will be retained, as considerable improvement of habitat quality and connectivity is a primary objective of the design and establishment of the PTWL Conservation Area and this PTWL-P&MP.</p> <p>As stated in this PTWL-P&MP, the overarching objective of the PTWL Conservation Area is to provide a 'balanced outcome of urban development and a consolidated, contiguous PTWL Conservation Area that reduces habitat fragmentation and improves habitat quality for the species in the long term'. The approved design of the PTWL Conservation Area has been determined in order to specifically meet this outcome.</p> <p>No change to the PTWL-P&MP is required to address this issue.</p> |

| Issue raised / opinion provided | Consideration and response |
|---|---|
| NSW Office of Environment and Heritage (OEH)(Queanbeyan Office) | |
| The commencement date for implementation of the PTWL-P&MP should be within 2 years of consent. | <p>The schedule for implementation of this PTWL-P&MP has been determined in accordance with the schedule for the staged development of Googong township. This staged development and the corresponding staged establishment of the PTWL Conservation Area is in accordance with the EPBC Act Conditions of Approval.</p> <p>The immediate establishment and management of the PTWL Conservation Area is impracticable and unnecessary given the existing landuse and management within and directly adjoining the PTWL Conservation Area will not substantially change in the years prior to the establishment of the PTWL Conservation Area (i.e. the land will continue to be fenced and managed for agricultural purposes, primarily grazing). The extended past period of this landuse and management has not prevented the persistence of a viable population of PTWL within a substantial area of high quality PTWL habitat.</p> |
| Removal of bush rock should be identified as a management priority. | <p>Whilst bush rock removal is recognised as a key threatened process to PTWL, the fencing type and schedule detailed in Section 2.2.1 will prevent unauthorised vehicular or pedestrian access to the PTWL Conservation Area. The collection of rocks from the PTWL Conservation Area and removal on foot via Googong Foreshores would be entirely impractical and therefore is not a considerable risk. Prior to development, the land adjacent to the PTWL Conservation Area will remain private property managed for agricultural purposes. Fencing of the relevant boundary section will be completed prior to the commencement of the adjacent residential development. As such, at no point prior to or following establishment of the PTWL Conservation will unauthorised vehicular access be permitted or be reasonably practical.</p> <p>Section 2.1.4 of the PTWL-P&MP has been amended to specifically address management of bush rock removal.</p> |
| The legal mechanism and the structures behind the conservation agreement should be strengthened to ensure the reserve is secured in perpetuity. | <p>The PTWL Conservation Area is a biodiversity offset for Googong township and this area and its delineation has been determined and agreed in consultation with DSEWPaC (and other stakeholders) throughout the EPBC Act referral process. The establishment of the PTWL Conservation Area was based on recommendations to exclude any development from areas identified as 'Very High' quality PTWL habitat and the objective of providing a balanced outcome between development and the long term improvement of PTWL habitat and reduction in fragmentation of the species, whilst assisting in maintaining connectivity.</p> <p>In addition, the PTWL Conservation Area will be handed over to Council and a plan of management in accordance with the requirements of the <i>Local Government Act 1993</i> will be prepared to provide for the protection of the land and the species in perpetuity. The irrevocable dedication of the PTWL Conservation Area to Council will ensure the area will not be used for another purpose in the future.</p> <p>Section 2.4.5 of the PTWL-P&MP provides details of the legal mechanisms to protect the PTWL Conservation Area in perpetuity.</p> |
| Long-term funding availability. | The long-term management and associated funding of the PTWL Conservation |

| Issue raised / opinion provided | Consideration and response |
|---|---|
| | <p>Area has been guaranteed through the development of a Voluntary Planning Agreement (VPA) between GTPL and Council made in accordance with the <i>Environmental Planning and Assessment Act 1979</i>. The VPA specifies the funding arrangements for the PTWL Conservation Area (and the overall Googong township) and provides that GTPL are to maintain all costs associated with the establishment and ongoing management PTWL Conservation Area until the last residential lots in the township are created (an approximate duration of 25 years). It is noted that any development within Googong township is unable to proceed unless it is in accordance with the requirements of this VPA.</p> <p>Section 2.4.5 has been amended to state the above.</p> |
| <p>Monitoring plots should be established to enable replication and to prevent wide spread habitat disturbance.</p> | <p>Monitoring survey effort will be expended in a manner that provides a sample of habitat qualities ranging from 'Medium' to 'Very High', and specifically encompassing areas where habitat creation/improvement (i.e. rock placement areas and native grass re-establishment areas) has occurred.</p> <p>The PTWL monitoring program has been designed in a manner that will involve a measured amount of survey effort (i.e. 15 hours per monitoring event) spread at low intensity across the entire PTWL Conservation Area. Given the inherent disturbance to habitat involved in rock turning surveys, this approach will spread the disturbance across a large area, and thereby, prevent the same specific areas being disturbed repetitively (as would be the case if defined survey plots were established). Repetitive and high intensity turning of rocks is known to substantially disturb PTWL habitat and reduce the likelihood of PTWL inhabitation of the specific rocks (Dr W. Osborne pers. comm; R. Speirs pers. obs.). In this regard, repetitively surveying the same plots of habitat for PTWL would likely result in progressively lower numbers being recorded. Such results would provide inaccurate indications regarding actual population numbers and the success of the establishment and management of the PTWL Conservation Area.</p> <p>The results of each monitoring event will be provided for inclusion in the NSW Wildlife Atlas, as per the standard conditions of the scientific licence held by the ecologist/zoologist engaged to conduct the monitoring.</p> <p>The PTWL monitoring program will provide invaluable data regarding the continued viability of the population, and hopefully, will illustrate that the conservation and protection of the PTWL Conservation Area (and associated works) has increased the size and secured the viability of the population in the long-term.</p> <p>Whilst the PTWL monitoring program will be conducted in accordance with the above, a degree of flexibility will be maintained to allow for adaptive management and for the incorporation of new or better survey techniques should these become known/developed in the future.</p> <p>Section 2.3.3 of the PTWL-P&MP has been amended to state the above.</p> |
| <p>Areas of imported rock should be identified as suitable areas for potential translocation of PTWL.</p> | <p>It is agreed that the use of the areas where imported rock has been placed will be the most suitable areas for the release of PTWL during future translocation of PTWL into the PTWL Conservation Area.</p> <p>Section 2.2.4 has been amended to include the following: 'To prevent increases in</p> |

| Issue raised / opinion provided | Consideration and response |
|---|---|
| | <p>competition in areas of existing habitat within the PTWL Conservation Area, all individuals translocated into the PTWL Conservation Area will be released in the areas of newly created/improved habitat (i.e. areas where imported rocks have been placed).</p> |
| <p>Weed management to commence as soon as possible.</p> | <p>Of the weed species present within and in the vicinity of the PTWL Conservation Area, only Serrated Tussock (approximately 50 plants were identified in November 2010) is considered to have the potential to substantially increase in abundance in the period preceding the establishment of the PTWL Conservation Area. The additional exotic flora species occurring within the PTWL Conservation Area are common agricultural weeds and pasture species unlikely to increase in prevalence whilst the land use and management regime remains largely unchanged.</p> <p>A targeted weed removal program (spot spraying) has been implemented to control the Serrated Tussock located along the Montgomery Creek riparian zone within the PTWL Conservation Area. In January 2013 the 50 plants were located and sprayed with Glyphosate (with blue marker dye). These plants will be checked during spring 2013 to ensure a thorough kill was achieved. Any plants remaining alive and any others located within the PTWL Conservation Area will were sprayed at this time.</p> <p>Section 2.2.2 of the PTWL-P&MP has been amended to reflect the above.</p> |
| <p>Asset Protection Zone must be mapped in the plan.</p> | <p>The precise location and extent of the Asset Protection Zone (APZ) to be located along the interface between the PTWL Conservation Area and the adjacent Googong township residential (subdivision) area is unable to be specified, as the detailed design for the subdivision has not been determined. However, where required, the 20 m wide buffer zone will form part of the APZs for the adjacent residential properties and, as such, will be managed as an Outer Asset Protection Area (in accordance with the Planning for Bushfire Protection A Guide for Councils, Planners, Fire Authorities and Developers, NSW Rural Fire Service, 2006), which entails maintaining fuel loads at less than eight (8) tonnes per hectare (ha). The manner in which this 20 m wide buffer zone may be managed for asset protection purposed is detailed in Section 2.2.1.</p> <p>No change to the PTWL-P&MP is required to address this issue.</p> |
| <p>Signage and walking trails to be erected to control disturbances to the reserve.</p> | <p>The purpose of the PTWL Conservation Area is to conserve, protect and manage a substantial and viable area of PTWL habitat specifically for the conservation of this species. Whilst people will not be specifically excluded from the PTWL Conservation Area (access will be provided from Googong Foreshores), the area is not proposed to become a reserve with 'park-like' facilities, aimed at catering for pedestrian or other recreational access or usage.</p> <p>No formed access tracks will be established within the PTWL Conservation Area. Signage will be located at strategic locations along the boundary of the PTWL Conservation Area to advise the purpose of the PTWL Conservation Area and be provided as part of the overall education program to be implemented by GTPL for Googong township. Section 2.3.6 of this PTWL-P&MP provides details in relation to the above.</p> |

| Issue raised / opinion provided | Consideration and response |
|--|--|
| | No change to the PTWL-P&MP is required to address this issue. |
| Thinning of <i>Kunzea eriocoides</i> needs to be assessed. | <p>The thinning of dense clumps of Burgan (<i>Kunzea eriocoides</i>) will occur as it will reduce shading of PTWL habitat, encouraging the growth of Kangaroo Grass and other native groundstorey species, which increase habitat quality for the PTWL. Reduced shading also increases the thermoregulatory benefit offered by habitat rocks to PTWL, and thus, increases their utilisation of these important habitat features. It should be noted, however, that the thinning of Burgan will not become a widespread operation, nor will it aim to remove or substantially reduce the presence of the species within the PTWL Conservation Area or the very extensive adjoining Googong Foreshores.</p> <p>Section 2.2.3 of the PTWL-P&MP has been amended to provide additional detail regarding the above.</p> |

Appendix C: Submissions received during consultation under Part 3A Project Approval

The Part 3A Project Approval was not issued at the time of NSW Office of Environment and Heritage's review of the PTWL-P&MP approved by DSEWPaC on 17 July 2012. Therefore, as required under the Part 3A Project Approval CoA D9, a copy of the DSEWPaC approved PTWL-P&MP was provided to the NSW Office of Environment and Heritage (Queanbeyan Office) on 16 October 2012. Comments were received from NSW Office of Environment and Heritage (Queanbeyan Office) on 26 November 2012.

Table 5 below provides a list of the issues raised by the NSW Office of Environment and Heritage (Queanbeyan Office) and appropriate consideration of these issues. Minor amendments to the final PTWL-P&MP (to become Final – Version 3) were undertaken following consideration of the submission.

Table 5: Issues raised in comments received from NSW Office of Environment and Heritage

| Issue raised / opinion provided | Consideration and response |
|---|--|
| NSW Office of Environment and Heritage (November 2012) | |
| Monitoring of PTWL abundance and distribution in the Conservation Area commence as soon as possible | <p>In light of the advice and request provided by the OEH, Googong Township Pty Ltd (GTPL) agreed to commission an additional monitoring event in Spring 2013. The purpose of this monitoring event was to collect baseline PTWL population data (as per the specifications provided in the PTWL-P&MP) prior to any potential impacts from the early stages of Googong township being felt within the PTWL Conservation Area. It is understood that with the addition of this spring 2013 monitoring event, the OEH will not require any other monitoring events prior to those required in accordance with the approved PTWL-P&MP.</p> <p>Section 2.3.3 of the PTWL-P&MP has been updated to reflect the commitment to an additional monitoring event in Spring 2013. The results of the Spring 2013 monitoring event have been added to Figure 2 for Version 4 of this PTWL-P&MP</p> |
| Similarly, the fencing and signage around the PTWL conservation area should be established prior to the first residents moving into the development to ensure the area is clearly identified and protected and that even the first residents are aware of the value and importance of this area | <p>The timing specified in this PTWL-P&MP for the establishment of the fencing and signage along the interface between the PTWL Conservation Area and adjacent development will result in its establishment prior to the public being able to access the area. Until such time as the trigger for 'Year 0' is reached, and the corresponding fencing requirements fulfilled, the land encompassed by the PTWL Conservation Area and adjoining areas will remain as private rural grazing land, not legally accessible to the public. It is understood that this has provided the clarification the OEH required regarding the timing of fence and signage establishment. Accordingly, no amendment to the PTWL-P&MP is proposed.</p> |

Appendix D: Section 88B Instrument

INSTRUMENT SETTING OUT TERMS OF EASEMENTS, POSITIVE COVENANTS AND RESTRICTIONS ON USE INTENDED TO BE CREATED PURSUANT TO SECTION 88B AND SECTION 88BA, CONVEYANCING ACT, 1919

Lengths are in metres:

(Sheet 1 of 4)

Plan: DP []

Plan of subdivision of []
covered by subdivision certificate no.

Full name and address of proprietor of the land:

Googong Township Pty Limited
ACN 154 515 593
Level 3, 64 Allara Street
Canberra ACT 2600

Full name and address of mortgagee of the land:

[]
[]
[]
[]

PART 1 - CREATION

| Number of item shown in the intention panel on the plan: | Identity of easement or positive covenant to be created and referred to in the plan: | Burdened lot(s) or parcel(s): | Benefited lot(s), road(s), bodies or Prescribed Authorities |
|--|--|-------------------------------|---|
| 1. | Positive covenant (A) | [Lot 14 in DP 1164687] | Lot 7 in DP 592796 |
| 2. | Positive covenant (B) | [Lot 15 in DP 1164687] | Lot 7 in DP 592796 |

PART 1A - RELEASE

| Number of item shown in the intention panel on the plan: | Identity of easement or positive covenant to be released and referred to in the plan: | Burdened lot(s) or parcel(s): | Benefited lot(s), road(s), bodies or Prescribed Authorities |
|--|---|-------------------------------|---|
| 3. | | | |


PART 2 - TERMS

1. Interpretation

1.1 Definitions

These meanings, in any form, apply unless the contrary intention appears:

Authority means any governmental or semi-governmental or local government authority,




SHORT BOUNDARYS

| Ref | Bearing | Distance | Ref | Bearing | Distance | Ref | Bearing | Distance |
|-----|------------|----------|-----|------------|----------|-----|------------|----------|
| 1 | 219°25'20" | 5.935 | 34 | 244°50'10" | 28.87 | 67 | 93°59'10" | 8.345 |
| 2 | 204°51' | 3.92 | 35 | 234°25' | 20.82 | 68 | 93°59'10" | 15.765 |
| 3 | 193°36' | 3.92 | 36 | 234°25' | 6.84 | 69 | 142°00'50" | 19.515 |
| 4 | 182°21'20" | 3.92 | 37 | 234°25'00" | 5.32 | 70 | 107°31'50" | 14.64 |
| 5 | 168°36'10" | 11.035 | 38 | 231°36'30" | 12.125 | 71 | 109°09'40" | 18.88 |
| 6 | 165°38' | 8.345 | 39 | 231°36'30" | 74.92 | 72 | 144°01'40" | 18.63 |
| 7 | 158°36'40" | 1.795 | 40 | 207°02'10" | 26.33 | 73 | 131°59'40" | 15.57 |
| 8 | 158°36'40" | 8.905 | 41 | 198°32'50" | 46.265 | 74 | 152°58'10" | 12.395 |
| 9 | 165°51'50" | 8.68 | 42 | 229°53' | 23.41 | 75 | 164°11'10" | 16.925 |
| 10 | 180°32'20" | 8.46 | 43 | 227°47'20" | 25.21 | 76 | 122°19'40" | 32.625 |
| 11 | 181°44'20" | 13.79 | 44 | 207°26'10" | 34.675 | 77 | 131°39'50" | 13.8 |
| 12 | 174°51'20" | 3.92 | 45 | 177°28'30" | 79.865 | 78 | 116°06' | 17.355 |
| 13 | 166°21'50" | 5.61 | 46 | 168°29' | 30.315 | 79 | 153°17' | 21.66 |
| 14 | 165°44' | 10.26 | 47 | 168°29' | 41.37 | 80 | 119°49'50" | 18.285 |
| 15 | 156°06'20" | 3.92 | 48 | 170°22'10" | 27.465 | 81 | 151°00'30" | 35.46 |
| 16 | 147°33' | 13.465 | 49 | 97°27'50" | 10.43 | 82 | 117°41'30" | 25.205 |
| 17 | 166°56'20" | 9.175 | 50 | 97°27'50" | 30.125 | 83 | 132°42' | 19.94 |
| 18 | 170°11'50" | 11.915 | 51 | 97°27'50" | 13.61 | 84 | 129°10' | 30.275 |
| 19 | 172°24'30" | 14.195 | 52 | 97°27'50" | 16.68 | 85 | 115°04'40" | 13.3 |
| 20 | 168°51'50" | 16.495 | 53 | 97°27'50" | 14.005 | 86 | 115°04'40" | 17.395 |
| 21 | 167°15'20" | 9.01 | 54 | 26°14'20" | 7.115 | 87 | 95°57'40" | 30.225 |
| 22 | 177°58'30" | 12.0 | 55 | 33°24'30" | 2.16 | 88 | 88°57'30" | 32.385 |
| 23 | 170°50'10" | 13.625 | 56 | 33°24'30" | 18.06 | 89 | 84°19'40" | 37.0 |
| 24 | 169°12'50" | 80.40 | 57 | 39°30'40" | 11.245 | 90 | 79°19'40" | 6.28 |
| 25 | 259°24'50" | 76.995 | 58 | 47°40'20" | 9.025 | 91 | 79°19'40" | 18.525 |
| 26 | 255°20'20" | 6.535 | 59 | 52°34'20" | 18.95 | 92 | 58°18'10" | 18.22 |
| 27 | 254°05'50" | 17.03 | 60 | 59°33'50" | 10.12 | | | |
| 28 | 254°05'40" | 15.48 | 61 | 64°44'20" | 5.38 | | | |
| 29 | 334°38'10" | 30.965 | 62 | 64°44'20" | 3.395 | | | |
| 30 | 313°55'30" | 27.375 | 63 | 64°44'10" | 2.615 | | | |
| 31 | 302°44'50" | 19.01 | 64 | 72°02'20" | 18.95 | | | |
| 32 | 302°44'50" | 33.105 | 65 | 81°28' | 20.22 | | | |
| 33 | 260°16'50" | 41.2 | 66 | 89°04'20" | 11.39 | | | |

SSM 159149 - PM 161690 90°14'45" 540.18 MGA

NOTES:
(A) POSITIVE COVENANT
(B) POSITIVE COVENANT



SURVEY PRACTICE REGULATIONS 2006 CLAUSE 35 (1) AND CLAUSE 61(2)

| MARK | MGA CO-ORDINATES ZONE 55 | | CLASS | ORDER | METHOD | ORIGIN |
|---|--------------------------|------------|-------|-------|--------------------|--------|
| | EASTING | NORTHING | | | | |
| CP87270920 | 701796.70 | 6078534.92 | D | 4 | SCIMS | FOUND |
| CR 65 | 703090.86 | 6078710.13 | D | 4 | SCIMS | FOUND |
| CR 67 | 703719.66 | 6078370.28 | D | 4 | SCIMS | FOUND |
| COMBINED SEA LEVEL AND SCALE FACTOR 0.99999 | | | | | | |
| SOURCE: SCIMS ON LINE 6/03/2008 | | | | | | |
| SSM 159149 | 702625.25 | 6078633.13 | D | NA | CADASTRAL TRAVERSE | FOUND |
| PM 161690 | 703165.43 | 6078630.81 | D | NA | CADASTRAL TRAVERSE | FOUND |

Table of mm

| | | | |
|--|---|---|----------------------|
| Surveyor: Michael Roy Stapleton Date of Survey: 11 JUNE 2012 Surveyor's Ref: 03074L CHECKLIST 2010M7100(1023) Partial Survey | PLAN OF LAND BURDENED BY COVENANT OVER LOTS 14 AND 15 DP 1164687 | LGA: QUEANBEYAN CITY Locality: GOOGONG Subdivision No: N/A Lengths are in metres Reduction Ratio 1:15000 | Registered DP |
|--|---|---|----------------------|