
	11 315m ² 7773 78
A15m ² 77	12
	Stage 24
	2521 A126 A301715
	2300m ² 230 300m ² 230 300 300 300 300 300 300 300 300 300

Plan of Development Table	Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Courtyard Allotments			
	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor		
Front Setback										
Living	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m		
Garage	4.9m*	n/a	4.9m*	n/a	4.9m*	n/a	4.9m*	n/a		
Corner Allotments										
Secondary Road Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m		
Rear Setback										
Rear	0.9m	1.0m	0.9m	1.0m	0.9m	1.0m	0.9m	1.0m		
Side - General Lots										
Built to Boundary	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m		
	Optional		Optional		Optional		Optional			
Non Built to Boundary	0.9m	0.9m	1.0m	1.0m	1.0m	1.0m	1.0m	1.5m		
Garage Location	Preferred Garages are to be located along the built to boundary wall or if no BTB wall on Western or Southern Boundary or Low Side of the Allotment.									
On site parking requirements (minimum)	2 car parking spaces with 1 space to be covered and enclosed Single, tandem or double garage acceptable									
Site Coverage (maximum)	60% for Lots 600m ² or less; 50% for Lots greater than 600m ²									

Note: * Garage or Carport Door



PLAN REF: DATE: CLIENT: DRAWN BY: CHECKED BY: MD

132030-120C 30 October 2019 PEET LZ

Legend

Site Boundary 🛑 🛑 Proposed Stage Boundary Entry Statement Area Subject to Subsidence Pedestrian Link Sports Park

Allotment Details

Preferred Private Open Space Location

_____ Maximum Building Location Envelope

Optional Built to Boundary Wall **VV** Preferred Garage Location

All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.

Dimensions have been rounded to the nearest 0.1 metres.

Areas have been rounded down to the nearest 5m².

The boundaries shown on this plan should not be used for final detailed engineers design.

Disclaimer Insert Hyperlink

Source Information: Site boundaries: Saunders Havill. Adjoining information: DCDB. Contours: QSpatial

 Revision:

 A:20/08/19
 POD Setback Amendments
B:27/09/19 Stage 26 Amendments



URBAN DESIGN Level 4 HQ South 520 Wickham Street PO Box 1559 Fortitude Valley QLD 4006 **T** +61 7 3539 9500 W rpsgroup.com



© COPYRIGHT PROTECTS THIS PLAN Unauthorised reproduction or amendment not permitted. Please contact the author.