

Development Control Notes General

- 1. All development is to be undertaken in accordance with the Development Approval.
- Building setbacks and built-to-boundary wall 2. locations shown are subject to future proposed easements and/or underground services.
- 3. The maximum height of buildings shall not exceed 8.5m and two (2) storeys, except when existing grades exceed 15% where the building may be up to 10m and 2 storeys in height.
- 4. The maximum site coverage for each lot is to be in accordance with the Plan of Development Table.

Setbacks

- 5. Setbacks are as per the Plan of Development Table 9. unless otherwise specified.
- 6. Setbacks are measured to outer most projection (OMP).
- 7. First floor setbacks must not exceed the minimum ground floor setbacks.

- 8. In the case of corner allotments an additional setback from the street corner is applicable. The setback applies to any building or structure greater than 2m high as follows:
 - In the case of Villa and Premium Villa Corner Lots the setback is measured as the line that joins the points on the front and side street boundaries of the lot that are located 6m back from the point of intersection of these two boundaries.
 - In the case of Courtyard, Premium Courtyard and Duplex Corner Lots the setback is measured as the line that joins the points on the front and side street boundaries of the lot that are located 9m back from the point of intersection of these two boundaries.
- Where Built to Boundary walls are not adopted side setbacks shall be in accordance with the Plan of Development Table.
- 10. Built to Boundary walls are to have a maximum length of 9 metres and a maximum height of 4.5 metres.

Outdoor Living Space

11. Private outdoor living space, must be provided for each dwelling, not less than 20m² in area with a minimum dimension of 3.0m.

Buildings facing a park or more than one street

12. Dwellings on lots with more than one frontage to a public right of way (including a road, bikeways, public footpath or the like) must address all public frontages.

Parking and Driveways

Garages:

- 13. Garages must not project forward of the main facade (front wall) of the dwelling.
- 14. Unless otherwise stated, the garage door or parking structure shall occupy no more than 50% of the street frontage for all lots up to 450m² in area, provided that the garage or parking structure is not located forward of the main building line of the dwelling.

Driveways:

- 15. A maximum of one driveway per dwelling is permitted.
- 16. The maximum width of a driveway where crossing the verge:
 - shall be 3.5m for single garages; and
 - 4.8m for double garages.

Definitions

Site Cover - the total area of the roof of the dwelling expressed as a percentage of the lot area, but which excludes eave overhangs.




Table	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor
Front Setback			i i i i i i i i i i i i i i i i i i i					
Living	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m
Garage	4.9m*	n/a	4.9m*	n/a	4.9m*	n/a	4.9m*	n/a
Corner Allotments								
Secondary Road Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	3.0m	3.0m /
Rear Setback								
Rear	0.9m	1.0m	0.9m	1.0m	0.9m	1.0m	1.0m	2.0m
Side - General Lots								
Built to Boundary	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	n/a	n/a
	Optional		Optional		Optional		0.0m	
Non Built to Boundary	0.9m	0.9m	1.0m	1.0m	1.0m	1.0m	1.2m	2.0m
Garage Location	Preferred Garages are to be located along the built to boundary wall or if no BTB wall on Western or Southern Boundary or Low Side of the Allotment.							
On site parking requirements (minimum)	2 car parking spaces with 1 space to be covered and enclosed Single, tandem or double garage acceptable1 space to be covered and enclosed per dwellin						ed and	
Site Coverage (maximum)	60% for Lots 600m ² or less; 50% for Lots greater than 600m ²							
Note: * Garage or Carport Door								

	Local Authority. Ipswich City	swich City Council		ALLOTMENT LAYOUT		1 : 500	A1	132030 -	22	С	
	Locality. Redbank Plains	DWG Name. 132	2030-Edens Stg1-7 ROL		STAGE 8	-	Scale	Sheet	Plan Ref		Rev
	Chk'd By. AZ	Naturally connected		PLAN OF DEVELOPMENT			not permitt	not permitted. Please contact the author.		W rpsgroup.com.au	
	Comp By. WNW	CR ₂ SSING			RPS		RIGHT PROTECTS THIS PLAN sed reproduction or amendment ed. Please contact the author.	T +61 7 3124 9300 F +61 7 3124 9399			
B: 04/10/16 Update Client Details C: 14/10/16 Amend Lot Codes & Pavement	Job Ref. 132030-1		TUEN 5				DDC	ACN 1		Brisbane Desig 455 Brunswick Fortitude Valley	Street
A: 15/09/16 Amend Allotments for Engineering	Date. 14 OCLODET 2016							550 4		Urban Desi	