Planning and Environment Act 1987 Wyndham Planning Scheme

Approved Plan As Required under Condition 35 Permit No WYP6865/13 Date 27/07/2020

GENERAL NOTES:

- ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM AND ALL COORDINATES ARE TO MAP GRID OF AUSTRALIA (MGA) ZONE 55.
- 2. ALL EXISTING SURFACE LEVELS SHOWN ON THE ENGINEERING DRAWINGS HAVE BEEN INTERPOLATED FROM A DIGITAL TERRAIN MODEL. THESE LEVELS HAVE BEEN USED AS THE BASIS FOR ALL ENGINEERING DESIGN AND DETERMINATION OF QUANTITIES AND ARE ACCURATE TO WITHIN ±0.05m.
- ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PEET'S MODIFIED AS4000-1997 -AMENDED FROM GENERAL CONDITIONS OF CONTRACT FOR USE IN VICTORIA, THE ROAD & DRAINAGE SPECIFICATION, APPROVED MUNICIPALITY SPECIFICATIONS AND STANDARD DRAWINGS AND TO THE SATISFACTION OF THE SUPERINTENDENT AND THE MUNICIPAL ENGINEER OR HIS REPRESENTATIVE.
- ROAD CHAINAGES REFER TO ROAD CENTRELINES. CHAINAGES FOR INTERSECTIONS AND 4 CUL-DE-SACS REFER TO THE LIP OF KERB
- THE LOCATION OF EXISTING SERVICES SHOULD BE DETERMINED BY THE CONTRACTOR PRIOR TO COMMENCING ANY EXCAVATION BY CONTACTING ALL LOCAL SERVICE GUIDE ONLY AND ARE NOT GUARANTEED AS CORRECT
- WHERE REQUIRED ANY BUILDINGS, TROUGHS, FENCES AND OTHER STRUCTURES ON SITE ARE TO BE REMOVED AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL IS TO BE INCLUDED IN THE OVERALL EARTHWORKS FIGURE UNLESS A SPECIFIC ITEM FOR REMOVAL IS DENOTED IN THE SCHEDULE.
- 7. ALL EXCAVATED ROCK AND SURPLUS SPOIL TO BE REMOVED AND DISPOSED OFF SITE UNLESS NOTED OTHERWISE.
- ALL FILLING ON LOTS AND WITHIN ROAD RESERVES GREATER THAN 200mm IS TO BE UNDERTAKEN USING LEVEL 1 SUPERVISION AND BE COMPLETED IN ACCORDANCE WITH AS 3798-2007. FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND REPLACED WITH TOPSOIL (WHERE REQUIRED) TO OBTAIN THE FINAL LEVELS SHOWN ON THE DRAWINGS.
- FILLING MATERIAL IS TO BE IN ACCORDANCE WITH THE SPECIFICATION, AS 3798-2007 & 9 TO THE SATISFACTION OF COUNCIL AND THE SUPERINTENDENT.
- 10. ALL BATTERS SHALL BE 1 IN 6, UNLESS OTHERWISE SHOWN.
- 11. NO FILL OR STOCKPILING OF MATERIAL IS TO BE PLACED ON ANY RESERVE FOR PUBLIC OPEN SPACE UNLESS OTHERWISE DIRECTED OR APPROVED BY THE SUPERINTENDENT.
- 12. TBM'S TO BE RE-ESTABLISHED BY THE LICENSED SURVEYOR IF FOUND TO BE MISSING AT THE COMMENCEMENT OF CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE FOR CARE AND MAINTENANCE OF T.B.M.'S THEREAFTER.
- 13. AT LEAST 3 DAYS PRIOR TO COMMENCING WORK ON EXCAVATIONS IN EXCESS OF 1.50m DEEP, A NOTIFICATION FORM MUST BE SENT TO WORKSAFE. THE CONTRACTOR IS TO COMPLY WITH WORKSAFE, THE MINES (TRENCHES) REGULATION 1982, THE MINES ACT 1958 AND OCCUPATIONAL HEALTH AND SAFETY ACT 1985, 2004.
- 14. ALL SERVICE TRENCHES UNDER DRIVEWAYS, FOOTPATHS AND PARKING BAYS TO BE BACKFILLED WITH CLASS 2 CRUSHED ROCK. SERVICE TRENCHES LESS THAN 750mm BEHIND KERB AND CHANNEL OR PAVED TRAFFIC AREAS ARE ALSO TO BE BACKFILLED WITH COMPACTED CLASS 2 CRUSHED ROCK.
- 15. WHERE REQUIRED, ALL EXISTING DAMS, DEPRESSIONS AND DRAINS ARE TO BE BREACHED, DRAINED, DESLUDGED AND SHALL BE EXCAVATED TO A CLEAN FIRM BASE. THE SURFACE SHALL BE INSPECTED. APPROVED AND LEVELED BY THE ENGINEER PRIOR TO COMMENCEMENT OF FILLING. THE FILL SHALL BE APPROVED SELECTED ON SITE MATERIAL OR APPROVED IMPORTED MATERIAL. THE FILL SHALL BE PLACED UNDER CONTROLLED MOISTURE CONDITIONS IN ACCORDANCE WITH THE SPECIFICATION
- 16. NO BLASTING TO BE CARRIED OUT WITHIN THE MUNICIPALITY WITHOUT OBTAINING COUNCILS PERMISSION.
- 17. GAS AND WATER CONDUITS ARE TO BE , Ø50mm . CLASS 12 P.V.C. – SINGLE SERVICE Ø100mm . CLASS 12 P.V.C. – DUAL SERVICE (DRINKING AND NON DRINKING WATER)
- WITH THE FOLLOWING MINIMUM COVER TO FINISHED SURFACE LEVELS: ROAD PAVEMENT - 0.80m VERGE, FOOTPATHS - 0.45m
- 18. ALL SERVICE CONDUIT TRENCHES UNDER ROAD PAVEMENTS TO BE BACKFILLED IN ACCORDANCE WITH RELEVANT MUNICIPALITY OR ROAD AUTHORITY SPECIFICATION.
- 19. AG/SUBSOIL DRAIN TO BE LAID BEHIND KERB WHERE REQUIRED IN ACCORDANCE WITH THE COUNCIL STANDARD DRAWINGS AND CONNECTED TO UNDERGROUND DRAINAGE.
- 20. ALL STORMWATER DRAINS ARE TO BE CLASS '2' R.C. PIPES UNLESS OTHERWISE SHOWN. ALL R.C. JOINTS ARE TO BE RUBBER RING JOINTED (R.R.J.).
- 21. CENTRELINES OF ALL EASEMENT DRAINS ARE OFFSET 1.0m OR 2.2m (WHERE OUTSIDE OF SEWER) FROM THE PROPERTY LINE UNLESS SHOWN OTHERWISE.
- 22. WHERE CURVED PIPE ALIGNMENTS ARE SHOWN ON THE FACE PLANS THEY ARE TO BE LAID PARALLEL TO THE BACK OF KERB, EXCEPT WHERE A RADIUS HAS BEEN SPECIFICALLY NOMINATED. CURVED PIPES ARE TO BE APPROVED BY COUNCIL AND IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS.
- 23. WATER TAPPINGS TO BE LOCATED IN CENTRE OF ALLOTMENTS UNLESS OTHERWISE SHOWN.
- 24. TELSTRA IS TO BE NOTIFIED 7 DAYS PRIOR TO PLACEMENT OF CONCRETE WORKS.
- 25. PAVEMENT DEPTHS MAY BE MODIFIED AS DIRECTED BY THE SUPERINTENDENT.

PAVEMENT TO BE BOXED OUT TO MINIMUM DEPTH DENOTED, INSPECTED AND IF SUBGRADE IS IN QUESTION, FURTHER TESTING CARRIED OUT TO DETERMINE FINAL PAVEMENT DEPTH.

- WHERE PAVEMENT IS CONSTRUCTED ON FILLING, FILL MATERIAL IS TO BE APPROVED BY THE SUPERINTENDENT AND COUNCIL. FILLING TO BE CONSTRUCTED IN LAYERS 150mm THICK WITH COMPACTION ACHIEVING 95% AUSTRALIAN STANDARD DENSITY.
- WHEN PAVEMENT EXCAVATION IS IN ROCK, ALL LOOSE MATERIAL (INCLUDING ROCKS AND 27 CLAY) MUST BE REMOVED. THE SUB-GRADE MUST THEN BE REGULATED WITH COUNCIL APPROVED MATERIAL.
- 28. LINEMARKING AND SIGNAGE TO BE INSTALLED IN ACCORDANCE WITH AS 1742 SERIES UNLESS NOTED OTHERWISE. STREET SIGNS ARE TO BE INSTALLED IN ACCORDANCE WITH COUNCIL STANDARDS.
- 29. ALL TEMPORARY WARNING SIGNS USED DURING CONSTRUCTION SHALL BE SUPPLIED AND MAINTAINED IN ACCORDANCE WITH AS 1742-3.
- AUTHORITIES. ANY EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE OFFERED AS A 30. TACTILE GROUND SURFACE INDICATORS ARE TO BE INSTALLED IN ACCORDANCE WITH THE DISABILITY DISCRIMINATION ACT AND RELEVANT COUNCIL STANDARD DRAWINGS.
 - 31. CONTRACTOR TO PROVIDE AN ENVIRONMENTAL MANAGEMENT PLAN INCLUDING SILT AND SEDIMENT RUNOFF PROTECTION ETC. PRIOR TO THE COMMENCEMENT OF WORKS.
 - 32. ALL TREES AND SHRUBS ARE TO BE RETAINED UNLESS OTHERWISE SHOWN. IF ROAD AND DRAINAGE CONSTRUCTION NECESSITATES THEIR REMOVAL, WRITTEN PERMISSION MUST BE OBTAINED FROM THE SUPERINTENDENT.
 - 33. TREES NOT SPECIFIED FOR REMOVAL ARE TO BE PROTECTED WITH APPROPRIATE EXCLUSION FENCING PRIOR TO COMMENCEMENT OF ANY WORKS.

DRAWING SCHEDULE

REFERENCE	DESCRIPTION	REVISION	SHEET No.			
CR100	ROAD & DRAINAGE FACE SHEET	6	1			
CR200	FACE PLAN	7	2			
CR201	SERVICES PLAN	6	3			
CR300	ROAD LONGITUDINAL SECTIONS	4	4			
CR301	ROAD & SHARED PATH LONGITUDINAL SECTIONS	3	5			
CR302	SHEET REMOVED FROM SET	-	-			
CR400	ROAD CROSS SECTIONS	3	6			
CR401	ROAD CROSS SECTIONS	3	7			
CR402	ROAD CROSS SECTIONS	4	8			
CR403	SHEET REMOVED FROM SET	-	-			
CR500	INTERSECTION DETAILS	4	9			
CR600	DRAINAGE LONG SECTIONS	3	10			
CR601	DRAINAGE LONG SECTIONS	5	11			
CR602	DRAINAGE LONG SECTIONS	5	12			
CR700	PAVEMENT AND TYPICAL DETAILS	4	13			
CR800	SIGNAGE AND LINEMARKING	5	14			
CR601 CR602 CR700	DRAINAGE LONG SECTIONS DRAINAGE LONG SECTIONS PAVEMENT AND TYPICAL DETAILS	5 5 4	11 12 13			


SERVICE I OCATION TABLE

JERVICE LOCATIO																
ROAD NAME		ABLE TER		RECYCLED GAS			3N ECOM)	NBN (EXPRESS)		ELECTRICITY			TREE			
	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	PC	DLE	U/G (TABLE	SIDE	OFFSET
	SIDE	UFFSET	SIDE	UFFSET	SIDE	UFFSET	SIDE	UFFSEI	SIDE	UFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	ULISET
DEBUT AVENUE (16.0m)	W	2.90	W	2.42	W	2.00	E	1.83	-	-	E	1.1 x#	E	2.55	вотн	1.00×
FRONTIER CIRCUIT (E/W) (16.0m)	Ν	2.90	Ν	2.42	Ν	2.00	S	1.83	-	-	S	1.1 x#	S	2.55	BOTH	1.00×
FRONTIER CIRCUIT (N/S) (13.5m)	W	3.35	W	2.85	W	2.40	W	1.85	-	-	Ē	1.0 x#	E	0.50	вотн	1.00×
CULTURE LANE (16.0m)	W	2.90	W	2.42	W	2.00	E	1.83	-	-	E	1.1 x#	E	2.55	вотн	1.00×

1. TELECOMMUNICATIONS AND ELECTRICITY CABLES TO BE CONSTRUCTED IN A COMMON TRENCH IN ACCORDANCE WITH ELECTRICITY AUTHORITY STANDARD DRG'S 2. × = 0FFSET 0.8m FROM BACK OF KERB UNLESS OTHERWISE STATED. REFER ELECTRICAL DESIGN DRAWINGS


3. # = BEHIND BACK OF KERB

C NUM5AMENDMENTS TO UTILITIES CORRIDORMH25-05-204AS CONSTRUCTEDMH06-12-193DRIVEWAY AMENDED, RELOCATED GAS WATER CONDUITSM.H.12-08-192AMENDMENT TO STAGE BOUNDARY 8 & 11M.H.01-03-191RESEQUENCING OF STAGES 8 & 9M.H.13-11-180ISSUED FOR CONSTRUCTIONJ.S.27-06-18	file na file lo	Rev	Amendments	Approved	Date
6ISSUED FOR CONSTRUCTIONM.H.09-07-205AMENDMENTS TO UTILITIES CORRIDORMH25-05-204AS CONSTRUCTEDMH06-12-193DRIVEWAY AMENDED, RELOCATED GAS WATER CONDUITSM.H.12-08-192AMENDMENT TO STAGE BOUNDARY 8 & 11M.H.01-03-1974.051RESEQUENCING OF STAGES 8 & 9M.H.13-11-180ISSUED FOR CONSTRUCTIONJ.S.27-06-18	Ĕ T	F	CHANGES TO LOT MIX	J.S.	08-06-18
6ISSUED FOR CONSTRUCTIONM.H.09-07-205AMENDMENTS TO UTILITIES CORRIDORMH25-05-204AS CONSTRUCTEDMH06-12-193DRIVEWAY AMENDED, RELOCATED GAS WATER CONDUITSM.H.12-08-192AMENDMENT TO STAGE BOUNDARY 8 & 11M.H.01-03-1972000000000000000000000000000000000000	tion	0	ISSUED FOR CONSTRUCTION	J.S.	27-06-18
6ISSUED FOR CONSTRUCTIONM.H.09-07-205AMENDMENTS TO UTILITIES CORRIDORMH25-05-204AS CONSTRUCTEDMH06-12-193DRIVEWAY AMENDED, RELOCATED GAS WATER CONDUITSM.H.12-08-1962AMENDMENT TO STAGE BOUNDARY 8 & 11M.H.01-03-19	344 G:/1	1	RESEQUENCING OF STAGES 8 & 9	M.H.	13-11-18
6ISSUED FOR CONSTRUCTIONM.H.09-07-205AMENDMENTS TO UTILITIES CORRIDORMH25-05-202004AS CONSTRUCTEDMH06-12-1911000000000000000000000000000000000	0CR1 80/3	2	AMENDMENT TO STAGE BOUNDARY 8 & 11	M.H.	01-03-19
6ISSUED FOR CONSTRUCTIONM.H.09-07-20N > 25AMENDMENTS TO UTILITIES CORRIDORMH25-05-204AS CONSTRUCTEDMH06-12-19	00 - 034	3	DRIVEWAY AMENDED, RELOCATED GAS WATER CONDUITS	M.H.	12-08-19
$ \begin{array}{c c c c c c c c c c c c c c c c c c c $	4 0/(4	AS CONSTRUCTED	MH	06-12-19
w ≥ 6 ISSUED FOR CONSTRUCTION M.H. 09-07-20	 2 2 1 1	5	AMENDMENTS TO UTILITIES CORRIDOR	MH	25-05-20
	AC/	6	ISSUED FOR CONSTRUCTION	M.H.	09-07-20





NEWHAVEN ESTATE **STAGE 8** PEET 1985 PTY LTD



REPRODUCED WITH PERMISSION TY PLAN AI

Ń	SCA
MGA 94 ZONE 55	MEL

LE WAY:

NOT TO SCALE 359 B11




© Spiire Australia Pty Ltd All Rights Reserved This document is produced by Spiire Australia Pty Ltd solely for the enefit of and use by the client in accordance with the terms of the etainer. Spiire Australia Pty Ltd does not and shall not assume any esponsibility or liability whatsoever to any third party arising out of iny use or reliance by third party on the content of this document.



Victoria 8007 Australia T 61 3 9993 7888 ABN 55 050 029 635 spiire.com.au



WARNING BEWARE OF UNDERGROUND/OVERHEAD SERVICES THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.



DESCRIPTION	EXISTING	PROPOSED
WATER MAIN, VALVE AND HYDRANT	Dw <u>_X</u> _©_	DW
WATER RECYCLED	— — NDW — — —	NDW
UNDERGROUND ELECTRICITY	— — E — — —	———— E ————
OVERHEAD ELECTRICITY & POLE	— — OE — -⊗- —	OE
TELSTRA & SERVICE PIT	— — — T — - Z —	T
OPTIC FIBRE		OF
OVERHEAD TELSTRA	— — — OT — — —	
GAS MAIN	G	G
BRANCH SEWER & MANHOLE	— — § — — —	<u>Ş</u>
SEWER & MANHOLE	SO	S
	— — — SRM — — —	
	> > _	
COUNCIL STORMWATER DRAIN & PIT		•
STORMWATER DRAINAGE PROPERTY INLETS		
HOUSE DRAIN	•H	●H
		> AG
MWC STORMWATER DRAIN & PIT		
MWC STORMWATER PITS		
STORMWATER DRAINAGE PIT NUMBER	(1)	(1)
GAS & WATER CONDUITS	GW	GW
CONCRETE VEHICLE CROSSING		\bigtriangledown
INDUSTRIAL CONCRETE VEHICLE CROSSING		
PAVEMENT SAWCUT LINE		SAWCUT
RIDGE / CHANGE OF GRADE LINE	_ · · · · /	<u> </u>
SURFACE CONTOUR MINOR (0.25m INT.)		168.90
SURFACE CONTOUR MAJOR		169.00
SURFACE LEVEL	E123.45	F124.68
BATTER LEVEL (TOP / TOE)	T 12 4.80	T124.80
EARTHWORKS GRADE		1 in 150
SIGN AND POST		_
LIGHT & POLE (BY OTHERS)	°	\sim
STREET SIGN	°>>>	<u>حح</u> ہ
PERMANENT SURVEY MARK		.
TEMPORARY BENCH MARK		•
BOLLARD	¥ 	¥
ROAD CHAINAGES	CH116.57 (L/R)TP	CH116.57 (L/R)TP
	— CH116.57	— CH116.57
LOT CHAINAGE	CH20.06	CH20.06
SETOUT POINT		(A2)
LIMIT OF WORKS		$\overline{}$
BATTER		
EXCAVATION GREATER THAN 0.20m		
FILLING GREATER THAN 0.20m		
FILL EXTENTS		
FENCES	· · · · · · · · · · · · · · · · · · ·	/ / /
TREE (& SURVEYED CANOPY) TO BE RETAINED	(ÉLE)	×
TREE TO BE REMOVED		
VEGETATION LINE	·····	
FOOTPATH		



