

# PLAN OF SUBDIVISION

LV use only  
**EDITION**

Plan Number  
**PS 734547H**

Location of Land  
Parish: TARNEIT  
Township: -  
Section: 21 (PART)  
Crown Allotment: -  
Crown Portion: C (PART)  
Title Reference: VOL 9650 FOL 372  
Last Plan Reference: LOT 6 ON PS701126U  
Postal Address: 820-830 LEAKES ROAD  
(at time of subdivision) TARNEIT 3029  
MGA 94 Co-ordinates E 295 660  
(of approx. centre of land in plan) N 5 810 500 Zone: 55

Council Name: WYNDHAM CITY COUNCIL  
Council Ref:

Vesting of Roads and/or Reserves		Notations	
Identifier	Council/Body/Person	Staging	
ROAD R1 RESERVE No.1 RESERVE No.2 RESERVE No.3	WYNDHAM CITY COUNCIL WYNDHAM CITY COUNCIL WYNDHAM CITY COUNCIL POWERCOR AUSTRALIA LTD	This <del>is</del> is not a staged subdivision Planning Permit No. WYP6826/13	
		<b>Survey</b> This plan is/ <del>is not</del> based on survey This survey has been connected to permanent marks no(s) 790, 714 & 759 In Proclaimed Survey Area No. - <b>Depth Limitation</b> DOES NOT APPLY	
		DIMENSIONS SHOWN THUS <u>279°49'40"</u> & <u>756.88</u> ARE NOT THE SUBJECT OF THIS SURVEY LOTS 1 TO 100 (BOTH INCLUSIVE) HAVE BEEN OMITTED FROM THIS PLAN AREA OF LAND SUBDIVIDED (EXCLUDING LOT A) - 4.814ha	


## Easement Information

**Legend:** E - Encumbering Easement, Condition in Crown Grant in the Nature of an Easement or Other Encumbrance      A - Appurtenant Easement  
R - Encumbering Easement (Road)

Subject Land	Purpose	Width (metres)	Origin	Land Benefited/In Favour Of
E-1 E-1	DRAINAGE SEWERAGE	SEE DIAG SEE DIAG	THIS PLAN THIS PLAN	WYNDHAM CITY COUNCIL CITY WEST WATER CORPORATION



**HAVEN - 1**  
**37 LOTS & BALANCE LOT A**

**Bosco Jonson Pty Ltd**  
A.B.N 15 169 138 827  
P.O. Box 5075, South Melbourne, Vic 3205  
16 Eastern Road South Melbourne  
Vic 3205 Australia  
Tel 03) 9699 1400 Fax 03) 9699 5992




LICENSED SURVEYOR (PRINT) ADRIAN A. THOMAS  
SIGNATURE ..... DIGITALLY SIGNED ..... DATE / /  
REF 29474013 26/11/15 VERSION P  
DWG 2947401AP

Sheet 1 of 5 sheets  
Original sheet size A3



ENLARGEMENT No.1  
NOT TO SCALE



ENLARGEMENT No.2  
NOT TO SCALE

SEE ENLARGEMENT No.1

TARNEIT ROAD



6°28'40"  
568.67

10°25'10"  
221.32

SEE ENLARGEMENT No.2

PLAN OF SUBDIVISION

Plan Number  
**PS 734547H**




HAVEN - 1

**Bosco Jonson Pty Ltd**  
A.B.N 15 169 138 827  
P.O. Box 5075, South Melbourne, Vic 3205  
16 Eastern Road South Melbourne  
Vic 3205 Australia  
Tel 03) 9699 1400 Fax 03) 9699 5992



ORIGINAL  
SCALE SHEET SIZE  
1:3000 A3




LICENSED SURVEYOR (PRINT) ADRIAN A. THOMAS  
SIGNATURE DIGITALLY SIGNED DATE / /  
REF 29474013 26/11/15 VERSION P  
DWG 2947401AP

Sheet 2

# PLAN OF SUBDIVISION

Plan Number

## PS 734547H




**A**  
(2 PARTS)  
SEE SHEET 2



HAVEN - 1

### Bosco Jonson Pty Ltd

A.B.N 15 169 138 827  
P.O. Box 5075, South Melbourne, Vic 3205  
16 Eastern Road South Melbourne  
Vic 3205 Australia  
Tel (03) 9699 1400 Fax (03) 9699 5992




LEAKES ROAD

ORIGINAL

SCALE

SCALE SHEET SIZE  
1:750 A3



Sheet 3

LICENSED SURVEYOR (PRINT) ADRIAN A. THOMAS

SIGNATURE DIGITALLY SIGNED DATE / /

REF 29474013 26/11/15 VERSION P  
DWG 2947401AP

# PLAN OF SUBDIVISION

Plan Number

**PS 734547H**

## CREATION OF RESTRICTION

The following restriction is to be created upon registration of Plan of Subdivision No. PS734547H (Plan of Subdivision) by way of a restrictive covenant and as a restriction as defined in the Subdivision Act 1988.

Land to benefit: Lots 101 to 137 (all inclusive) on the Plan of Subdivision.

Land to be burdened: Lots 101 to 137 (all inclusive) on the Plan of Subdivision.

## DESCRIPTION OF RESTRICTION

Except with the written consent of the Transferor and in all other instances with the written consent of each and every registered proprietor of a benefiting Lot on the Plan of Subdivision the registered proprietor or proprietors for the time being of any burdened Lot on the Plan of Subdivision shall not:


- (a) subdivide or allow a lot to be subdivided except corner lots;
- (b) consolidate or allow a lot to be consolidated;
- (c) build more than one dwelling on a lot except corner lots;
- (d) build or allow to be built on the Lot any dwelling:
  - i. whose primary frontage does not face and address the road or a laneway or open space;
  - ii. without a front veranda, portico, porch or other integral entrance feature which is clearly visible from the street and consistent with the design of the dwelling;
  - iii. where the facade is fully constructed in brick;
  - iv. with less than 2 material finishes on the front facade, each of which must cover a minimum of 30% of the facade;
  - v. where materials incorporated into the front facade do not return a minimum of 1 metre to the sides of the dwelling (excluding parapet construction);
  - vi. using contrasting but complementary base, accent, face brick and roof tile colours;
  - vii. with window frames and glazing that contrast and do not complement the facade colour and the overall colour palette of the dwelling;
  - viii. containing any leadlight or stained glass features;
  - ix. whose height is greater than 8.5 metres from the natural surface level;
  - x. without fittings and connections which allow toilets and gardens to be flushed and/or serviced by recycled water;
  - xi. without being cabled and equipped with fibre cabling in accordance with the specifications nominated by NBN Co from time to time;
  - xii. with an identical facade to another dwelling house, unless such dwelling house is separated by a minimum of three dwelling houses in each direction;
- (e) build or allow to be built a dwelling house which does not, prior to occupation, have constructed a roofed and fully enclosed garage:
  - i. setback a minimum of 840mm from the main building line of the dwelling;
  - ii. where the opening occupies 40% or less of the width of the lot; and
  - iii. with sectional or tilt panels in the same colour scheme as that of the dwelling, or finished with a wood grain or timber panel;
- (f) build or allow to be built on the Land any outbuildings (including any garage, workshop, garden shed, storage shed, heating and cooling systems, antennae and satellite dishes, washing lines, solar units and hot water services or other outbuilding) which:
  - i. exceed 20 square metres in area;
  - ii. exceed 3.6 metres in height;
  - iii. are visible from any street or the private open space of any other Lot on the Plan of Subdivision or public open space; or
  - iv. are constructed from any materials or finishes or in any style or colours which are inconsistent with the main dwelling;
- (g) build or allow to be built any dwelling with a roof:
  - i. if pitched, at a pitch of less than 22 degrees;
  - ii. of any material other than steel or masonry; or
  - iii. of any other colour other than from the Colourbond contemporary range or a similar colour;
- (h) build or allow to be built any front fence:
  - i. more than 1.2 metres in height;
  - ii. with less than 50 percent transparency unless the front fence is less than 0.7 metres in height then it may be solid;
  - iii. which is inconsistent with the dwelling on the Lot in relation to style, materials and colours;
  - iv. of materials other than timber slats or masonry pillars with metal infill panels;
  - v. with mock Victorian, Edwardian or other heritage detailing;
- (i) build or allow to be built any side or rear fencing:
  - i. of materials other than Colourbond standard sheeting infill panels;
  - ii. other than 1.8 metres in height (except where there is a front fence); or
  - iii. of a colour in respect of infill panels, posts and rails other than Greyridge;
- (j) build or allow to be built any side fencing which extends in front of the building line unless a front fence has been installed, which additional side fencing must be 1.2 metres in height;
- (k) on a corner lot, build or allow to be built any fence to a secondary boundary which is a street or public space:
  - i. which does not return a minimum of 2 metres behind the front building line;
  - ii. of materials other than Colourbond standard sheeting infill panels;
  - iii. other than 1.8 metres in height; or
  - iv. of a colour in respect of infill panels, posts and rails other than Greyridge;

continued

HAVEN – 1

**Bosco Jonson Pty Ltd**


A.B.N 15 169 138 827  
 P.O. Box 5075, South Melbourne, Vic 3205  
 16 Eastern Road South Melbourne  
 Vic 3205 Australia  
 Tel 03) 9699 1400 Fax 03) 9699 5992



ORIGINAL

SCALE

SCALE  
 SHEET SIZE  
**A3**



Sheet 4

LICENSED SURVEYOR (PRINT) ADRIAN A. THOMAS

SIGNATURE . . . . . DIGITALLY SIGNED . . . . . DATE / /

REF 29474013 26/11/15 VERSION P  
 DWG 2947401AP

# PLAN OF SUBDIVISION

Plan Number

**PS 734547H**

## CREATION OF RESTRICTION (CONTINUED)


- (l) on a corner lot, build or allow to be built any dwelling where the home design does not address both the primary and secondary street frontages and be of a consistent architectural design. Design elements (such as verandahs, detailing, feature windows & materials) used on the primary frontage must continue on that part of the secondary frontage visible from the public realm;
- (m) build or allow to be built:
  - i. more than one vehicle crossover to the Lot;
  - ii. a driveway exceeding 3.5 metres in width;
  - iii. a dwelling which is occupied before completion of the driveway;
  - iv. a driveway constructed of stampcrete or plain concrete;
  - v. a driveway of a colour which is inconsistent with the materials and finishes of the dwelling;
- (n) build or allow to be built:
  - i. any retaining structures greater than 1 metre in height between a dwelling and a street or public space;
  - ii. any cut and fill deeper than 1 metre without utilization of planted and landscaped embankments with a maximum 1:3 gradient or a combination of a series of retaining structures with a maximum of 1 metre high steps and planted embankments or terracing;
- (o) allow the front yard of a Lot not to be landscaped within 3 months of the date of issue of the occupancy permit for a dwelling house;
- (p) build or allow to be built a letterbox which is not located and constructed to Australia Post standards, and which does not complement the dwelling house in terms of character, materials, colour, style and design;
- (q) do anything in respect of the Lot in contravention of the planning requirements set out in the precinct structure plan forming part of the Wyndham Planning Scheme;
- (r) allow any rubbish to accumulate or remain unsecured on the Lot unless stored in an appropriately sized skip or bin;
- (s) allow any grass or weeds on the Lot to grow excessively;
- (t) allow any building materials to be delivered or stored on the nature strip or anywhere else outside the title boundary of the Lot upon which the dwelling house is being constructed;
- (u) during construction:
  - i. allow construction rubbish or other rubbish to move from the Lot to other lots; or
  - ii. allow any trade or delivery vehicles to be parked on footpaths, verges, nature strips or park reserves or in any location which hinders overall development construction.
- (v) erect, permit or allow to be erected or to remain erected on the Lot any advertisement, hoarding, sign or similar structure and will not permit the Lot or any building or buildings constructed thereon to be used for the display of any advertisement, sign or notice provided that this restriction shall not prevent the erection of a signboard that the Lot is for sale and shall not prevent the display of the nameplate or light of any medical practitioner, dentist, legal practitioner or other such professional trade or business nameplate.
- (w) allow any plant or machinery or any recreation vehicle or commercial vehicle, (including without limitation a caravan, boat, box trailer, boat trailer, and car trailer but excluding any motor cycle, motor car, motor station wagon or utility or four wheel drive car registered for use on a highway) to be left or parked on the street or on the Lot between the building line and the front boundary (unless either of those occurs during the normal course of business by a visiting trades person) or on the nature strip or footpath.

The restriction shall expire ten years after the date of registration of this plan.

HAVEN – 1

**Bosco Jonson Pty Ltd**


A.B.N 15 169 138 827  
 P.O. Box 5075, South Melbourne, Vic 3205  
 16 Eastern Road South Melbourne  
 Vic 3205 Australia  
 Tel 03) 9699 1400 Fax 03) 9699 5992



ORIGINAL

SCALE

SCALE  
 SHEET SIZE  
**A3**



Sheet 5

LICENSED SURVEYOR (PRINT) ADRIAN A. THOMAS

SIGNATURE . . . . . DIGITALLY SIGNED . . . . . DATE / /

REF 29474013 26/11/15 VERSION P  
 DWG 2947401AP