

NEWHAVEN ESTATE STAGE 26 PEET NO.1895 PTY LTD

GENERAL NOTES:

SURVEY

- ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM AND ALL COORDINATES ARE TO MAP GRID OF AUSTRALIA (MGA) 94, ZONE 55.
- ALL EXISTING SURFACE LEVELS SHOWN ON THE ENGINEERING DRAWINGS HAVE BEEN INTERPOLATED FROM A DIGITAL TERRAIN MODEL. THESE LEVELS HAVE BEEN USED AS THE BASIS FOR ALL ENGINEERING DESIGN AND DETERMINATION OF QUANTITIES AND ARE ACCURATE TO WITHIN ±0.05m.
- ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH PEET'S MODIFIED AS4000-1997 AMENDED FROM GENERAL CONDITIONS OF CONTRACT, THE ROAD & DRAINAGE SPECIFICATION, APPROVED MUNICIPALITY SPECIFICATIONS AND STANDARD DRAWINGS AND TO THE SATISFACTION OF THE SUPERINTENDENT AND THE MUNICIPAL ENGINEER OR HIS REPRESENTATIVE.
- ROAD CHAINAGES REFER TO ROAD CENTRELINES. CHAINAGES FOR INTERSECTIONS AND CUL-DE-SACS REFER TO THE LIP OF KERB.

EARTHWORKS

- THE LOCATION OF EXISTING SERVICES SHOULD BE DETERMINED BY THE CONTRACTOR PRIOR TO COMMENCING ANY EXCAVATION BY CONTACTING ALL LOCAL SERVICE AUTHORITIES. ANY EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE OFFERED AS A GUIDE ONLY AND ARE NOT GUARANTEED AS CORRECT.
- WHERE REQUIRED ANY BUILDINGS, TRENCHES, FENCES AND OTHER STRUCTURES ON SITE ARE TO BE REMOVED AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL IS TO BE INCLUDED IN THE OVERALL EARTHWORKS FIGURE UNLESS A SPECIFIC ITEM FOR REMOVAL IS DENOTED IN THE SCHEDULE.
- ALL EXCAVATED ROCK AND SURPLUS SPOIL TO BE REMOVED AND DISPOSED OFF SITE UNLESS NOTED OTHERWISE.
- ALL FILLING ON LOTS AND WITHIN ROAD RESERVES GREATER THAN 200mm IS TO BE UNDERTAKEN USING LEVEL 1 SUPERVISION AND BE COMPLETED IN ACCORDANCE WITH AS 3798-2007. FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND REPLACED WITH TOPSOIL (WHERE REQUIRED) TO OBTAIN THE FINAL LEVELS SHOWN ON THE DRAWINGS.
- FILLING MATERIAL IS TO BE IN ACCORDANCE WITH THE SPECIFICATION, AS 3798-2007 & TO THE SATISFACTION OF COUNCIL AND THE SUPERINTENDENT.
- ALL BATTERS SHALL BE 1 IN 6, UNLESS OTHERWISE SHOWN.
- NO FILL OR STOCKPILING OF MATERIAL IS TO BE PLACED ON ANY RESERVE FOR PUBLIC OPEN SPACE UNLESS OTHERWISE DIRECTED OR APPROVED BY THE SUPERINTENDENT.
- T.B.M.'S TO BE RE-ESTABLISHED BY THE LICENSED SURVEYOR IF FOUND TO BE MISSING AT THE COMMENCEMENT OF CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE FOR CARE AND MAINTENANCE OF T.B.M.'S THEREAFTER.
- AT LEAST 3 DAYS PRIOR TO COMMENCING WORK ON EXCAVATIONS IN EXCESS OF 150mm DEEP, A NOTIFICATION FORM MUST BE SENT TO WORKSAFE. THE CONTRACTOR IS TO COMPLY WITH WORKSAFE, THE MINES (TRENCHES) REGULATION 1982, THE MINES ACT 1958 AND OCCUPATIONAL HEALTH AND SAFETY ACT 1985, 2004.
- ALL SERVICE TRENCHES UNDER DRIVEWAYS, FOOTPATHS AND PARKING BAYS TO BE BACKFILLED WITH CLASS 2 CRUSHED ROCK. SERVICE TRENCHES LESS THAN 750mm BEHIND KERB AND CHANNEL OR PAVED TRAFFIC AREAS ARE ALSO TO BE BACKFILLED WITH COMPACTED CLASS 2 CRUSHED ROCK.
- WHERE REQUIRED, ALL EXISTING DAMS, DEPRESSIONS AND DRAINS ARE TO BE BREACHED, DRAINED, DESLUDGED AND SHALL BE EXCAVATED TO A CLEAN FIRM BASE. THE SURFACE SHALL BE INSPECTED, APPROVED AND LEVELED BY THE ENGINEER PRIOR TO COMMENCEMENT OF FILLING. THE FILL SHALL BE APPROVED SELECTED ON SITE MATERIAL OR APPROVED IMPORTED MATERIAL. THE FILL SHALL BE PLACED UNDER CONTROLLED MOISTURE CONDITIONS IN ACCORDANCE WITH THE SPECIFICATION.
- NO BLASTING TO BE CARRIED OUT WITHIN THE MUNICIPALITY WITHOUT OBTAINING COUNCIL'S PERMISSION.

SERVICES

- GAS AND WATER CONDUITS ARE TO BE .050mm . CLASS 12 P.V.C. - SINGLE SERVICE
Ø100mm . CLASS 12 P.V.C. - DUAL SERVICE (DRINKING AND NON DRINKING WATER)
WITH THE FOLLOWING MINIMUM COVER TO FINISHED SURFACE LEVELS:
ROAD PAVEMENT - 0.80m
VERGE, FOOTPATHS - 0.45m
- ALL SERVICE CONDUIT TRENCHES UNDER ROAD PAVEMENTS TO BE BACKFILLED IN ACCORDANCE WITH RELEVANT MUNICIPALITY OR ROAD AUTHORITY SPECIFICATION.
- WATER TAPPINGS TO BE LOCATED AS PER RELEVANT AUTHORITY STANDARD, UNLESS NOTED OTHERWISE.
- TELSTRA ARE TO BE NOTIFIED 7 DAYS PRIOR TO PLACEMENT OF CONCRETE WORKS.

STORM WATER DRAINAGE

- AG/SUBSOIL DRAIN TO BE LAID BEHIND KERB WHERE REQUIRED IN ACCORDANCE WITH THE COUNCIL STANDARD DRAWINGS AND CONNECTED TO UNDERGROUND DRAINAGE.
- ALL STORMWATER DRAINS ARE TO BE CLASS '2' R.C. PIPES UNLESS OTHERWISE SHOWN. ALL R.C. JOINTS ARE TO BE RUBBER RING JOINTED (R.R.J.).

- CENTRELINES OF ALL EASEMENT DRAINS ARE OFFSET 1.0m OR 2.2m (WHERE OUTSIDE OF SEWER) FROM THE PROPERTY LINE UNLESS SHOWN OTHERWISE.
- WHERE CURVED PIPES ARE SHOWN ON THE FACE PLANS THEY ARE TO BE LAID PARALLEL TO THE BACK OF KERB, EXCEPT WHERE A RADIUS HAS BEEN SPECIFICALLY NOMINATED. CURVED PIPES ARE TO BE APPROVED BY COUNCIL AND IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS.
- HOUSE DRAINS NOT OUT OF PIT TO BE OFFSET IN ACCORDANCE WITH COUNCIL STANDARDS UNLESS NOTED OTHERWISE.


PAVEMENT

- PAVEMENT DEPTHS MAY BE MODIFIED AS DIRECTED BY THE SUPERINTENDENT. PAVEMENT TO BE BOXED OUT TO MINIMUM DEPTH DENOTED, INSPECTED AND IF SUBGRADE IS IN QUESTION, FURTHER TESTING CARRIED OUT TO DETERMINE FINAL PAVEMENT DEPTH.
- WHERE PAVEMENT IS CONSTRUCTED ON FILLING, FILL MATERIAL IS TO BE APPROVED BY THE SUPERINTENDENT AND COUNCIL. FILLING TO BE CONSTRUCTED IN LAYERS 150mm THICK WITH COMPACTION ACHIEVING 95% AUSTRALIAN STANDARD DENSITY.
- WHEN PAVEMENT EXCAVATION IS IN ROCK ALL LOOSE MATERIAL (INCLUDING ROCKS AND CLAY) MUST BE REMOVED. THE SUB-GRADE MUST THEN BE REGULATED WITH COUNCIL APPROVED MATERIAL.

SIGNAGE AND LINEMARKING

- LINEMARKING AND SIGNAGE TO BE INSTALLED IN ACCORDANCE WITH AS 1742 SERIES UNLESS NOTED OTHERWISE. STREET SIGNS ARE TO BE INSTALLED IN ACCORDANCE WITH COUNCIL STANDARDS.
- ALL TEMPORARY WARNING SIGNS USED DURING CONSTRUCTION SHALL BE SUPPLIED AND MAINTAINED IN ACCORDANCE WITH AS 1742-3.
- TACTILE GROUND SURFACE INDICATORS ARE TO BE INSTALLED IN ACCORDANCE WITH THE DISABILITY DISCRIMINATION ACT AND RELEVANT COUNCIL STANDARD DRAWINGS.
- CONTRACTOR TO PROVIDE AN ENVIRONMENTAL MANAGEMENT PLAN INCLUDING SILT AND SEDIMENT RUNOFF PROTECTION ETC. PRIOR TO THE COMMENCEMENT OF WORKS.
- ALL TREES AND SHRUBS ARE TO BE RETAINED UNLESS OTHERWISE SHOWN. IF ROAD AND DRAINAGE CONSTRUCTION NECESSITATES THEIR REMOVAL, WRITTEN PERMISSION MUST BE OBTAINED FROM THE SUPERINTENDENT.
- TREES NOT SPECIFIED FOR REMOVAL ARE TO BE PROTECTED WITH APPROPRIATE EXCLUSION FENCING PRIOR TO COMMENCEMENT OF ANY WORKS.
- THE CONTRACTOR IS REQUIRED TO OBTAIN A 'PERMIT TO WORK' FROM MELBOURNE WATER'S SURVEILLANCE OFFICER AT THE PRE-COMMENCEMENT MEETING. THE CONTRACTOR IS REQUIRED TO ENSURE THAT THE 'PERMIT TO WORK' IS KEPT UP TO DATE FOR THE DURATION OF THE CONTRACT.

ENVIRONMENTAL



LOCALITY PLAN
NOT TO SCALE

WARNING
BEWARE OF TRANSMISSION LINES
TRANSMISSION POWER LINES IN CLOSE PROXIMITY OF WORKS, INDUCED ELECTRICAL CURRENTS MAY OCCUR. APPROPRIATE SAFETY MEASURES TO BE CARRIED OUT.

WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.



CONTRACTOR TO CONTACT RELEVANT SERVICE AUTHORITIES, ESTABLISH REQUIRED GUIDELINES AND COMPLY WITH AUTHORITIES' REQUIREMENTS.

DRAWING SCHEDULE

DRAWING	DESCRIPTION	SHEET No.	REVISION
CR100	FACE SHEET	1	B
CR200	FACE PLAN	2	B
CR201	SERVICES PLAN	3	B
CR300	ROAD LONG SECTIONS	4	B
CR400	ROAD CROSS SECTIONS - SHEET 1	5	A
CR401	ROAD CROSS SECTIONS - SHEET 2	6	B
CR500	INTERSECTION DETAILS	7	A
CR600	DRAINAGE LONG SECTIONS & PIT SCHEDULE	8	B
CR700	PAVEMENT AND TYPICAL DETAILS	9	A
CR800	SIGNAGE AND LINEMARKING	10	B

LEGEND

DESCRIPTION	EXISTING	PROPOSED
WATER MAIN, VALVE AND HYDRANT	--- DW ---	--- DW ---
WATER RECYCLED	--- NDW ---	--- NDW ---
UNDERGROUND ELECTRICITY	--- E ---	--- E ---
OVERHEAD ELECTRICITY & POLE	--- OE ---	--- OE ---
TELECOMMUNICATIONS & SERVICE PIT	--- T ---	--- T ---
OPTIC FIBRE	--- OF ---	--- OF ---
OVERHEAD TELECOMMUNICATIONS	--- OT ---	--- OT ---
GAS MAIN	--- G ---	--- G ---
SEWER & MAINTENANCE STRUCTURE	--- S ---	--- S ---
CENTRAL INVERT	--- I ---	--- I ---
COUNCIL STORMWATER DRAIN AND PIT	--- SD ---	--- SD ---
STORM WATER DRAINAGE PROPERTY INLETS	--- SWI ---	--- SWI ---
COUNCIL STORM WATER PITS	--- SWP ---	--- SWP ---
HOUSE DRAIN	--- HD ---	--- HD ---
AG DRAIN AND FLUSHER	--- AG ---	--- AG ---
STORM WATER DRAINAGE PIT NUMBER	Ex. 4.7	1
GAS & WATER CONDUITS	--- GW ---	--- GW ---
CONCRETE VEHICLE CROSSING	--- VC ---	--- VC ---
RIDGE / CHANGE OF GRADE LINE	--- RL ---	--- RL ---
SURFACE CONTOUR MINOR	- 169.00 -	169.00
SURFACE CONTOUR MAJOR	- 168.90 -	168.90
SURFACE LEVEL	E123.45	F124.68
BATTER LEVEL (TOP / TOE)	T124.80	T124.80
RETAINING WALL LEVEL (TOP/BOTTOM)	TW112.76	TW128.50 BW126.74
EARTHWORKS GRADE	1 in 150	1 in 150
SIGN AND POST	--- SP ---	--- SP ---
LIGHT & POLE (BY OTHERS)	--- LP ---	--- LP ---
STREET SIGN	--- SS ---	--- SS ---
PERMANENT SURVEY MARK	--- PSM ---	--- PSM ---
TEMPORARY BENCH MARK	--- TBM ---	--- TBM ---
BOLLARD	--- B ---	--- B ---
ROAD CHAINAGES	CH116.57 (L/R)T/P CH116.57	CH116.57 (L/R)T/P CH116.57
LOT CHAINAGES	CH20.06	CH20.06
SETOUT POINT	--- SP ---	--- SP ---
LIMIT OF WORKS	--- LW ---	--- LW ---
BATTER	--- B ---	--- B ---
EXCAVATION GREATER THAN 0.20m	--- E ---	--- E ---
FILLING GREATER THAN 0.20m	--- F ---	--- F ---
FENCE - TREE PROTECTION	--- FT ---	--- FT ---
FENCE - VEHICLE EXCLUSION	--- FE ---	--- FE ---
FENCES	--- F ---	--- F ---
GUARD RAIL	--- GR ---	--- GR ---
TREE (& SURVEYED CANOPY) TO BE RETAINED	--- TR ---	--- TR ---
TREE TO BE PROTECTED	--- TP ---	--- TP ---
TREE TO BE REMOVED	--- TR ---	--- TR ---
VEGETATION LINE	--- VL ---	--- VL ---
TREE RING FOR PROPOSED TREE LOCATION	--- TR ---	--- TR ---
FOOTPATH	--- FP ---	--- FP ---
TACTILE GROUND SURFACE INDICATOR	--- TGI ---	--- TGI ---
KERB TRANSITION	--- KT ---	B2 SM2

file name: 306199CR100.dwg, layout name: CR100, plotted by: Isach Giannopoulos, file location: \\spire.com.au\media\306199\CR100\ACAD\plot_date_03/11/2023_2:21 PM_Sheet_1 of 12_Sheets

Rev	Amendments	Approved	Date
B	ISSUED TO COUNCIL	D.S	03/11/23
A	ISSUED TO COUNCIL	D.S	17/10/23

Scale


© Spiire Australia Pty Ltd All Rights Reserved
This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

spiire
L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
spiire.com.au ABN 55 050 029 635

PEET
Designed
J.GIANNPOULOS
Authorised
M.HOLMES
Checked
D.SEVERINO
Date
OCT 2023


**NEWHAVEN ESTATE
STAGE 26
ROAD AND DRAINAGE
FACE SHEET**
WYNDHAM CITY COUNCIL
PEET NO.1895 PTY LTD
PRELIMINARY Drg No 306199CR100 Rev B

WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.



file name: 306199CR200.dwg, layout: name: CR200, created by: Jack Giannopoulos, date: 03/11/2023 2:21 PM, sheet: 2 of 12 sheets, location: \\spire.com.au\media\306199CR200\ACAD\plot.dwg

Rev	Amendments	Approved	Date
B	ISSUED TO COUNCIL	D.S	03/11/23
A	ISSUED TO COUNCIL	D.S	17/10/23




System Certified
 © Spiire Australia Pty Ltd All Rights Reserved
 This document is produced by Spiire Australia Pty Ltd solely for the benefit of and use by the client in accordance with the terms of the retainer. Spiire Australia Pty Ltd does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

L6 414 LA TROBE STREET PO BOX 16084 MELBOURNE
 VICTORIA 8007 AUSTRALIA T 61 3 9993 7888
 spiire.com.au ABN 55 050 029 635


Designed
 J.GIANNOPOULOS
 Authorised
 M.HOLMES
 Checked
 D.SEVERINO
 Date
 OCT 2023

NEWHAVEN ESTATE
STAGE 26
ROAD AND DRAINAGE
FACE PLAN
 WYNDHAM CITY COUNCIL
 PEET NO.1895 PTY LTD
 Drg No
306199CR200
 Rev
B



LOCALITY PLAN

SITE OF WORKS



MGA 94
ZONE 55

SCALE: 1:20,000 @ A1
1:40,000 @ A3
MELWAY / VICROADS: 359A11

SCHEDULE 8: DRAWING SCHEDULE

DRAWING No.	TITLE	SHEET NO.	CURRENT REVISION
CS100	NOTES, SCHEDULE & LOCATION PLAN	1	A
CS200	DETAIL PLAN	2	A
CS300	LONGITUDINAL SECTIONS SHEET 1	3	A
CS301	LONGITUDINAL SECTIONS SHEET 2	4	A
CS302	LONGITUDINAL SECTION SHEET 3	5	A

GENERAL NOTES:

- ONLY CONTRACTORS ACCREDITED BY GREATER WESTERN WATER TO SC1(a), SC1 AND SC7 SHALL BE ELIGIBLE TO CONSTRUCT THESE WORKS.
- ONLY PRODUCTS APPROVED AND CATALOGUED BY THE WATER AGENCY SHALL BE USED.
- WORKS MUST BE TO CONSTRUCTED ACCORDING TO THE MRWA EDITION OF THE WSAA SEWERAGE CODE OF AUSTRALIA WSA 02-2014-3.1.
- THE DESIGN CONSULTANT IS RESPONSIBLE FOR THE DESIGN AND COORDINATION OF THE WORKS. ANY PROBLEM ARISING DURING CONSTRUCTION SHALL BE DIRECTED TO THE CONSULTANT.

SURVEY, SET OUT AND ASSET RECORDING

- ALL CONTOURS AND LEVELS ARE IN METRES TO THE AUSTRALIAN HEIGHT DATUM (A.H.D.) MGA94, ZONE 55.
- ALL CO-ORDINATES SHOWN ARE TO MAP GRID OF AUSTRALIA (MGA).
- CHAINAGES SHOWN ON DETAIL PLANS ARE DISCONTINUOUS AT MAINTENANCE STRUCTURES.
- CHAINAGES SHOWN ON LONG SECTION SHEETS ARE CONTINUOUS.
- COORDINATES ARE TO SEWER LINE INTERSECTION POINT UNLESS OTHERWISE SHOWN.
- BEFORE COMMENCEMENT OF WORK, THE CONTRACTOR MUST COMPLETE A LEVEL CHECK BETWEEN ALL TBM'S TO VERIFY LEVEL VALUES.
- TBM'S AND CONTROL POINTS ARE TO BE MAINTAINED AND PROTECTED AT ALL TIMES DURING CONSTRUCTION.
- SHOULD ANY MARKS BE DISTURBED, THE CONTRACTOR WILL IMMEDIATELY NOTIFY THE CONSULTANT TO ARRANGE RE-INSTANTMENT AT THE CONTRACTORS EXPENSE.

PROPERTY CONNECTIONS

- NUMBER OF LOTS IN STAGE: 51 LOTS.
- NUMBER OF LOTS TO BE SEWERED: 72 LOTS
- ALL PROPERTY CONNECTIONS TO BE DN100 UNLESS OTHERWISE INDICATED.
- BRANCH TIE DISTANCE SHOWN ON DETAIL PLAN ARE FROM APPROVED SUBDIVISION SURVEY PEGS. BRANCH TIES FOR FUTURE LOTS ARE SHOWN AS A CHAINAGE. (CH) DISTANCE IS FROM THE DOWNSTREAM SEWER STRUCTURE.
- INVERT LEVEL OF THE PROPERTY CONNECTION POINT IS SHOWN OPPOSITE THE BRANCH POSITION.
- PROPERTY CONNECTIONS REQUIRING BOUNDARY TRAPS WILL BE DESIGNATED WITH "BT" AT THE END OF THE PROPERTY TYPE DESCRIPTION.
- DN100 SEWERS SHALL HAVE A GRADE OF 1 IN 60 UNLESS OTHERWISE STATED.

BENDS

- DETECTABLE MARKERS SHALL BE INSTALLED ABOVE ALL BENDS WHICH ARE NOT DIRECTLY CONNECTED TO MAINTENANCE STRUCTURES. REFER FIGURE 104B-B

EARTHWORKS AND RETAINING WALLS:

- IN AREAS SUBJECT TO EARTHWORKS, CONSTRUCTION OF SEWERS SHALL NOT COMMENCE UNTIL EARTHWORKS HAS BEEN COMPLETED UNLESS WRITTEN APPROVAL HAS BEEN GIVEN BY THE WATER AUTHORITY.

EMBEDMENT

- EMBEDMENT SHALL BE TYPE A (REFER MRWA-S-202) UNLESS OTHERWISE SPECIFIED ON THE LONG SECTION.

BACKFILL

- SELECTION AND COMPACTION OF TRENCH BACKFILL MATERIAL SHALL BE IN ACCORDANCE WITH THE WATER AGENCY ADOPTED VERSION OF MRWA SPECIFICATION NO 04-03.2.
- REFER TO LONG SECTION DRAWINGS FOR BACKFILL REQUIREMENTS.

COMPACTION TESTING

- TEST RESULTS SHALL BE PROVIDED TO THE SUPERINTENDENT PRIOR TO PRACTICAL COMPLETION / ACCEPTANCE OF WORKS.
- THE CONTRACTOR IS REQUIRED TO UNDERTAKE ALL TESTING OF FILL COMPACTION IN ACCORDANCE WITH MRWA BACKFILL SPECIFICATION 04-03.2.

SAFETY:

- PRIOR TO COMMENCEMENT OF WORKS ON SITE, THE CONTRACTOR MUST ENSURE THAT ALL MATTERS RELATING TO THE OCCUPATIONAL HEALTH AND SAFETY ACT 2004 AND OCCUPATIONAL HEALTH AND SAFETY REGULATIONS 2017, HAVE BEEN AND WILL BE COMPLIED WITH.

WORK ON LIVE SEWERS:

- ALL WORKS ON LIVE SEWERS MUST BE CARRIED OUT BY A WATER COMPANY ACCREDITED CONTRACTOR.
- ALL EXISTING SEWERS MUST BE PLUGGED TO STOP GAS EMISSIONS PRIOR TO ANY CONNECTIONS BEING MADE TO THESE SEWERS.
- TO ENABLE CONNECTIONS TO LIVE ASSETS OR ANY WORK ON LIVE ASSETS, THE CONTRACTOR SHALL SUBMIT THE APPROPRIATE FORMS TO THE SUPERINTENDENT AT LEAST 3 WORKING DAYS PRIOR TO ANY WORKS ON LIVE SEWERS.
- THE CONTRACTOR IS NOT PERMITTED TO BREAK INTO AN EXISTING LIVE PIPELINE, ENTER A LIVE SEWER OR REMOVE THE COVER TO A LIVE MAINTENANCE STRUCTURE UNLESS AUTHORISED BY THE WATER AGENCY.

TESTING:

- THE CONTRACTOR IS TO GIVE A MINIMUM OF TWO (2) DAYS NOTICE TO THE SUPERINTENDENT AND WATER AGENCY PRIOR TO THE TESTING BEING UNDERTAKEN. TESTING IS TO BE UNDERTAKEN IN THE PRESENCE OF SUPERINTENDENT.

CULTURAL HERITAGE REQUIREMENTS

- THE CONTRACTOR IS TO KEEP A COPY OF THE APPROVED CULTURAL HERITAGE MANAGEMENT PLAN ON SITE AT ALL TIMES DURING WORKS.

ENVIRONMENTAL MANAGEMENT PLAN:

- ON COMMENCEMENT OF CONSTRUCTION WORKS THE CONTRACTOR MUST COMPLY WITH THE RECOMMENDATIONS OF THE EPA PUBLICATION "CONSTRUCTION TECHNIQUES FOR SEDIMENT POLLUTION CONTROL" (PUBLICATION NO 275 1991).
- PRIOR TO THE COMMENCEMENT OF WORK, THE CONTRACTOR IS TO SUBMIT A SITE ENVIRONMENTAL MANAGEMENT PLAN TO MELBOURNE WATER.
- ALL TREES AND VEGETATION ARE TO BE PROTECTED UNLESS OTHERWISE INDICATED FOR REMOVAL. THE EXTENT OF ANY VEGETATION REMOVAL SHALL BE CONFIRMED ON SITE WITH THE SUPERINTENDENT AND LOCAL COUNCIL PRIOR TO COMMENCEMENT, AND IN ACCORDANCE WITH ANY PLANNING PERMITS. ANY REMOVAL SHALL BE DOCUMENTED.
- ALL AREAS CONTAINING CREEK VEGETATION, TREES AND REVEGETATED AREAS NEAR THE CONSTRUCTION ZONE ARE TO BE FENCED OFF DURING THE WORKS WITH SECURE AND HIGHLY VISIBLE MATERIAL SUCH AS PARA-WEABBING FENCING.
- ENSURE ALL MACHINERY, EQUIPMENT AND/OR FOOTWEAR ENTERING THE SITE IS WEED AND PATHOGEN FREE.

CONSULTANT'S REQUIREMENTS:

- THE CONTRACTOR IS TO CONTACT ALL LOCAL SERVICE AUTHORITIES FOR INFORMATION REGARDING EXISTING SERVICE LOCATIONS PRIOR TO COMMENCING ANY EXCAVATION. THE CONTRACTOR IS TO MAKE ALLOWANCE IN TENDER RATES FOR PROOFING OF CRITICAL SERVICES FOR ASSISTANCE IN LOCATING SERVICES OR IN AN EMERGENCY TELEPHONE 'DIAL BEFORE YOU DIG'.
- THE CONTRACTOR SHALL REINSTATE ANY AFFECTED ASSETS (I.E FOOTPATH, VEHICLE CROSSINGS & NATURE STRIP) TO THE REQUIREMENTS OF THE MUNICIPAL COUNCIL AT CONTRACTORS EXPENSE.
- CONSTRUCTION PRE COMMENCEMENT DOCUMENTATION MUST BE SUBMITTED TO THE SUPERINTENDENT AS PER WATER AUTHORITY REQUIREMENTS.
- SETOUT AND VERIFICATION OF LEVELS SHALL REMAIN THE RESPONSIBILITY OF THE CONTRACTOR.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF THE HORIZONTAL ALIGNMENT AND FOR OFFSETTING PEGS DURING CONSTRUCTION
- THE CONTRACTOR SHALL OBTAIN A ROAD OPENING PERMIT FOR ANY WORKS WITHIN THE ROAD RESERVE AND COMPLY WITH ALL REQUIREMENTS
- ONLY AN ACCREDITED SURVEYOR MAY BE USED TO UNDERTAKE ASSET RECORDING OF THE WORK. ALL SURVEYING WORKS AND DATA TO BE SUBMITTED MUST BE IN ACCORDANCE WITH THE WATER AUTHORITY'S REQUIREMENTS.
- ALL LONG RADIUS BENDS AND CURVED SEWERS ARE TO HAVE MARKER DISCS PLACED AS PER STANDARD DRAWING MRWA-S-104B WITH EXCEPTION TO DEPTH WHICH IS TO BE LAID AT MAX 1m FROM THE SURFACE.
- ALL CURVED SEWER TO BE CONSTRUCTED IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS. (24 HOUR CURING TIME FOR GLUE PRIOR TO COLD BENDING REQUIRED)

SCHEDULE 6: MAINTENANCE HOLES

MAINTENANCE HOLE ID	MH SHAFT TYPE (GRP/PP (Plastic) / Concrete)	MH TOP TYPE (Conical/Flat)	COVER CLASS	INTERNAL DIAMETER (mm)	MIN. WALL THICKNESS (mm)	DEPTH TO INVERT (mm)	DROPS	LADDER (L) STEP IRONS (S) LANDING (Ld)	CORROSION PROTECTION (Coating / PE or PVC Lining)	SHAFT RE-INFORCEMENT	COMMENTS (Offsets / Details)
Ex SH-1-5	CONCRETE	CONICAL	B	1050	150	3890	-	S	-	-	EXISTING
NH26-3	CONCRETE	FLAT	B	1050	150	2280	1 x DN150	S	-	-	E: 294.644.606 N: 5810828.422
NH26-4	CONCRETE	CONICAL	B	1050	150	2000	-	S	-	-	-
NH26-6	CONCRETE	CONICAL	D	1050	150	1620	-	S	-	-	-
NH26-11	CONCRETE	CONICAL	B	1050	150	2200	-	S	-	-	-
NH26-13	CONCRETE	CONICAL	B	1050	150	1570	-	S	-	-	-
NH26-15	CONCRETE	FLAT	B	1050	150	3720	-	S	-	-	E: 294.486.063 N: 5810837.726
NH26-17	CONCRETE	FLAT	B	1050	150	3120	-	S	-	-	E: 294.652.875 N: 5810808.713

SCHEDULE 1: NEW PIPE

PIPE SIZE	PIPE TYPE	LENGTH (m)	PIPE CLASS	STANDARD
DN150	UPVC-DWV	1056.00	SN8	WSA PC 230

SCHEDULE 2: PROPERTY CONNECTIONS

CONNECTION TYPE	TYPE 1a	TYPE 1b	TYPE 2	TYPE 4a	TYPE 4b	TYPE S	TYPE 4S	TYPE B	TYPE 4B	JUMP UP TYPE F COUPLINGS (TY2 or 4)
QUANTITIES	-	1	67	-	-	3	-	1	-	15

SCHEDULE 3: SERVICE OFFSETS AND LOCATIONS:

ROAD NAME	POTABLE WATER		RECYCLED WATER		GAS		NBN (TELECOM)		ELECTRICITY			
	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	SIDE	OFFSET	POLE		U/G CABLE	
									SIDE	OFFSET		SIDE
FETE WAY	W	2.90	W	2.42	W	2.00	E	1.83	E	0.80x	E	2.55
VOYAGER BOULEVARD	N	2.90	N	2.42	N	2.00	S	1.83	S	0.80x	S	2.55
BANQUET DRIVE	N	3.00	N	2.52	N	2.10	S	1.83	S	0.80x	S	2.55
CAVILL WAY	W	3.00	W	2.52	W	2.10	E	1.83	E	0.80x	E	2.55

- TELECOMMUNICATIONS AND ELECTRICITY CABLES TO BE CONSTRUCTED IN A COMMON TRENCH IN ACCORDANCE WITH ELECTRICITY AUTHORITY STANDARD DRG'S.
- GAS AND WATER MAINS TO BE CONSTRUCTED IN A COMMON TRENCH.
- x = OFFSET FROM BACK OF KERB (TO BE CONFIRMED BY ELECTRICAL CONSULTANTS PLANS)

SCHEDULE 4: MAINTENANCE STRUCTURES

MAINTENANCE STRUCTURE ID	TYPE - (IS/MS/MC)	COVER CLASS	DEPTH TO INVERT (mm)	SHAFT CONNECTIONS	COMMENTS / REFERENCES (Offsets / Details)
NH26-2MC	MC	B	2740	-	E: 294.553.522 N: 5810844.263
NH26-5MS	MS	B	1600	-	E: 294.741.757 N: 5810811.525
NH26-7MS	MS	B	1530	1 x DN100	-
NH26-8MS	MS	B	1260	-	-
NH26-9MS	MS	B	2210	-	-
NH26-10MS	MS	B	2100	1 x DN100	-
NH26-12IS	IS	B	1240	-	E: 294.762.503 N: 5810962.388
NH26-14IS	IS	B	1250	-	E: 294.661.152 N: 5810973.875
NH26-16MC	MC	B	3480	1 x DN100	E: 294.553.522 N: 5810844.263
NH26-18MS	MS	B	2810	-	E: 294.670.131 N: 5810805.712
NH26-19IS	IS	B	2200	-	E: 294.742.34.7 N: 5810793.152

SCHEDULE 5: WATER AGENCY GRANTED DISPENSATIONS (N/A)

ID	LOCATION	ASSET/FEATURE	DESCRIPTION OF DISPENSATION ACCEPTED
NH26-6	FRONT OF LOT		STRUCTURE WITHIN EASEMENT AT FRONT OF LOT
NH26-7MS	FRONT OF LOT		STRUCTURE WITHIN EASEMENT AT FRONT OF LOT
NH26-8MS	FRONT OF LOT		STRUCTURE WITHIN EASEMENT AT FRONT OF LOT
NH26-11	FOOTPATH		CLEARANCE BETWEEN PIT COVER AND THE BOUNDARY IS 650-800mm
NH26-13	FOOTPATH		CLEARANCE BETWEEN PIT COVER AND THE BOUNDARY IS 560-800mm

SCHEDULE 7: WATER SEALS, BOUNDARY TRAPS AND SYPHONS

STRUCTURE TYPE	BOUNDARY TRAP	WATER SEAL	SYPHONS
QUANTITY	0	0	0



WARNING
BEWARE OF UNDERGROUND/OVERHEAD SERVICES
THE LOCATION OF SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN. SPECIAL CONSIDERATION SHOULD BE GIVEN TO CONSTRUCTION PROCEDURES UNDER OVERHEAD ELECTRICITY TRANSMISSION LINES.

LEGEND

<ul style="list-style-type: none"> INSPECTION SHAFT (IS) MAINTENANCE SHAFT (MS) MAINTENANCE CHAMBER (MC) MAINTENANCE HOLE (MH) MAINTENANCE HOLE (COVER CENTERED OVER BLACK SEGMENT) WATER SEAL END OF PIPE (EP) LOTS WITHOUT REASONABLE ACCESS 	<ul style="list-style-type: none"> IL = Invert Level TW = Top of Retaining Wall TY = Property Connection Type TP = Tangent Point BT = Boundary Trap Lot F100.00 Finished Surface Level E100.00 Existing Surface Level T100.00 Top/Toe of Batter Level RETAINING WALL 	<ul style="list-style-type: none"> EXISTING SERVICES: GAS OPTIC FIBRE TELECOM ELECTRICITY DRINKING WATER NON-DRINKING WATER
--	---	--

DESIGNED	J.GIANNPOULOS	PROJECT NUMBER	####
DATE:	16/10/23	AUTHORISED	
DRAWN	J.GIANNPOULOS	REGISTERED ENGINEER	
DATE:	16/10/23	NAME:	XXXX
CHECKED		PE REG. NO.:	
DATE:		DATE:	

PEET NO.1895 PTY LTD
PEET

spiire
L6 414 La Trobe Street PO Box 16084 Melbourne
Victoria 3007 Australia T 61 3 9950 7888
spiire.com.au ABN 55 050 023 635



Greater Western Water

GREATER WESTERN WATER
WYNDHAM CITY COUNCIL
NEWHAVEN ESTATE STAGE 26
SEWER RETICULATION EXT.NO.
NOTES, SCHEDULES & LOCATION PLAN


SCALE: AS SHOWN
SHEET: 1 OF 5
SPIIRE DWG No.: 306199CS100
REV A
PRELIMINARY

NOTES:

- CONTRACTOR TO CONSTRUCT FINISHED SURFACE LEVEL OF MAINTENANCE STRUCTURE COVER AS PER TABLE 313-E AND ASSOCIATED NOTES AS SHOWN IN MRWA WSAW SEWER CODE STANDARD DRAWING MRWA-S-313. THE SEWER CONTRACTOR IS TO LIAISE WITH THE ROAD CONTRACTOR TO CONFIRM FINISHED SURFACE LEVELS AND CONSTRUCT THE COVER ABOVE IF REQUIRED BY THE STANDARD DRAWINGS.
- DEPTH TO INVERT SHOWN ON LONGITUDINAL SECTIONS IS FROM FINISHED SURFACE LEVEL TO THE INVERT. ADDITIONAL DEPTH MAY BE REQUIRED TO SUIT THE RELEVANT MAINTENANCE COVER REQUIREMENTS.




DATUM	42											
PIPE DETAILS	150Ø PVC		150Ø PVC				150Ø PVC		150Ø PVC		150Ø PVC	
GRADE	1:57		1:57				1:180		1:180		1:180	
EMBEDMENT	F		R				F		R		F	
DEPTH TO INVERT	3.89	3.49	2.74	2.71	2.28	2.25	2.00	1.97	1.60	1.57	1.42	
INVERT LEVEL	45.88	46.19	47.15	47.18	47.69	47.72	47.97	48.00	48.61	48.64	8.66	
FINISHED SURFACE LEVEL	49.77	49.68	49.89		49.98		49.97		50.21	50.09		
CHAINAGE	0.00	17.77	72.24		164.75		208.77		263.30	268.28		
LENGTH	(17.77)		(54.47)				(92.51)		(44.02)		(54.53)	



DATUM	43									
PIPE DETAILS	150Ø PVC		150Ø PVC		150Ø PVC				150Ø PVC	
GRADE	1:180		1:180		1:159				1:90	
EMBEDMENT	F		R		F				R	
DEPTH TO INVERT	1.42	1.42	1.62	1.59	1.53	1.50			1.26	
INVERT LEVEL	48.66	48.76	48.77	48.80	49.11	49.14			49.77	
FINISHED SURFACE LEVEL	50.09	50.17	50.39		50.64				51.03	
CHAINAGE	268.28	285.20	287.40		336.50				393.00	
LENGTH	(16.93)		(2.20)		(49.10)				(56.50)	

DATUM	43				
PIPE DETAILS	150Ø PVC		150Ø PVC		
GRADE	1:180		1:180		
EMBEDMENT	F		R		
DEPTH TO INVERT	2.00	1.97	2.21	2.18	2.10
INVERT LEVEL	47.97	48.00	48.10	48.13	48.21
FINISHED SURFACE LEVEL	49.97		50.31		50.31
CHAINAGE	0.00		18.61		32.61
LENGTH	(18.61)		(14.00)		



file name: 306199CS300.dwg, layout: name: CS300, plotted by: Jack Giampanolis, file location: \\spire.com.au\data\306199CS300.dwg, date: 16/10/2023 2:48 PM, sheet: ### of ###, sheets:

REV	DESCRIPTION	DATE	REG. ENG.
A	ISSUED TO COUNCIL	16/10/23	D.S.

LEGEND

- INSPECTION SHAFT (IS)
- MAINTENANCE SHAFT (MS)
- MAINTENANCE CHAMBER (MC)
- MAINTENANCE HOLE (MH)
- MAINTENANCE HOLE (COVER)
- CENTERED OVER BLACK SEGMENT
- WATER SEAL
- END OF PIPE (EP)
- LOTS WITHOUT REASONABLE ACCESS

EXISTING SERVICES:

- GAS
- OPTIC FIBRE
- TELECOM
- ELECTRICITY
- DRINKING WATER
- NON-DRINKING WATER

SYMBOLS:

- IL = Invert Level
- TW = Top of Retaining Wall
- TY = Property Connection Type
- TP = Tangent Point
- BT = Boundary Trap Lot
- F100.00 = Finished Surface Level
- E100.00 = Existing Surface Level
- T100.00 = Top/Toe of Batter Level
- RETAINING WALL

DESIGNED	J.GIANNPOULOS	PROJECT NUMBER	###
DATE	16/10/23	AUTHORISED	
DRAWN	J.GIANNPOULOS	REGISTERED ENGINEER	
DATE	16/10/23	NAME	XXXX
CHECKED		PER REG. NO.	
DATE		DATE	

PEET NO.1895 PTY LTD

spiire

L6 414 La Trobe Street PO Box 16084 Melbourne
Victoria 3007 Australia T 61 3 9950 7888
spire.com.au ABN 55 050 029 635

GREATER WESTERN WATER

WYNDHAM CITY COUNCIL


NEWHAVEN ESTATE STAGE 26
SEWER RETICULATION EXT.NO.

LONGITUDINAL SECTION SHEET 1


SCALE: AS SHOWN	REV
SHEET: 3 OF 5	A
SPiire DWG No.: 306199CS300	
PRELIMINARY	

NOTES:

- CONTRACTOR TO CONSTRUCT FINISHED SURFACE LEVEL OF MAINTENANCE STRUCTURE COVER AS PER TABLE 313-E AND ASSOCIATED NOTES AS SHOWN IN MRWA WSAA SEWER CODE STANDARD DRAWING MRWA-S-313. THE SEWER CONTRACTOR IS TO LIAISE WITH THE ROAD CONTRACTOR TO CONFIRM FINISHED SURFACE LEVELS AND CONSTRUCT THE COVER ABOVE IF REQUIRED BY THE STANDARD DRAWINGS.
- DEPTH TO INVERT SHOWN ON LONGITUDINAL SECTIONS IS FROM FINISHED SURFACE LEVEL TO THE INVERT. ADDITIONAL DEPTH MAY BE REQUIRED TO SUIT THE RELEVANT MAINTENANCE COVER REQUIREMENTS.




NH26-10MS NH26-11 NH26-12IS





DATUM	44											
PIPE DETAILS	150φ PVC						150φ PVC					
GRADE	1:117						1:90					
EMBEDMENT												
BACKFILL TYPE	F											
DEPTH TO INVERT	2.10	2.07					2.20	2.17				1.24
INVERT LEVEL	4.8.21	4.8.24					4.9.35	4.9.38				4.9.87
FINISHED SURFACE LEVEL	50.31						51.56					51.11
CHAINAGE	32.61						163.01					207.01
LENGTH	(130.40)						(44.00)					

NH26-9MS NH26-13 NH26-14IS EX. SH-1-5 TP NH26-15



DATUM	44											
PIPE DETAILS	150φ PVC						150φ PVC					
GRADE	1:70						1:89					
EMBEDMENT												
BACKFILL TYPE	F											
DEPTH TO INVERT	2.21	2.18					1.57	1.54				1.25
INVERT LEVEL	4.8.10	4.8.13					4.9.99	50.02				50.51
FINISHED SURFACE LEVEL	50.31						51.56					51.76
CHAINAGE	0.00						130.40					174.40
LENGTH	(130.40)						(44.00)					



file name: 306199CS300.dwg, layout: sewer_CS301, plotted by: Jacob Giannopoulos, file location: \\spiire.com.au\media\306199CS301\306199CS301\306199CS301.dwg, date: 16/10/2023 2:48 PM, sheet: ### of ###, sheets

LEGEND

- INSPECTION SHAFT (IS)
- MAINTENANCE SHAFT (MS)
- MAINTENANCE CHAMBER (MC)
- MAINTENANCE HOLE (MH)
- MAINTENANCE HOLE (COVER)
- CENTERED OVER BLACK SEGMENT
- WATER SEAL
- END OF PIPE (EP)
- LOTS WITHOUT REASONABLE ACCESS

EXISTING SERVICES:

- GAS
- OPTIC FIBRE
- TELECOM
- ELECTRICITY
- DRINKING WATER
- NON-DRINKING WATER

SYMBOLS:

- IL = Invert Level
- TW = Top of Retaining Wall
- TY = Property Connection Type
- TP = Tangent Point
- BT = Boundary Trap Lot
- F100.00 = Finished Surface Level
- E100.00 = Existing Surface Level
- T100.00 = Top/Toe of Batter Level
- RETAINING WALL

DESIGNED: J.GIANNPOULOS DATE: 16/10/23

DRAWN: J.GIANNPOULOS DATE: 16/10/23

CHECKED: DATE:

PROJECT NUMBER: ###

AUTHORISED: DATE:

REGISTERED ENGINEER: NAME: PE REG. NO. XXXX DATE:

PEET NO.1895 PTY LTD

spiire

Greater Western Water


WYNDHAM CITY COUNCIL

NEWHAVEN ESTATE STAGE 26

SEWER RETICULATION EXT.NO.

LONGITUDINAL SECTION SHEET 2

SCALE: AS SHOWN
SHEET: 4 OF 5
SPIRE DWG No.: 306199CS301
REV: A
PRELIMINARY



- NOTES:**
- CONTRACTOR TO CONSTRUCT FINISHED SURFACE LEVEL OF MAINTENANCE STRUCTURE COVER AS PER TABLE 313-E AND ASSOCIATED NOTES AS SHOWN IN MRWA WSAA SEWER CODE STANDARD DRAWING MRWA-5-313. THE SEWER CONTRACTOR IS TO LIAISE WITH THE ROAD CONTRACTOR TO CONFIRM FINISHED SURFACE LEVELS AND CONSTRUCT THE COVER ABOVE IF REQUIRED BY THE STANDARD DRAWINGS.
 - DEPTH TO INVERT SHOWN ON LONGITUDINAL SECTIONS IS FROM FINISHED SURFACE LEVEL TO THE INVERT. ADDITIONAL DEPTH MAY BE REQUIRED TO SUIT THE RELEVANT MAINTENANCE COVER REQUIREMENTS.




FIGURE 1
TYPE F BACKFILL





FIGURE 2
TYPE R BACKFILL



sewer backfill procedure

9.121 GITA COMPLIANCE CHECKLIST

As detailed in Section 4.2.3 of the MRWA specification, the GITA is required to provide a checklist for each section of the pipeline where a significantly different clay or clay like cohesive soil is to be used.

Line Description

Section End Description (M structure, X-Y, Address)	Various
Section End Description (M structure, X-Y, Address)	Various
Linear Distance	Various
Number of Compaction Tests Required	1 per 2 nd 200mm layer/50m length

Specification	Upper Depth Range	Lower Depth Range
Depth Range	Surface to -4m	Exceeding -4m
Optimum Backfill Material	Excavated insitu materials	VicRoads Crushed Rock (or refer to Section 9.1)
Backfill Material Requirements	95% SMDD/98% SMDD (top 0.3m in all areas)	95% SMDD/98% SMDD (top 0.3m in all areas)
AS2870-2011 Classification	Class H2 to Class E	N/A
High Risk Factors Likely to be Found	1. Pockets of high plasticity clays may result in large soil clods during excavation. Soil clods in this size/form is unsuitable as backfill and shall be broken down to minus 100mm prior to backfilling. 2. Side wall collapse - very high risk	N/A
Risk Controls Required	1. Management of soil clods 2. Shielding	N/A
Compaction machine	Excavator	Excavator
Compaction Type	Padfoot wheel attachment	Padfoot wheel attachment
Compaction Weight	20 - 30 tonne	20 - 30 tonne
Number of Passes per Layer	The actual number of passes shall depend on the moisture condition of the fill source, maximum particle size of clods and the size of the excavator. A trial section shall be	The actual number of passes shall depend on the moisture condition of the fill source and the size of the excavator. A trial section shall be

sewer backfill procedure

Line Description	Work Method	Work Method
Loose Layer Thickness	No greater than 200mm	No greater than 200mm
Moisture Limits	85% - 115% moisture ratio	85% - 115% moisture ratio
Max time to Stockpile (20°C - 30°C)	72 hours (if suitably sealed)	N/A
Max time to Stockpile (>30°C)	24 hours	N/A
Material Test Data Results	Refer to section 8.2	N/A
Risk and Cost Assessments	-	-

10. LIMITATIONS

This document is COPYRIGHT - all rights reserved. No part of this document may be reproduced or copied in any form or by means without written permission by Ground Science Pty Ltd. All other property in this submission shall not pass until all fees for preparation have been settled. This submission is for the use only of the party to whom it is addressed and for no other purpose. No responsibility is accepted to any third party who may use or rely on the whole or any part of the content of this submission. No responsibility will be taken for this report if it is altered in any way, or not reproduced in full.

10.1 SUBSIDIENCE

Subsidence of the backfilled trenches may occur either in the short term or long term after the works have been completed and is generally caused by consolidation of the underlying soils. Subsidence of a backfill trench may occur as a result of poor workmanship, failure to place the backfill materials in the layer depths/ minimum compaction levels detailed in this document and/or softening of the soils either naturally or under the influence of moisture from damaged services. Ground Science and the contents of this geotechnical field procedure do not warrant the outcome of the trench backfill. Any subsidence that has occurred which has proved to be a result of the work undertaken by the Contractor, shall be suitably remediated at their own cost. If the subsidence has been caused by poor compaction, the Contractor may be held responsible and accountable.

11. REFERENCES

- AS1289 "Methods of Testing Soils for Engineering Purposes"
- AS1726 "Geotechnical Investigations"
- AS3798 2007 "Guidelines on Earthworks for Commercial and Residential Developments"
- AS2870 2011 "Residential Slabs and Footing"

Newhaven Estate, Tarnet G3228.2 AA		9 December 2016 Page 7	
Newhaven Estate, Tarnet G3228.2 AA		9 December 2016 Page 8	
ISSUED TO COUNCIL	16/10/23	D.S.	
REV	DESCRIPTION	DATE	REG. ENG.

LEGEND

INSPECTION SHAFT (IS)	IL = Invert Level	EXISTING SERVICES:
MAINTENANCE SHAFT (MS)	TW = Top of Retaining Wall	--- GAS
MAINTENANCE CHAMBER (MC)	TY = Property Connection Type	--- OPTIC FIBRE
MAINTENANCE HOLE (MH)	TP = Tangent Point	--- TELECOM
MAINTENANCE HOLE (COVER CENTERED OVER BLACK SEGMENT)	BT = Boundary Trap Lot	--- ELECTRICITY
WATER SEAL	F100.00 Finished Surface Level	--- DRINKING WATER
END OF PIPE (EP)	E100.00 Existing Surface Level	--- NON-DRINKING WATER
LOTS WITHOUT REASONABLE ACCESS	T100.00 Top/Toe of Batter Level	
	RETAINING WALL	

DESIGNED J.GIANNPOULOS DATE: 16/10/23	PROJECT NUMBER ####	PEET NO.1895 PTY LTD PEET	spiire L6 414 La Trobe Street PO Box 16084 Melbourne Victoria 3007 Australia T 61 3 9993 7888 spiire.com.au ABN 55 050 023 635	GREATER WESTERN WATER WYNDHAM CITY COUNCIL NEWHAVEN ESTATE STAGE 26 SEWER RETICULATION EXT.NO. LONGITUDINAL SECTIONS SHEET 3	SCALE: AS SHOWN
DRAWN J.GIANNPOULOS DATE: 16/10/23	AUTHORISED DATE:				SHEET: 5 OF 5
CHECKED DATE:	REGISTERED ENGINEER NAME: PE REG. NO. XXXX DATE:				SPIIRE DWG No.: 306199CS302 REV A PRELIMINARY

file name: 306199CS302.dwg, layout: new, c:\306199CS302, plotted by: Jack Giampanolis, file location: \\spiire.com.au\media\306199CS302\306199CS302.dwg, 10/2023 2:48 PM Sheet ### of ### Sheets