



**Legend**


- - - Stage Boundary
- 0.5m Contours
- Future Allotment Layout
- Mandatory Built to Boundary Wall
- Nominal Built to Boundary Wall
- Preferred Driveway Location
- Preferred Private Open Space Location
- Indicative On-Street Parking
- Indicative Bin Pad Location for Lot 100 and 101
- Easement
- Indicative 2.5m Shared Pedestrian/Cycle Path
- Indicative 2.0m Shared Pedestrian/Cycle Path\*
- Indicative 1.5m Footpath
- Sewer Pump Station

**Note:**  
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.  
Dimensions have been rounded to the nearest 0.1 metres.  
Areas have been rounded down to the nearest 5m<sup>2</sup>.  
The boundaries shown on this plan should not be used for final detailed engineers design.  
\*2.0m shared pathway provided to the full southern boundary of the river park precinct off which a path network in the open space area will adjoin.

**Source Information:**  
**Site boundaries:** Wolter Consulting  
**Adjoining information:** DCDB  
**Contours:** THG



**Diagram A**  
SCALE: 1 : 5,000



**KEY MAP**  
SCALE: 1 : 20,000

**Parking Breakdown**

Total On-Street Parking Spaces Required .....	54
Total On-Street Parking Spaces Provided .....	56

PLAN REF: 7025 - 305  
Rev No: D  
DATE: 20 FEBRUARY 2023  
CLIENT: PEET  
DRAWN BY: JC/NF  
CHECKED BY: DG



**RIVERBANK**  
**OVERALL STAGE 2**  
**PROPOSAL PLAN - SHEET 1**



**URBAN DESIGN**  
Level 4 HQ South  
520 Wickham Street  
PO Box 1559  
Fortitude Valley QLD 4006  
T +61 7 3539 9500  
W rpsgroup.com



© COPYRIGHT PROTECTS THIS PLAN  
Unauthorised reproduction or amendment not permitted. Please contact the author.

**Development Statistics**

	Stage 2A	Stage 2B	Stage 2C	Stage 2D	Stage 2E	Overall	
<b>Stage Area</b>	<b>1.256 ha</b>	<b>16.072 ha</b>	<b>9.112 ha</b>	<b>2.186 ha</b>	<b>0.256 ha</b>	<b>28.882 ha</b>	
<b>Saleable Area</b>							
Single Family Allotments	0.839 ha	1.144 ha	0.906 ha	1.438 ha	0.256 ha	<b>4.583 ha</b>	
<b>Total Area of Allotments</b>	<b>0.839 ha</b>	<b>1.144 ha</b>	<b>0.906 ha</b>	<b>1.438 ha</b>	<b>0.256 ha</b>	<b>4.583 ha</b>	
<b>Open Space</b>							
Pedestrian Linkage / Road Reserve	—	—	—	0.030 ha	—	<b>0.030 ha</b>	
Regional Open Space	—	10.697 ha	7.830 ha	—	—	<b>18.527 ha</b>	
Drainage Reserve	—	—	—	0.080 ha	—	<b>0.080 ha</b>	
Future Road	—	3.734 ha	—	—	—	<b>3.734 ha</b>	
<b>Total Open Space</b>	<b>—</b>	<b>14.431 ha</b>	<b>7.830 ha</b>	<b>0.110 ha</b>	<b>—</b>	<b>22.371 ha</b>	
<b>Area of New Road</b>							
	<b>0.417 ha</b>	<b>0.497 ha</b>	<b>0.376 ha</b>	<b>0.638 ha</b>	<b>—</b>	<b>1.928 ha</b>	
<b>Residential Allotments</b>							
<b>Squat Allotments</b>	<b>Typical Size</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	
Squat Allotments	15m x 20.5m	—	—	—	4	—	4
<b>Sub-Total Squat Allotments</b>		<b>—</b>	<b>—</b>	<b>—</b>	<b>4</b>	<b>—</b>	<b>4</b>
<b>25m Deep Allotments</b>		<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>
Courtyard Allotment	14m x 25m	2	—	—	—	—	2
<b>Sub-Total 25m Deep Allotments</b>		<b>2</b>	<b>—</b>	<b>—</b>	<b>—</b>	<b>—</b>	<b>2</b>
<b>26m Deep Allotments</b>	<b>Typical Size</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>
Premium Villa Allotment	12.5m x 26m	—	—	—	6	—	6
Courtyard Allotment	14m x 26m	—	—	—	2	—	2
<b>Sub-Total 26m Deep Allotments</b>		<b>—</b>	<b>—</b>	<b>—</b>	<b>8</b>	<b>—</b>	<b>8</b>
<b>30m Deep Allotments</b>	<b>Typical Size</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>
Villa Allotment	10.7m x 30m	—	5	2	3	—	10
Villa Allotment Type 2	11.2m x 30m	—	7	5	3	—	15
Premium Villa Allotment	12.5m x 30m	4	6	7	5	—	22
Courtyard Allotment	14m x 30m	3	9	5	7	—	24
Traditional Allotment	20m x 30m	1	1	—	2	—	4
<b>Sub-Total 30m Deep Allotments</b>		<b>8</b>	<b>28</b>	<b>19</b>	<b>20</b>	<b>—</b>	<b>75</b>
<b>32m Deep Allotments</b>	<b>Typical Size</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>	<b>Lots</b>
Villa Allotment	10.7m x 32m	—	—	—	1	—	1
Premium Villa Allotment	12.5m x 32m	1	—	—	2	3	6
Courtyard Allotment	14m x 32m	7	—	1	2	1	11
Traditional Allotment	20m x 32m	—	—	—	—	1	1
<b>Sub-Total 32m Deep Allotments</b>		<b>8</b>	<b>—</b>	<b>1</b>	<b>5</b>	<b>5</b>	<b>19</b>
<b>Total Residential Allotments</b>		<b>18</b>	<b>28</b>	<b>20</b>	<b>37</b>	<b>5</b>	<b>108</b>
<b>Length of New Road</b>							
16.5m Wide New Road	—	185m	209m	368m	—	<b>762m</b>	
18.0m Wide New Road	75m	98m	12m	—	—	<b>185m</b>	
22.0m Wide New Road	125m	—	—	—	—	<b>125m</b>	
Shared Access Driveway	—	—	—	15m	—	<b>15m</b>	
<b>Total Length of New Road</b>	<b>200m</b>	<b>283m</b>	<b>221m</b>	<b>383m</b>	<b>—</b>	<b>1087m</b>	

**SITE COVER**

Building Height	Lot Size			
	300m² or less	301 - 400m²	401 - 500m²	501m² +
8.5m or less	75%	70%	60%	60%

**GARAGE AND CARPORT OPENINGS**

Covered car space opening(s) per street frontage			
	Less Than 12.5m	12.5m to 18m	Greater than 18m
Single Storey Dwelling	a. maximum 50% of the front frontage width (being the frontage vehicle access is from); and	a. 6m wide maximum; and	a. recessed at least 1.0m behind the main building line
Additional Requirements for Single Storey Dwelling	b. recessed: i. at least 1.0m behind the main building line; or ii. at least 1.0m behind a front portico and no more than 2.0m in front of the main building line.		
Two Storey Dwelling	a. 6.0m wide maximum; and b. recessed 1.0m behind the front wall or balcony of upper level.  Editor's note - Front wall is to have a minimum length of 40% of the adjoining frontage.		

**BUILT TO BOUNDARY WALLS RESIDENTIAL USES**

Lot frontage width	Mandatory / Optional	Length and Height of Built to Boundary Wall
<b>More than 7.5m to 12.5m</b>	Mandatory - one side	Max Length: 60% of the length of the boundary Max Height: 4.5m
<b>More than 12.5m to 18m</b>	Optional: i. on 1 boundary only; ii. where the built to boundary wall adjoins a lot with a frontage less than 18m. Not permitted - Otherwise	Max Length: the lesser of 15m or 60% of the length of the boundary Max Height: 4.5m
<b>Greater than 18m</b>	Not permitted	Not permitted*

Note - Max Length includes the length of walls of any other buildings on the same boundary. e.g. detached garage, carport or shed.

Note - For the maximum height of domestic outbuildings refer to the examples that achieve aspects of the performance outcomes for building height and domestic outbuildings.

\*Note - Built to boundary walls are not permitted, however, reduced side and rear boundary clearances may be permitted as prescribed (e.g. QDC).

**PLAN OF DEVELOPMENT SETBACKS**

Height of Wall	Frontage						Side	Rear
	Primary			Secondary to street			Non-built to boundary wall	To OMP and wall
	To Wall	To OMP*	To covered car parking space	To Wall	To OMP*	To covered car parking space	To Wall	To OMP* and Wall
Less than 4.5m	Min. 3m	Min. 2m	Min. 5.4m	Min. 2m	Min. 1m	Min. 5.4m	Min. 1m**	As per QDC
4.5m to 8.5m	Min. 3m	Min. 2m	N/A	Min. 2m	Min. 1m	N/A	#Min. 1m**	As per QDC

\* OMP includes architectural features such as piers, pylons, eaves, etc.

\*\* Eaves may encroach to a maximum of 450mm.

# One side must be setback a min. 1.5m to the wall.

Note - This is a qualifiable standard that is an alternative provision to QDC, part MP1.1, A1 (a), (b) and (c), A2 (a), (b) and (d) and part MP1.2, A1 (a), (b) and (c), A2 (a), (b) and (d). Non-compliance with this provision for a Dwelling house requires a concurrence agency response from Council.

**Notes:**

**General**

- Maximum building location envelopes shown are subject to future proposed easements and/or other underground services.

**Site Cover**

- Site cover (excluding eaves, sun shading devices, patios, balconies and other unenclosed structures) does not exceed that outlined in the Site Cover Table.

**Car Parking Spaces**

- Minimum of 2 onsite car parking spaces are provided per dwelling.

**Garages and Carports**

- Garage and carport openings shall be as per Garage and Carport Openings Table.

**Driveways**

- Driveway crossovers are located in accordance with this Plan of Development.
- Driveways do not include a reversing bay, manoeuvring area or visitor parking space(s) (other than tandem spaces) in the front setback.

**Waste**

- Each dwelling includes a bin storage area that:
  - is not visible from public areas or screened from public areas;
  - has a minimum area of 1.0m x 2.0m
  - if located within the garage, the area must be ventilated;
  - if located within the front setback, must be stored in a small enclosure.

**Casual Surveillance**

- Dwellings generally must address primary frontages with a minimum of a window and either a front door or pedestrian entrance. Dwellings on corner lots may have a front door addressing the secondary frontage but must still address the primary frontage with a window on each level.
- The building must have a window with an area of at least 1m² or multiple habitable room windows having a combined area of at least 2.5m² that face the street.

**Corner lots**

- For corner lots, the Primary Frontage shall be considered the narrow frontage addressing a road.

**Built to Boundary Walls**

- Built to boundary walls shall be as per Built to Boundary Walls Residential Uses Table, unless indicated otherwise on this Proposal Plan.

**Setbacks**

- Minimum setbacks shall be as per Plan of Development Setbacks Table.

PLAN REF: **7025 – 305**

Rev No: **D**

DATE: 20 FEBRUARY 2023

CLIENT: PEET

DRAWN BY: JC/NF

CHECKED BY: DG

Not to Scale @ A3

**RIVERBANK**  
**OVERALL STAGE 2**  
**PROPOSAL PLAN - SHEET 2**

**PEET**

**URBAN DESIGN**  
 Level 4 HQ South  
 520 Wickham Street  
 PO Box 1559  
 Fortitude Valley QLD 4006  
 T +61 7 3539 9500  
 W rpsgroup.com

**rps**

© COPYRIGHT PROTECTS THIS PLAN  
 Unauthorised reproduction or amendment not permitted. Please contact the author.